

- NOTES:
- REMOVE AND REPLACE APPROX. 83 SY OF EXISTING CONCRETE DRIVEWAY (NE) AND 40 SY (SW). MATCH ALL EXISTING ELEVATIONS AND GRADES. COMPACT TOP 12" OF SUBGRADE AND PLACE MINIMUM 6" THICK - 4000 PSI CONCRETE. JOINTS SHALL BE INSTALLED PER STANDARD CITY DETAIL. ON SW DRIVEWAY REMOVE AND REPLACE COMPLETE PANELS.
 - REMOVE APPROXIMATELY 71 SY OF EXISTING CONCRETE ISLAND. EXCAVATE EXISTING FOOTPRINT OF ISLAND AND COMPACT EXISTING SUBGRADE. REPLACE WITH ASPHALT REPAIR SECTION PER DETAIL TO MATCH ADJACENT PAVEMENT GRADES.
 - AREAS NOTED HAVE BROKEN ASPHALT. CONTRACTOR SHALL SAWCUT PAVEMENT TO A NEAT EDGE AND REMOVE ASPHALT AND STONE BASE. CONTRACTOR SHALL COMPACT EXISTING SUBGRADE AND REPLACE WITH ASPHALT REPAIR SECTION TO MATCH EXISTING GRADES. ADJACENT TO TWO EXISTING STORM STRUCTURES CONTRACTOR SHALL EXCAVATE DOWN TO EXPOSE THE PIPE CONNECTION TO INLET AND SEAL ANY VOIDS WITH NON-SHRINK GROUT. PLACE STRUCTURAL FILL AND COMPACT IN MAX. 10" LIFTS TO 98% MAXIMUM DENSITY (STD. PROCTOR). TOP 12" OF SUBGRADE SHALL BE COMPACTED TO 100% MAX. DENSITY (STD. PROCTOR). REMOVE EXISTING RAIL AND GROUT HOLES WITH NON-SHRINK GROUT TO PROVIDE A SMOOTH SURFACE.
 - CONTRACTOR SHALL PRESSURE WASH/SAND BLAST TO REMOVE EXISTING STRIPING ON EXISTING ASPHALT AND CONCRETE WITHOUT DAMAGING SURFACE.
 - CONTRACTOR SHALL THEN INSTALL A SEAL COAT ON EXISTING/ NEW ASPHALT (APPROX. 2515 SY) AS SHOWN ON SITE LAYOUT PLAN. DO NOT SEAL COAT CONCRETE AND PROTECT ADJACENT SURFACES FROM OVER SPRAY.
 - REMOVE EXISTING SIDEWALK AND REPLACE WITH TYPE "B" CURB RAMP PER DETAIL.
 - DEMOLISH EXISTING PAVEMENT AND INSTALL NEW CURB AND GUTTER AS SHOWN ON DWG. C2.0.
 - SECTION OF BUILDING INDICATED SHALL BE REMOVED. GRADE TO DRAIN AWAY FROM FOUNDATION AND TOWARDS NEW SIDEWALK (±6" DROP IN 14'). INSTALL SOD.
 - PRIOR TO ANY CLEARING, GRADING OR CONSTRUCTION ACTIVITY; TREE PROTECTION FENCING WILL BE INSTALLED AROUND PROTECTED TREES. NO CONSTRUCTION WORKERS, TOOLS, MATERIALS, OR VEHICLES ARE PERMITTED WITHIN THE TREE PROTECTION AREA. TREE PROTECTION MUST BE MAINTAINED DURING ALL PHASES OF PROJECT CONSTRUCTION.

2432 CAROLINA BEACH RD.
 PID# R06018-005-011-001
 EUDIE ROBERTS
 DEED BOOK 1279, PAGE 0944
 ZONED COMMERCIAL SERVICE

LEGEND


 DEMOLITION

City of WILMINGTON
 NORTH CAROLINA
 Public Services • Engineering Division
 APPROVED STORMWATER MANAGEMENT PLAN
 Date: _____ Permit # _____
 Signed: _____

Approved Construction Plan

Name: _____ Date: _____

Planning _____
 Public Utilities _____
 Traffic _____
 Fire _____



PRELIMINARY - NOT FOR CONSTRUCTION

THOMAS & HUTTON
 Engineering | Surveying | Planning | GIS | Consulting
 215 S. Kerr Avenue • Unit B
 Wilmington, NC 28403 • 910.332.3360
 www.thomasandhutton.com
 Savannah, GA | Brunswick, GA | Charleston, SC | Myrtle Beach, SC
 JOB #: 23264 DESIGNED: BDR | REVIEWED: APR/VD

WAFLE HOUSE
 SITE DEVELOPMENT PLANS
 for

WAFLE HOUSE
 UNIT # _____
 2448 CAROLINA BEACH ROAD, WILMINGTON, NORTH CAROLINA

| DATE | REVISION DESCRIPTION |
|----------|---|
| 09/06/13 | REVISED PER CITY OF WILMINGTON COMMENTS |
| 10/11/13 | REVISED PER CITY OF WILMINGTON COMMENTS |

PROJECT NAME:
WAFLE HOUSE
 UNIT # _____
 2448 CAROLINA BEACH ROAD
 LAND LOT XXX
 CITY OF WILMINGTON
 NEW HANOVER COUNTY, NC

SHEET TITLE:
DEMOLITION PLAN


PROJECT No. WAFXXX SHEET No. C1.0
 DATE: 06/22/13
 ISSUE NO. 1

North Carolina

 One Call Center
 Call Before You Dig
 "It's The Law"
 1-800-632-4949

WAFLE HOUSE, INC.
 APPROVALS

SIGNATURE _____ DATE _____
 SIGNATURE _____ DATE _____
 SIGNATURE _____ DATE _____
 SIGNATURE _____ DATE _____



- NOTES:**
- ACCESSIBLE ROUTE - EXTERIOR:**
 - MINIMUM CLEAR WIDTH IS 5'. IF ACCESSIBLE ROUTE HAS LESS THAN 5' CLEAR WIDTH, THEN PARKING SPACES AT LEAST 5'x8' SHALL BE LOCATED EVERY 200' OR LESS INTERSECTING SIDEWALKS MEET THIS REQUIREMENT. LONGITUDINAL (RUNNING) SLOPE MAY NOT EXCEED 5% UNLESS RAMP IS INSTALLED (RAMP'S MAY NOT EXCEED 8.33%). CROSS SLOPE MAY NOT EXCEED 2%. GAPS IN ROUTE MAY NOT EXCEED 1/2" IN WIDTH.
 - FINISHED SURFACE HEIGHT DIFFERENCE REQUIREMENTS:**
 - A. 0 TO 1/4" - NO REQUIREMENTS.
 - B. 1/4" TO 1/2" - BEVEL WITH 1:2 SLOPE.
 - C. LARGER THAN 1/2" - CONFORM TO REQUIREMENTS FOR RAMP.
 - RAMP:**
 - MAX RAMP SLOPE 8.33% (2:24).
 - RAMP'S STEEPER THAN 8.33% ARE NOT ACCEPTABLE.
 - MAX RISE FOR ANY RAMP RUN IS 30" (AT 8.33% SLOPE, MAXIMUM RUN OF RAMP IS 30').
 - MAX CROSS SLOPE OF RAMP 2% (50).
 - LANDINGS:**
 - RAMP'S SHALL HAVE LEVEL LANDINGS AT BOTTOM AND TOP OF EACH RAMP.
 - LANDING SHALL BE AT LEAST AS WIDE AS RAMP LEADING TO IT.
 - LANDING LENGTH SHALL BE MINIMUM 5' CLEAR.
 - IF RAMP'S CHANGE DIRECTION AT LANDING, MINIMUM LANDING SIZE SHALL BE 6'x6'.
 - ALL LANDINGS ARE TO BE NO MORE THAN 2% SLOPE IN ANY DIRECTION.
 - CURB RAMP:**
 - MAX SLOPE OF CURB RAMP 8.33%.
 - MAX SLOPE OF SIDE FLARES 10%.
 - MAX SLOPE OF ADJOINING GUTTERS, ROAD SURFACE, OR ACCESSIBLE ROUTE 5%.
 - MIN WIDTH 50" (NOT INCLUDING SIDE FLARES).
 - DETECTABLE WARNING IS REQUIRED ON CURB RAMP'S AT TRAFFIC AISLES, AND SHALL BE 24" MINIMUM IN THE DIRECTION OF TRAVEL AND EXTEND THE FULL WIDTH OF THE CURB RAMP OR FLUSH SURFACE. DETECTABLE WARNING SHALL BE LOCATED SO THE EDGE NEAREST THE CURB LINE IS 6" TO 8" FROM THE CURB LINE.
 - PAVEMENT MARKINGS:**
 - AS REQUIRED BY LOCAL JURISDICTIONAL AUTHORITY (RECOMMENDED CROSSWALK MARKING TO DESIGNATE ACCESSIBLE PEDESTRIAN ROUTE)

- HANDICAP PARKING SPACES**
 - MINIMUM 6' WIDE ACCESSIBLE PARKING SPACE
 - MINIMUM 6' WIDE ACCESS AISLE AT STANDARD SPACES
 - MINIMUM 8' WIDE ACCESS AISLE AT VAN ACCESSIBLE SPACES
 - MAXIMUM 2% (50) SLOPE IN ANY DIRECTION
 - SIGNAGE**
 - ACCESSIBLE PARKING SPACES SHALL BE DESIGNATED AS RESERVED BY A SIGN SHOWING THE SYMBOL OF ACCESSIBILITY. VAN ACCESSIBLE SPACES SHALL HAVE AN ADDITIONAL SIGN "VAN-ACCESSIBLE" MOUNTED BELOW THE SYMBOL. SUCH SIGNS SHALL BE LOCATED SO THEY CANNOT BE OBTURED BY A VEHICLE PARKED IN THE SPACE (60" ABOVE GRADE UNLESS OTHER HEIGHT REQUIRED BY LOCAL JURISDICTION).
 - ACCESSIBLE ROUTES**
 - MUST COMPLY WITH ADA, THE FAIR HOUSING ACT AND ICE/ANSI A117.1-2003.
- ADDITIONAL NOTES:**
- ALL STRIPING SHALL BE 4" WIDE, WHITE UNLESS OTHERWISE NOTED.
 - WHERE SHOWN ON PLANS AREAS SHALL BE DESIGNATED AS NO PARKING BY INSTALLATION OF 4" WIDE WHITE STRIPES AT MAXIMUM 24" CENTERS.
 - CONTRACTOR SHALL PROVIDE AND INSTALL 12 WHEELSTOPS ALONG NORTHERN SIDE OF THE BUILDING. FACE OF WHEELSTOPS SHALL BE 2'-6" FROM FACE OF EXISTING CONCRETE CURB OR ITS PROJECTION.
 - ALL PROPOSED VEGETATION WITHIN SITE DISTANCE TRIANGLES SHALL NOT INTERFERE WITH CLEAR VISUAL SIGHT LINES FROM 30" TO 10'.
 - IN AREAS NOTED PITCH CURB AND MATCH ASPHALT ELEVATION WITH GUTTER EDGE. IF PARKING LOT IS OVERLAIN, SET NEW GUTTER ELEVATIONS AS REQUIRED TO MATCH NEW PAVEMENT SURFACE.
 - TAPER CURB DOWN OVER FINAL 3" TO MATCH THE ELEVATION OF SIDEWALK.

LEGEND

- ACCESSIBLE ROUTE
- ASPHALT SEAL COAT
- CONCRETE P.V.M.T. / SIDEWALK
- CURB AND GUTTER
- FLOW DIRECTION


T&H CONTROL POINT
 PK NAIL SET IN PAVEMENT
 N: 163,153.79
 E: 2,321,824.42
 ELEV.: 26.19 (NAVD88)

GRAPHIC SCALE
 (IN FEET)
 1 inch = 10 ft.

City of WILMINGTON
 NORTH CAROLINA
 Public Services • Engineering Division
 APPROVED STORMWATER MANAGEMENT PLAN
 Date: _____ Permit # _____
 Signed: _____

Approved Construction Plan
 Name: _____ Date: _____

Planning _____
 Public Utilities _____
 Traffic _____
 Fire _____



THOMAS & HUTTON
 Engineering | Surveying | Planning | GIS | Consulting
 215 S. Kerr Avenue • Unit B
 Wilmington, NC 28403 • 910.332.3360
 www.thomasandhutton.com
 Savannah, GA | Brunswick, GA | Charleston, SC | Myrtle Beach, SC
 JOB # 23264 DESIGNED: BDR REVIEWED: APR/VD-JDR

SITE DEVELOPMENT PLANS
 for
WAFFLE HOUSE
 UNIT # _____
 2448 CAROLINA BEACH ROAD, WILMINGTON, NORTH CAROLINA


| DATE | REVISION DESCRIPTION |
|----------|---|
| 09/05/13 | REVISED PER CITY OF WILMINGTON COMMENTS |
| 10/21/13 | CORRECTED SITE TRIANGLE LOCATIONS |
| 10/23/13 | REVISED PER CITY OF WILMINGTON COMMENTS |

PROJECT NAME:
 UNIT # _____
 2448 CAROLINA BEACH ROAD
 LAND LOT XXX
 CITY OF WILMINGTON
 NEW HANOVER COUNTY, NC

SHEET TITLE:
LAYOUT PLAN

PROJECT No.: WAFXXX
SHEET No.: C2.0











DATE: 06/22/13
ISSUE No.: 1



North Carolina
 One Call Center
 Call Before You Dig
 "It's The Law"
 1-800-632-4949

WAFFLE HOUSE, INC.
 APPROVALS

| | |
|-----------|------|
| SIGNATURE | DATE |



PRELIMINARY - NOT FOR CONSTRUCTION

THOMAS & HUTTON
Engineering | Surveying | Planning | GIS | Consulting

215 S. Kerr Avenue • Unit B
Wilmington, NC 28403 • 910.332.3360
www.thomasonhutton.com

DESIGNED: BDR REVIEWED: PBJ/SD

SITE DEVELOPMENT PLANS
for
WAFFLE HOUSE

UNIT # _____
2448 CAROLINA BEACH ROAD, WILMINGTON NORTH CAROLINA

REVISION DESCRIPTION
REVISED PER CITY OF WILMINGTON COMMENTS

DATE: 09/06/13

PROJECT NAME:
WAFFLE HOUSE

UNIT # _____

2448 CAROLINA BEACH ROAD
LAND LOT XXX
CITY OF WILMINGTON
NEW HANOVER COUNTY, NC

SHEET TITLE:
DETAILS

PROJECT No. SHEET No.
WAFXXX C3.1

DATE:
06/22/13
ISSUE No. 1

CITY OF WILMINGTON NORTH CAROLINA
Public Services • Engineering Division
APPROVED STORMWATER MANAGEMENT PLAN

Date: _____ Permit # _____
Signed: _____


Approved Construction Plan
Name: _____ Date: _____

Planning _____
Public Utilities _____
Traffic _____
Fire _____

North Carolina
One Call Center
Call Before You Dig
"It's The Law"
1-800-632-4949

WAFFLE HOUSE, INC.
APPROVALS

SIGNATURE _____ DATE _____
SIGNATURE _____ DATE _____
SIGNATURE _____ DATE _____
SIGNATURE _____ DATE _____



Approved Construction Plan

Name _____ Date _____

Planning _____

Public Utilities _____

Traffic _____

Fire _____

- PLANTING LEGEND**
- TREES**
- + Trident Maple
 - Acer buergerianum
 - 8' Ht. min 2.5" Caliper Qty: 10
- SHRUBS**
- ⊗ Pink Muhly Grass
 - ⊗ Muhlenbergia capillaris
 - 3 gal 12" Ht. x 12" Sp. Qty: 30
 - ⊕ Carissa Holly
 - ⊕ Ilex cornuta 'Carissa'
 - 3 gal 15" Ht. x 15" Sp. Qty: 12
 - ⊗ Pittosporum
 - ⊗ Pittosporum tobira
 - 5 gal 24" Ht. x 24" Sp. Qty: 44
 - ⊕ Wax Myrtle
 - ⊕ Myrica cerifera
 - 3 gal 36" Ht. x 36" sp. Qty: 6
 - ⊗ Dwarf japanese plum yew
 - ⊗ Cephalotaxus harringtonia "Nana"
 - 3 gal 36" Ht. x 36" sp. Qty: 25
 - ⊗ Dwarf Pittosporum
 - ⊗ Pittosporum tobira 'Wheeler's dwarf'
 - 3 gal 12" Ht. x 12" Sp. Qty: 8
 - ⊕ Dwarf skypencil Holly
 - ⊕ Ilex crenata 'dwarf sky pencil'
 - 3 gal 36" Ht. x 12" Sp. Qty: 22
- GROUNDCOVERS AND MULCHES**
- ⊞ Brown Brick Chip Mulch
 - 3" deep @ Qty: 320 sf
 - ⊞ Dark Hardwood Mulch
 - 3" deep @ Qty: 3535 sf
 - ⊞ Bermuda Grass Sod
 - Qty: ±4500 sf

- ISLAND PLANTING & STREET YARD**
- 170 SF. WITH (1) TREE, (9) SHRUBS & MULCH
- SCREEN**
- (22) 3'HGT. SHRUBS

FOUNDATION PLANTING NORTH SIDE OF BUILDING

1386 S.F. BLDG FACE x 12% = 166 S.F. REQUIRED

68 S.F. FOUNDATION PLANTING PROVIDED DUE TO EXISTING PAVEMENT

FOUNDATION PLANTING EAST SIDE OF BUILDING

612 S.F. BLDG FACE x 12% = 74 S.F. REQUIRED

477 S.F. FOUNDATION PLANTING PROVIDED

FOUNDATION PLANTING WEST SIDE OF BUILDING

NO PLANTING DUE TO EXISTING PAVEMENT

FOUNDATION PLANTING SOUTH SIDE OF BUILDING

NO PLANTING DUE TO EXISTING DRIVE-UP SERVICE LANE

ISLAND PLANTING

625 SF. WITH (1) TREE, 5 SHRUBS, GRASS, AND MULCH

ISLAND PLANTING

200 SF. WITH (1) TREE, (11) SHRUBS, & MULCH

ISLAND PLANTING

920 SF. WITH (1) TREE, GRASS AND MULCH

PERIMETER LANDSCAPE

EXISTING JUNIPERS TO REMAIN ON SLOPE BETWEEN EXISTING PARKING LOTS

PERIMETER BUFFER

EXISTING BUFFER AND FENCE TO REMAIN - VEGETATION TO BE LIMBED UP

FENCE TO SCREEN DUMPSTERS

STREET YARD LANDSCAPING AND PARKING AREA SCREENING

3668 S.F. OF STREET YARD AREA

1 TREE AND 6 SHRUBS / 600 S.F. (IN CITY R.O.W.) = 6 TREES AND 36 SHRUBS REQUIRED

6 TREES AND 36 SHRUBS PROVIDED

Approved Construction Plan

North Carolina

One Call Center

Call Before You Dig

"It's The Law"

1-800-632-4949

WAFFLE HOUSE, INC.

APPROVALS

SIGNATURE _____ DATE _____

SIGNATURE _____ DATE _____

SIGNATURE _____ DATE _____

SIGNATURE _____ DATE _____

SageDesign

SageDesign PLLC

Sara Burroughs, RLA


228 North Front Street

Suite 202D

Wilmington, NC 28401

Ph. (910) 232-3878

sara@sagedesign.us



THOMAS & HUTTON

Engineering | Surveying | Planning | GIS | Consulting

2155 S. Kerr Avenue • Unit B

Wilmington, NC 28403 • 910.332.3340

www.thomasandhutton.com

Savannah, GA | Brunswick, GA | Charleston, SC | Myrtle Beach, SC

JOB # 23284 - DESIGNED: BOR - REVIEWED/APPROD: JOR

WAFLE HOUSE

for

SITE DEVELOPMENT PLANS

UNIT # _____

2448 CAROLINA BEACH ROAD, WILMINGTON, NORTH CAROLINA

| REVISION DESCRIPTION | DATE |
|---|----------|
| REVISED - PER CITY OF WILMINGTON COMMENTS | 09/08/13 |
| REVISED - CITY COMMENTS & CORRECTED SITE TRIANGLE | 10/11/13 |
| REVISED - CITY COMMENTS & CORRECTED SITE TRIANGLE | 10/23/13 |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

PROJECT NAME:

UNIT # _____

2448 CAROLINA BEACH ROAD LAND LOT XXX

CITY OF WILMINGTON

NEW HANOVER COUNTY, NC

SHEET TITLE:


LANDSCAPE PLAN

PROJECT No. WAFXXX


SHEET No. L1.0

DATE: 06/22/13

ISSUE NO. 1



A SINGLE STEM TREE INSTALLATION DETAIL
SCALE: NTS



B SHRUB INSTALLATION DETAIL
SCALE: NTS

| Approved Construction Plan | |
|----------------------------|------|
| Name | Date |
| Planning | |
| Public Utilities | |
| Traffic | |
| Fire | |

PLANT MATERIAL NOTES

- ALL PLANT MATERIAL SHALL CONFORM TO THE MOST CURRENT STANDARDS ESTABLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMAN.
- CONTAINERIZED PLANTS SHALL HAVE A ROOT SYSTEM SUFFICIENT ENOUGH IN DEVELOPMENT TO HOLD THE SOIL INTACT WHEN REMOVED FROM THE CONTAINER. THE ROOT SYSTEM SHALL NOT BE ROOT BOUND, A CONDITION WHERE THE ROOT SYSTEM IS DENSE IN MASS, EXCESSIVELY INTERTWINED, AND HAS ESTABLISHED A CIRCULAR GROWTH PATTERN.
- ALL PLANTS SHALL BE FRESHLY DUG, SOUND, HEALTHY, VIGOROUS, WELL-ROOTED PLANTS AND ESTABLISHED IN THE CONTAINER IN WHICH THEY ARE SOLD. THE PLANTS SHALL HAVE TOPS WHICH ARE GOOD QUALITY AND ARE IN A HEALTHY GROWING CONDITION.
- PLANTS SHALL NOT BE PRUNED PRIOR TO DELIVERY UNLESS APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO SHIPMENT.
- ALL TREE PITS, SHRUB BEDS AND PREPARED PLANTING BEDS ARE TO BE COMPLETELY EXCAVATED IN ACCORDANCE WITH THE PLANTING DETAILS.
- TOPSOIL AMENDMENTS REQUIRED FOR SOIL MIXES SHALL BE PROVIDED BY CONTRACTOR AND APPROVED BY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION. CONTRACTOR MUST LOAD, HAUL, MIX AND SPREAD ALL TOPSOIL AND OTHER SOIL ADDITIVES AS REQUIRED ON SITE.
- CONTRACTOR SHALL VERIFY AND/OR AMEND ALL PLANTING SOILS TO ENSURE PROPER SUITABILITY INCLUDING STATE RECOMMENDED QUANTITIES OF NITROGEN, PHOSPHORUS, AND POTASH NUTRIENTS AND SOIL AMENDMENTS TO BE ADDED TO PRODUCE QUALITY PLANTING SOIL FOR ALL PLANT MATERIAL TO SURVIVE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT ALL PLANTING PITS PERCOLATE PROPERLY PRIOR TO PLANTING INSTALLATION.
- SHRUBS, BULBS, AND GROUNDCOVERS SHALL BE TRIANGULARLY SPACED AT SPACING SHOWN ON PLANTING PLANS AND/OR IN THE PLANT SCHEDULE.
- THE CONTRACTOR SHALL THE VERIFY EXTENT OF SEEDING OR SOD AREA WITH OWNER REPRESENTATIVE AND LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.

TREE INSTALLATION NOTES

- TREES SUPPLIED MUST HAVE BEEN PROPERLY PLANTED AND GROWN IN THE NURSERY. THE ROOT CROWN (ALSO CALLED THE TRUNK FLARE) SHALL BE EVIDENT NEAR THE TOP OF THE GROUND. ANY EXCESS SOIL, UP TO 3 INCHES COVERING THE CROWN WILL HAVE TO BE REMOVED CAREFULLY BY HAND, IN ORDER TO PREVENT ROOT SCRAPES. THE TREE IS THEN TO BE PLANTED WITH THE ROOT CROWN IN PROPER RELATION TO THE SURROUNDING GRADE. ANY TREES WITH MORE THAN 3 INCHES OF SOIL ON TOP OF THE ROOT CROWN WILL BE REJECTED. THE NURSERY OWNERS MAY DIG OVERSIZE BALLS AND REMOVE THE SOIL IN ORDER FOR THE ROOT SYSTEM DIAMETER (WHICH IS THE REQUIRED ROOT BALL DIAMETER) TO MEET THE SPECIFICATION FOR THE TRUNK CALIPER REQUIRED.
- BALL AND BURLAPPED (B&B) PLANTS MUST HAVE FIRM, NATURAL BALLS OF EARTH, OF DIAMETER NOT LESS THAN RECOMMENDED IN THE "TREE AND SHRUB TRANSPLANTING MANUAL", AND BE OF SUFFICIENT DEPTH TO INCLUDE THE FIBROUS AND FEEDING ROOTS. PLANTS MOVED WITH A BALL WILL NOT BE ACCEPTED IF THE BALL IS DRY, CRACKED OR BROKEN BEFORE OR DURING PLANTING OPERATIONS.
- REMOVE ALL TREATED OR PLASTIC-COATED BURLAP, STRAPPING, WIRE OR NYLON TWINE FROM ROOT BALL. AFTER SETTING IN HOLE, CUT AWAY 2/3 OF WIRE BASKET, IF ANY, AND TOP 1/3 OF BURLAP.
- SOAK ROOT BALL AND PIT IMMEDIATELY AFTER INSTALLATION.
- CONSTRUCT 4" HIGH SAUCER (WATER BERM) OUTSIDE OF PLANT MIX BACK FILL.
- WHERE TREES ARE PLANTED IN ROWS, THEY SHALL BE UNIFORM IN SIZE AND SHAPE.
- NO EXISTING TREES SHALL BE REMOVED WITHOUT WRITTEN AUTHORIZATION FROM THE OWNER REPRESENTATIVE EXCEPT WHERE NOTED ON PLANS. NO GRUBBING SHALL OCCUR WITHIN EXISTING TREE AREAS.
- THE CONTRACTOR SHALL STAKE THE LOCATIONS OF ALL PROPOSED TREES AND OBTAIN APPROVAL FROM THE LANDSCAPE ARCHITECT AND OWNER REPRESENTATIVE PRIOR TO INSTALLATION.
- ALL TREES SHALL BE STAKED AT TIME OF INSTALLATION IN ACCORDANCE WITH PLANTING DETAILS.
- THE CONTRACTOR SHALL ENSURE THAT TREES REMAIN VERTICAL AND UPRIGHT FOR THE DURATION OF THE GUARANTEE PERIOD.
- STAKES FOR TREE SUPPORT SHALL BE CONSTRUCTED OF 2"x2" x18" UNTREATED PINE. GUYING FABRIC SHALL BE "ARBOR TAPE", AS MANUFACTURED BY NEPTCO, PAWTUCKET, RI. (401) 722-5500 (OR APPROVED EQUAL). COLOR SHALL BE OLIVE DRAB.

SHRUB INSTALLATION NOTES

- CUT ROOTS AS NECESSARY IN CONTAINERIZED PLANTS THAT ARE POT BOUND. REJECT PLANTS THAT HAVE GIRDLED ROOT OR ARE BOUND.
- INSTALL TOP OF PLANT BALL 2" ABOVE ADJACENT GRADE.
- TAMP PLANT SOIL MIX FIRMLY IN 8" LIFTS AROUND PLANT BALL.
- SOAK PLANT BALL AND PIT IMMEDIATELY AFTER INSTALLATION.
- PURSUANT TO LDC 18-483 A 3' BUFFER SHALL BE PROVIDED IN FRONT OF SPACES 36 AND 37; IF PROPOSED EVERGREEN SCREEN DOES NOT SURVIVE, OWNER SHALL PROVIDE A 3' HGT. 'GREEN SCREEN' WITH SCREEN AND EVERGREEN PLANT MATERIAL TO SATISFY THIS CODE REQUIREMENT.

SageDesign
SageDesign PLLC
Sara Burroughs, RLA
228 North Front Street
Suite 202D
Wilmington, NC 28401
Ph. (910) 232-3878
sara@sagedesign.us



| WAFFLE HOUSE, INC. | |
|--------------------|------|
| APPROVALS | |
| SIGNATURE | DATE |



THOMAS & HUTTON
Engineering | Surveying | Planning | GIS | Consulting
215 S. Kerr Avenue • Unit B
Wilmington, NC 28403 • 910.332.3360
www.thomasandhutton.com
Savannah, GA | Brunswick, GA | Charleston, SC | Myrtle Beach, SC
JOB # 23284

SITE DEVELOPMENT PLANS
for
WAFFLE HOUSE
UNIT # _____
2448 CAROLINA BEACH ROAD, WILMINGTON, NORTH CAROLINA

| DATE | REVISION DESCRIPTION |
|----------|---|
| 09/06/13 | REVISED PER CITY OF WILMINGTON COMMENTS |
| 10/11/13 | REVISED - CITY COMMENTS & CORRECTED SITE TRIANGLE |

PROJECT NAME: _____

UNIT # _____

2448 CAROLINA BEACH ROAD
LAND LOT XXX
CITY OF WILMINGTON
NEW HANOVER COUNTY, NC

SHEET TITLE:
LANDSCAPE DETAILS

PROJECT No. **WAFXXX** SHEET No. **L2.0**

DATE: 06/22/13
ISSUE NO. 1