


1"=200'



VICINITY MAP (NTS)



SITE DEVELOPMENT PLAN FOR BELLE MEADE APARTMENTS WILMINGTON, NORTH CAROLINA DECEMBER 2014



IN	idex of she
SHT C-0	COVER SHEET
SHT C-1	GENERAL NOTES
SHT C-2	EXISTING CONDITIC
SHT C-2.1	SITE INVENTORY P
SHT C-3.1	OVERALL SITE PLA
SHT C-3.2	SITE PLAN
SHT C-4	UTILITY PLAN
SHT C-5.1	OVERALL DRAINAGE
SHT C-5.2	GRADING, DRAINAG SEDIMENT CONTRO
SHT C-6	EXISTING WET DET
SHT C-7	STANDARD DETAILS
SHT C-8	STANDARD DETAILS
SHT C-9	STANDARD DETAILS
SHT L—1	LANDSCAPE PLAN
	Public Services APPROVED STORM
	Date:
	Signed:
	Approved Co
	Planning
	Traffic
	Fire

SITE DATA TABLE
GENERAL NOTES:
DEITERNIE NEW HANOVER COUNTY PARCEL NOS.: PIN 312408.99.9928.000 / PID R07000-004-004-000 PIN 313517.00.5557.000 / PID R07100-003-005-000 PIN 313517.00.6444.000 / PID R07100-003-007-000 PIN 313517.00.7245.000 / PID R07100-003-008-000
SITE ADDRESS: 4703 CAROLINA BEACH ROAD
2. TOTAL TRACT AREA: 10.93 AC.± (476,251 S.F.)
3. ZONING DISTRICT: B-1 (CDMU) REQ'D. PROV'D SETBACKS - 20' FRONT SETBACKS - 20' FRONT 35' REAR* 35' REAR* 10' SIDE 10' SIDE * (ADJACENT TO RESIDENTIAL ZONED PROPERTY)
4. CAMA LAND CLASSIFICATION: URBAN
5. THERE ARE NO WETLANDS LOCATED ON THIS PROPERTY.
6. THIS PROPERTY IS <u>NOT</u> WITHIN A SPECIAL FLOOD HAZARD ZONE PER FEMA FLOOD INSURANCE RATE MAP #3720313500J, REVISED DATE 04/03/06
DEVELOPMENT DATA:
TOTAL TRACT AREA = 10.93 AC.
DEVELOPMENT AREA - 10.93 AC. PROPOSED DENSITY 228 UNITS - 20.86 UNITS/AC
BUILDING COVERAGE – 105,800 S.F. (22.2%) (7–3 STORY) @ 80.5' X 178.33' + BATHHOUSE + MAINTENANCE BLDG + COMMERCIAL SPACE
TOTAL GROSS FLOOR AREA - 310,284 S.F. GFA COMMERCIAL = 3,800 S.F. \pm APARTMENTS = <u>306,484 S.F.\pm</u> 310,284 SF (65.2%)
TOTAL BEDROOMS - 372 84 X 1 BR = 84 BR 144 X 2 BR = 288 BR
MAX. BLDG. HGT. – 3–STORY / 35' MEAN ROOF PROPOSED – 35' MEAN ROOF
PARKING - 84 - 1 BR UNITS X 1.5 MIN. SP./UNIT = 126 144 - 2 BR UNITS X 2.0 MIN. SP./UNIT = 288 3,800 SF COMMERCIAL - 1 SP./400 SF = 10 MINIMUM TOTAL SPACES REQ'D. = 424 84 - 1 BR UNITS X 2.5 MAX. SP./UNIT = 210 144 - 2 BR UNITS X 2.5 MAX. SP./UNIT = 360 3,800 SF COMMERCIAL - 1 SP./200 SF = 19 MAXIMUM TOTAL SPACES PREMIT'D. = 589 ** 437 TOTAL SPACES PREMIT'D. = 589 ** 437 TOTAL SPACES PROV'D. (12 H/C) ** PER ADA REGS FOR PARKING FACILITY WITH 401-500 SPACES 9 H/C SPACES REQUIRED BIKE PARKING REQ'D = 5 MIN/100 SPACES BIKE PARKING PROV'D = 22
NEW IMPERVIOUS SURFACES -
ROOFTOP - 105,800 S.F. ASPHALT PAVEMENT - 164,547 S.F. CONCRETE - 23,485 S.F. NEW TOTAL - 293,832 S.F. (61.7%)
UTILITY CAPACITY REQUESTS: PROPOSED SEWER CAPACITY – 228 UNITS @ 240 GPD/BR = 54,720 GPD PROPOSED WATER CAPACITY – 228 UNITS @ 400 GPD/BR = 91,200 GPD
For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.
NOTE: ALL DESIGN AND CONSTRUCTION SHALL BE IN CONFORMANCE WITH THE CITY OF WILMINGTON LAND DEVELOPMENT CODE, TECHNICAL STANDARDS MANUAL & THE STATE OF NORTH CAROLINA

COORDINATION NOTES

1. THE CONTRACTOR IS REQUIRED TO OBTAIN ANY/ALL PERMITS REQUIRED FOR CONSTRUCTION OF THESE PI ANS

2. ALL WORK IS TO BE IN ACCORDANCE WITH CITY OF WILMINGTON, NEW HANOVER COUNTY, THE CAPE FEAR PUBLIC UTILITY AUTHORITY (CFPUA) AND THE STATE OF NORTH CAROLINA. 3 THE CONTRACTOR IS TO ESTABLISH AND CHECK ALL HORIZONTAL AND VERTICAL CONTROLS TO BE USED WITH THE PROJECT. IN ADDITION, THE CONTRACTOR IS TO COMPUTE THE LAYOUT OF THE ENTIRE SITE PLAN IN ADVANCE OF BEGINNING ANY WORK ASSOCIATED WITH THE SUBJECT PLANS. CONTRACTOR SHALL EMPLOY A PROFESSIONAL SURVEYOR TO PERFORM SITE IMPROVEMENT STAKEOUT(S).

4. ANYTIME WORK IS PERFORMED OFF-SITE OR WITHIN AN EXISTING EASEMENT, THE CONTRACTOR IS TO NOTIFY THE HOLDER OF SAID EASEMENT AS TO THE NATURE OF PROPOSED WORK, AND TO FOLLOW ANY GUIDELINES OR STANDARDS WHICH ARE ASSOCIATED WITH OR REFERENCED IN THE RECORDED EASEMENT.

GENERAL NOTES

- 1. EXISTING TOPOGRAPHY, BOUNDARY AND UTILITIES, HAVE BEEN PREPARED BY FIELD SURVEY BY MICHAEL UNDERWOOD & ASSOCIATES, PA., PREVIOUSLY APPROVED PLANS AND OTHER AVAILABLE INFORMATION.
- . REASONABLE CARE HAS BEEN EXERCISED IN SHOWING THE LOCATION OF EXISTING UTILITIES ON THE PLANS. THE EXACT LOCATION OF ALL EXISTING UTILITIES IS NOT KNOWN IN ALL CASES. THE CONTRACTOR SHALL EXPLORE THE AREA AHEAD OF DITCHING OPERATIONS BY OBSERVATIONS, ELECTRONIC DEVICES, HAND DIGGING AND BY PERSONAL CONTACT WITH THE UTILITY COMPANIES. IN ORDER TO LOCATE EXISTING UTILITIES IN ADVANCE OF TRENCHING OPERATIONS SO AS TO ELIMINATE OR MINIMIZE DAMAGE TO EXISTING UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS RESULTING FROM ANY DAMAGE TO THE EXISTING UTILITY LINES INCLUDING LOSS OF UTILITY REVENUES. CONTRACTOR SHALL ARRANGE FOR TEMPORARY SUPPORT OF EXISTING UTILITIES, SUCH AS POLES, CONDUITS, FIBER OPTIC CABLES, TELEPHONE CABLES, WATER LINES, ETC ...
- 3. CONTRACTOR SHALL COMPLY WITH THE LATEST REVISIONS AND INTERPRETATIONS OF THE DEPARTMENT OF LABOR SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION PROMULGATED UNDER THE OCCUPATIONAL SAFETY AND HEALTH ACT.
- 4. CONTRACTOR SHALL PLAN AND CONSTRUCT WORK SO AS TO CAUSE MINIMUM INCONVENIENCE TO THE OWNER AND THE PUBLIC. THE CONTRACTOR SHALL PROVIDE, ERECT AND MAINTAIN AT ALL TIMES DURING THE PROGRESS OR TEMPORARY SUSPENSION OF WORK, SUITABLE BARRIERS, FENCES, SIGNS OR OTHER ADEQUATE PROTECTION, INCLUDING FLAGMEN AND WATCHMEN AS NECESSARY TO INSURE THE SAFETY OF THE PUBLIC AS WELL AS THOSE ENGAGED IN THE CONSTRUCTION WORK. CONSTRUCTION SIGNING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF "CONSTRUCTION AND MAINTENANCE OPERATIONS SUPPLEMENT TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" BY THE DOT.
- 5. ALL MATERIAL CLEARED OR DEMOLISHED BY THE CONTRACTOR IN ORDER TO CONSTRUCT THE WORK SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE PROPERLY DISPOSED OF OFF-SITE.
- 6. ALL WORK BY THE CONTRACTOR SHALL BE WARRANTED BY THE CONTRACTOR FOR A PERIOD OF ONE YEAR AFTER THE OWNER ACCEPTS THE WORK.
- 7. CONTRACTOR SHALL CALL THE NORTH CAROLINA ONE-CALL CENTER AT 1 (800) 632-4949 AND ALLOW THE CENTER TO LOCATE EXISTING UTILITIES BEFORE DIGGING.
- 8. CONTRACTOR SHALL REMOVE ASPHALT, AGGREGATE BASE COURSE, AND CONCRETE CURB & GUTTER WITHIN LIMITS OF DEMOLITION AS SHOWN ON PLAN.

DEMOLITION NOTES

- 1. CONTRACTOR TO COORDINATE WITH THE OWNER TO PROPERLY MAINTAIN OR RELOCATE EXISTING SERVICE CONNECTIONS WHEN NECESSARY
- 2. CONTRACTOR IS TO WALK THE SITE AND BECOME FAMILIAR WITH THE SCOPE OF DEMOLITION REQUIRED. ALL DEMOLITION WORK REQUIRED TO CONSTRUCT NEW SITE IMPROVEMENTS WILL BE PERFORMED BY THE CONTRACTOR AND WILL BE UNCLASSIFIED EXCAVATION.
- DEMOLITION SHALL INCLUDE BUT IS NOT LIMITED TO THE EXCAVATION, HAULING AND OFFSITE DISPOSAL OF CONCRETE PADS, CONCRETE DITCHES, FOUNDATIONS, SLABS, STEPS, AND STRUCTURES: ABANDONED UTILITIES, BUILDINGS, PAVEMENTS AND ALL MATERIALS CLEARED AND STRIPPED TO THE EXTENT NECESSARY AS DIRECTED BY THE SOILS ENGINEER FOR THE INSTALLATION OF THE NEW IMPROVEMENTS AND WITHIN THE LIMITS OF CLEARING AND GRADING AND AS SHOWN ON THESE PLANS
- THE CONTRACTOR SHALL PROTECT ALL ADJACENT PROPERTY, STRUCTURES AND UTILITIES ON THE PROPERTY NOT TO BE DEMOLISHED. DAMAGE TO PROPERTIES OF OTHERS DUE TO THE CONTRACTOR'S ACTIVITIES SHALL BE REPLACED IN KIND BY THE CONTRACTOR AT NO COST TO
- 5. ELECTRIC, TELEPHONE, SANITARY SEWER, WATER AND STORM SEWER UTILITIES THAT SERVICE OFF-SITE PROPERTIES SHALL BE MAINTAINED DURING THE CONSTRUCTION PROCESS BY THE CONTRACTOR
- 6. EXISTING UTILITIES NOT INTENDED FOR DEMOLITION SHALL BE MAINTAINED, PROTECTED AND UNDISTURBED DURING DEMOLITION
- 7. ALL EXISTING IMPROVEMENTS INDICATED OR REQUIRED TO BE DEMOLISHED SHALL
- INCLUDE REMOVAL FROM THE PROPERTY AND PROPER DISPOSAL.
- 8. CONTRACTOR SHALL COORDINATE RELOCATION OF ALL EXISTING OVER HEAD AND UNDERGROUND UTILITIES INCLUDING CABLE, GAS, TELEPHONE AND ELECTRIC AND ANY OTHER UTILITIES THROUGH THE SITE WITH THE RESPECTIVE COMPANIES.
- 9. PROVIDE SMOOTH SAW CUT OF EXISTING PAVEMENTS, CURBS AND GUTTERS AND SIDEWALKS TO BE DEMOLISHED.
- 10. ALL DEMOLITION WORK SHALL BE DONE IN STRICT ACCORDANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS AS WELL AS OSHA REGULATIONS.
- INFORMATION CONCERNING UNDERGROUND UTILITIES WAS OBTAINED FROM AVAILABLE RECORDS, BUT THE THE CONTRACTOR MUST DETERMINE THE EXACT LOCATION AND ELEVATIONS OF THE MAINS BY DIGGING TEST PITS BY HAND.

EROSION AND SEDIMENT CONTROL NOTES

GENERAL NOTES:

- 1. CLEAR AND REMOVE FROM SITE ALL TREES, ROOTS, ROOT MAT, ETC. FROM THE AREA WITHIN DESIGNATED CLEARING LIMITS.
- 2. PLANT GRASS OVER ALL GRADED AREAS AS SHOWN IN THE TABLE ON THIS SHEET OF CEASE OF ANY GRADING ACTIVITY.
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING AND RESTORING TO PRE-CONSTRUCTION CONDITIONS ANY AREAS OUTSIDE THE PROJECT LIMITS THAT MAY INADVERTENTLY BE DAMAGED DUE TO THE FAILURE OF THE EROSION MEASURES
- 4. DURING GRADING AND AFTER GRADING HAS BEEN COMPLETED, CONTRACTOR SHALL CONTINUE TO MAINTAIN PERMANENT AND TEMPORARY EROSION CONTROL MEASURES UNTIL FINAL INSPECTION AND APPROVAL BY NEW HANOVER COUNTY
- 5. WATER, FERTILIZE, MOW AND MAINTAIN SPRIGGED, SODDED AND PLANTED AREAS UNTIL FINAL APPROVAL BY NEW HANOVER COUNTY.
- 6. ANY BORROW MATERIAL BROUGHT ONTO SITE MUST BE FROM A LEGALLY OPERATED MINE OR OTHER APPROVED SOURCE.
- 7. ANY EXCESS MATERIAL REMOVED FROM SITE MUST BE HAULED TO A LEGALLY OPERATED MINE OR OTHER APPROVED SOURCE.

MAINTENANCE PLAN

ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL, BUT IN NO CASE, LESS THAN ONCE EVERY WEEK AND WITHIN 24 HOURS OF EVERY HALF INCH RAINFALL.

ALL POINTS OF EGRESS WILL HAVE CONSTRUCTION ENTRANCES THAT WILL BE PERIODICALLY TOP-DRESSED WITH AN ADDITIONAL 2 INCHES OF #4 STONE TO MAINTAIN PROPER DEPTH. THEY WILL BE MAINTAINED IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM LEAVING THE SITE. IMMEDIATELY REMOVE OBJECTIONABLE MATERIAL SPILLED WASHED OR TRACKED ONTO THE CONSTRUCTION ENTRANCE OR ROADWAYS.

SEDIMENT WILL BE REMOVED FROM HARDWARE CLOTH AND GRAVEL INLET PROTECTION. BLOCK AND GRAVEL INLET PROTECTION, ROCK DOUGHNUT INLET PROTECTION AND ROCK PIPE INLET PROTECTION WHEN THE DESIGNED STORAGE CAPACITY HAS BEEN HALF FILLED WITH SEDIMENT. ROCK WILL BE CLEANED OR REPLACED WHEN THE SEDIMENT POOL NO LONGER DRAINS AS DESIGNED. DEBRIS WILL BE REMOVED FROM THE ROCK AND HARDWARE CLOTH TO ALLOW PROPER DRAINAGE. SILT SACKS WILL BE EMPTIED ONCE A WEEK AND AFTER EVERY RAIN EVENT. SEDIMENT WILL BE REMOVED FROM AROUND BEAVER DAMS, DANDY SACKS AND SOCKS ONCE A WEEK AND AFTER EVERY RAIN EVENT.

DIVERSION DITCHES WILL BE CLEANED OUT IMMEDIATELY TO REMOVE SEDIMENT OR OBSTRUCTIONS FROM THE FLOW AREA. THE DIVERSION RIDGES WILL ALSO BE REPAIRED. SWALES MUST BE TEMPORARILY STABILIZED WITHIN 21 CALENDAR DAYS OF CEASE OF ANY PHASE OF ACTIVITY ASSOCIATED WITH A SWALE.

SEDIMENT WILL BE REMOVED FROM BEHIND THE SEDIMENT FENCE WHEN IT BECOMES HALF FILLED. THE SEDIMENT FENCE WILL BE REPAIRED AS NECESSARY TO MAINTAIN A BARRIER. STAKES MUST BE STEEL. STAKE SPACING WILL BE 6 FEET MAX. WITH THE USE OF EXTRA STRENGTH FABRIC, WITHOUT WIRE BACKING. STAKE SPACING WILL BE 8 FEET MAX. WHEN STANDARD STRENGTH FABRIC AND WIRE BACKING ARE USED. IF ROCK FILTERS ARE DESIGNED AT LOW POINTS IN THE SEDIMENT FENCE THE ROCK WILL BE REPAIRED OR REPLACED IF IT BECOMES HALF FULL OF SEDIMENT, NO LONGER DRAINS AS DESIGNED OR IS DAMAGED.

SEDIMENT WILL BE REMOVED FROM SEDIMENT TRAPS WHEN THE DESIGNED STORAGE CAPACITY HAS BEEN HALF FILLED WITH SEDIMENT. THE ROCK WILL BE CLEANED OR REPLACED WHEN THE SEDIMENT POOL NO LONGER DRAINS OR WHEN THE ROCK IS DISLODGED. BAFFLES WILL BE REPAIRED OR REPLACED IF THEY COLLAPSE, TEAR, DECOMPOSE OR BECOME INEFFECTIVE. THEY WILL BE REPLACED PROMPTLY. SEDIMENT WILL BE REMOVED WHEN DEPOSITS REACH HALF THE HEIGHT OF THE 1ST BAFFLE.

SEDIMENT WILL BE REMOVED FROM THE SEDIMENT BASIN WHEN THE DESIGN STORAGE CAPACITY HAS BEEN HALF FILLED WITH SEDIMENT. ROCK WILL BE CLEANED OR REPLACED WHEN THE SEDIMENT POOL NO LONGER DRAINS OR IF THE ROCK IS DISLODGED. BAFFLES WILL BE REPAIRED OR REPLACED IF THEY COLLAPSE, TEAR, DECOMPOSE OR BECOME INEFFECTIVE. THEY WILL BE REPLACED PROMPTLY. SEDIMENT WILL BE REMOVED FROM BAFFLES WHEN DEPOSITS REACH HALF THE HEIGHT OF THE 1ST BAFFLE. FLOATING SKIMMERS WILL BE INSPECTED WEEKLY AND WILL BE KEPT CLEAN.

ALL SEEDED AREAS WILL BE FERTILIZED, RESEEDED AS NECESSARY AND MULCHED ACCORDING TO SPECIFICATIONS IN THE VEGETATIVE PLAN TO MAINTAIN A VIGOROUS, DENSE VEGETATIVE COVER. ALL SLOPES WILL BE STABILIZED WITHIN 21 CALENDAR DAYS. ALL OTHER AREAS WILL BE STABILIZED WITHIN 15 WORKING DAYS.

FLOCCULANTS WILL BE USED TO ADDRESS TURBIDITY ISSUES. THE PUMPS, TANKS, HOSES AND INJECTION SYSTEMS WILL BE CHECKED FOR PROBLEMS OR TURBID DISCHARGES DAILY.

<u>stabilization notes</u>

1. ALL DISTURBED AREAS WILL BE STABILIZED WITHIN 15 WORKING DAYS OF CEASE OF ANY PHASE OF ACTIVITY AND SLOPES WITHIN 21 CALENDAR DAYS.

PERMANENT SEEDING SCHEDULE - MIXTURE 5CP

<u>SPECIES</u> CENTIPEDE GRASS

Seeding Dates

MARCH – JUNE

Soil Amendments APPLY LIME AND FERTILIZER ACCORDING TO SOIL TESTS, OR APPLY 300 LB/ACRE 10–10–10 FERTILIZER.

Mulch DO NOT MULCH.

Maintenance FERTILIZE VERY SPARINGLY LB/ACRE NITROGEN IN SPRING WITH NO PHOSPHORUS. CENTIPEDE GRASS CANNOT TOLERATE HIGH PH OR EXCESS FERTILIZER.

TEMPORARY SEEDING-LATE WINTER/EARLY SPRING

WINTER AND EARLY SPRING

<u>SPECIES</u> Rye (GRAIN)

*ANNUAL LESPEDEZA (KOBE IN PIEDMONT AND COASTAL PLAIN, KOREAN IN MOUNTAINS) *OMIT ANNUAL LESPEDEZA WHEN DURATION OF TEMPORARY COVER IS NOT TO EXTEND BEYOND JUNE.

<u>SUMMER</u>

<u>SPECIES</u> GERMAN MILLET

<u>Fall</u>

<u>SPECIES</u> RYE (GRAIN)

Seeding dates COASTAL PLAIN - DEC.1-APR. 15 - LATE WINTER AND EARLY SPRING APRIL 15 - AUG. 15 - SUMMER

AUG. 15 - DEC. 30 - FALL Soil amendments

FOLLOW RECOMMENDATIONS OF SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND 750 LB/ACRE 10-10-10 FERTILIZER. Mulch

APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.

Maintenance REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.

		Scale		Designer	By	Date	o. Revision	No.
BELLE MEADE AP	l R	Date	GSP	Drawn By				
		December 2014	GSP	,				
New Hanover Co	Wilmington	Job No. 2014–0006	P-0718	License #				

RATE (LB/ACRE) 10-20

<u>RATE (LB/ACRE)</u> 120

<u>RATE (LB/ACRE)</u> 40

<u>rate (lb/acre)</u> 120

ARTMENTS

ountv

North Carolina

GENERAL GRADING NOTES

- 1. REASONABLE CARE HAS BEEN EXERCISED IN SHOWING THE LOCATION OF EXISTING UTILITIES ON THE PLANS. THE EXACT LOCATION OF SUCH UTILITIES IS NOT KNOWN IN ALL CASES. THE CONTRACTOR SHALL EXPLORE THE AREA AHEAD OF THE DITCHING OPERATION BY OBSERVATIONS, ELECTRONIC DEVICES, HAND DIGGING AND BY PERSONAL CONTACT WITH THE UTILITY COMPANIES IN ORDER TO LOCATE EXISTING UTILITIES IN ADVANCE OF THE TRENCHING OPERATIONS SO AS TO AVOID AND PREVENT DAMAGE TO THE EXISTING UTILITIES. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COST RESULTING FROM ANY DAMAGE TO THE EXISTING UTILITY LINES INCLUDING BUT NOT LIMITED TO REPAIRS AND LOSS SERVICE REVENUE. CONTRACTOR SHALL ARRANGE FOR TEMPORARY SUPPORT OF EXISTING UTILITIES, SUCH AS POLES, CONDUITS, FIBER OPTIC CABLES, TELEPHONE CABLES, WATER LINES, ETC ...
- 2. CONTRACTOR SHALL COMPLY WITH THE LATEST REVISIONS AND INTERPRETATIONS OF THE DEPARTMENT OF LABOR SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION PROMULGATED UNDER THE OCCUPATIONAL SAFETY AND HEALTH ACT.
- 3. CONTRACTOR SHALL PLAN AND CONSTRUCT WORK SO AS TO CAUSE MINIMUM INCONVENIENCE TO THE OWNER AND THE PUBLIC. THE CONTRACTOR SHALL PROVIDE, ERECT AND MAINTAIN AT ALL TIMES DURING THE PROGRESS OR TEMPORARY SUSPENSION OF WORK, SUITABLE BARRIERS, FENCES, SIGNS OR OTHER ADEQUATE PROTECTION, INCLUDING FLAG MEN AND WATCHMEN AS NECESSARY TO INSURE THE SAFETY OF THE PUBLIC AS WELL AS THOSE ENGAGED IN THE CONSTRUCTION WORK. CONSTRUCTION SIGNING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF "CONSTRUCTION AND MAINTENANCE OPERATIONS SUPPLEMENT TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" BY THE NCDOT.
- 4. ALL MATERIAL CLEARED AND GRUBBED BY THE CONTRACTOR IN ORDER TO CONSTRUCT THE WORK, SUCH AS TREES, VEGETATION, FENCING, ETC ... SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE PROPERLY DISPOSED OF OFF-SITE OR BURNED IF PROPER PERMITS ARE RECEIVED.

SITE NOTES

BROOM CLEAN AT ALL TIMES.

- 1. ANY DISCREPANCY IN THIS PLAN AND ACTUAL FIELD CONDITIONS SHALL BE REPORTED TO THE OWNER PRIOR TO START OF CONSTRUCTION. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF ALL SETBACKS, EASEMENTS AND DIMENSIONS SHOWN HEREON BEFORE BEGINNING CONSTRUCTION.
- 2. THE GENERAL CONTRACTOR SHALL CONTACT ALL OWNERS OF EASEMENTS, UTILITIES AND R.O.W.'S PUBLIC OR PRIVATE, PRIOR TO WORKING IN THESE AREAS.
- 3. CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY, AND ADJOINING PROPERTY PROTECTED FROM DAMAGE.
- 4. ACCESS TO UTILITIES, FIRE HYDRANTS, STREET LIGHTING, ETC., SHALL REMAIN UNDISTURBED, UNLESS COORDINATED WITH THE RESPECTIVE UTILITY.
- 5. DO NOT SCALE THIS DRAWING AS IT IS A REPRODUCTION AND SUBJECT TO DISTORTION.
- 6. THE GENERAL CONTRACTOR SHALL REMOVE ALL DEBRIS FROM THE SITE UPON COMPLETION OF THE PROJECT AND AT LEAST ONCE A WEEK DURING CONSTRUCTION.
- 7. THE GENERAL CONTRACTOR SHALL KEEP THE AREA OUTSIDE THE "CONSTRUCTION LIMITS"
- 8. CONTRACTOR SHALL MAINTAIN AN "AS-BUILT" SET OF DRAWINGS TO RECORD THE EXACT LOCATION OF ALL PIPING PRIOR TO CONCEALMENT. DRAWINGS SHALL BE GIVEN TO THE OWNER UPON COMPLETION OF THE PROJECT WITH A COPY OF THE TRANSMITTAL LETTER TO THE ENGINEER.
- 9. IF DEPARTURES FROM THE SPECIFICATIONS OR DRAWINGS ARE DEEMED NECESSARY BY THE CONTRACTOR, DETAILS OF SUCH DEPARTURES AND REASONS THEREOF SHALL BE GIVEN TO THE OWNER FOR REVIEW, NO DEPARTURES FROM THE CONTRACT DOCUMENT SHALL BE MADE WITHOUT THE PERMISSION OF THE OWNER.
- 10. CONTRACTOR SHALL VERIFY LOCATION AND ELEVATION OF ALL UNDERGROUND UTILITIES. THE LOCATION OF ALL EXISTING UTILITIES ARE NOT NECESSARILY SHOWN ON PLANS AND WHERE SHOWN ARE ONLY APPROXIMATE. THE CONTRACTOR SHALL ON HIS INITIATIVE AND AT NO EXTRA COST HAVE LOCATED ALL UNDERGROUND LINES AND STRUCTURES AS NECESSARY. NO CLAIMS FOR DAMAGES OR EXTRA COMPENSATION SHALL ACCRUE TO THE CONTRACTOR FROM THE PRESENCE OF SUCH PIPE OTHER OBSTRUCTIONS OR FROM DELAY DUE TO REMOVAL OR REARRANGEMENT OF THE SAME. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO UNDERGROUND STRUCTURES. CONTACT NORTH CAROLINA ONE CALL TOLL FREE 1-800-632-4949 AT LEAST 48 HOURS PRIOR TO CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING ALL NONSUBSCRIBING UTILITIES.
- 11. ALL PERMITS RELATIVE TO PROJECT MUST BE OBTAINED, PRIOR TO CONSTRUCTION
- 12. ALL CONSTRUCTION TO BE IN ACCORDANCE WITH PERMITS ISSUED AND APPLICABLE STATE, COUNTY, AND LOCAL CODES.
- 13. FOR BUILDING DIMENSIONS. SEE ARCHITECTURAL DRAWINGS.
- 14. ALL DIMENSIONS AND RADII ARE TO OUTSIDE FACE OF BUILDING OR TO FACE OF CURB UNLESS OTHERWISE NOTED.
- 15. THE CONTRACTOR SHALL OBTAIN AND PAY FOR ALL INSPECTIONS, CERTIFICATIONS, EQUIPMENT, ETC., THAT MAY BE REQUIRED.
- 16. THE ENGINEER AND/OR OWNER DISCLAIM ANY ROLE IN THE CONSTRUCTION MEANS AND METHODS ASSOCIATED WITH THE PROJECT AS SET FORTH IN THESE PLANS.

GENERAL STORM SEWER NOTES

PI ANS

- ALL STORM SEWERS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CITY OF WILMINGTON AND THE STATE OF NORTH CAROLINA REQUIREMENTS AS SPECIFIED ON THE DRAWINGS AND IN THE PROJECT SPECIFICATIONS.
- BEDDING FOR ALL STORM SEWER PIPE SHALL BE AS SPECIFIED ON THE DRAWINGS, PROJECT SPECIFICATIONS, AND MANUFACTURER SPECIFICATIONS.
- 3. ALL STORM SEWER PIPES TO BE HDPE ADS N-12 OR EQUIVALENT, UNLESS OTHERWISE SPECIFIED.
- 4. ALL STORM SEWER PIPES SHOWN AS RCP ON THE PLANS SHALL BE REINFORCED CONCRETE PIPE CONFORMING TO ASTM C-76, UNLESS INDICATED OTHERWISE ON

	GROUND STABILIZATION							
SITE AREA DESCRIPTION	STABILIZATION TIME FRAME	STABILIZATION TIME FRAME EXCEPTIONS						
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE						
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE						
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.						
SLOPES 3:1 OR FLATTER	14 DAYS	7-DAYS FOR SLOPES GREATER THAN 50 FEET IN LENGTH						
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE (EXCEPT FOR PERIMETERS AND HQW ZONES)						

GENERAL NOTES

EXISTING UTILITY NOTES

- FIELD PRIOR TO GROUND BREAKING.

UTILITY CONTACTS: 1-800-632-4949

NOTICE REQUIRED

EMERGENCY DIAL 911


1. IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO VERIFY THE ACTUAL LOCATION AND AVAILABILITY OF ALL EXISTING AND PROPOSED UTILITIES IN THE


2. EXISTING UTILITIES AND STRUCTURES SHOWN, BOTH UNDERGROUND AND ABOVE GROUND, ARE BASED ON A FIELD SURVEY AND THE BEST AVAILABLE RECORD DRAWINGS. THE CONTRACTOR SHALL FIELD VERIFY FIELD CONDITIONS PRIOR TO BEGINNING RELATED CONSTRUCTION. ANY DISCREPANCIES SHALL BE REPORTED TO THE OWNER'S REPRESENTATIVE IMMEDIATELY.


1. CONTACT THE NORTH CAROLINA ONE CALL CENTER PRIOR TO DOING AND DIGGING.


ALL EXISTING UNDERGROUND UTILITIES SHALL BE PHYSICALLY LOCATED BY CONTRACTOR PRIOR TO THE BEGINNING OF ANY CONSTRUCTION IN THE VICINITY OF SAID UTILITIES. CONTRACTORS SHALL NOTIFY OPERATORS WHO MAINTAIN UNDERGROUND UTILITY LINES IN THE AREA OF PROPOSED EXCAVATION AT LEAST TWO WORKING DAYS, BUT NOT MORE THAN TEN WORKING DAYS PRIOR TO ANY EXCAVATION OR DEMOLITION. CONTACT "CAROLINA ONE CALL" AT 1-800-632-4949


POLICE - FIRE - RESCUE























	/			CURR INLET			
		24" FES INV.: 6.28		RIM:			
/	3	6"FES NV.: 8.58					
				- +7			
				15-16-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-			
				-1+			
				3			
					/		
						',/////// / ////////////////////////////	·
						<u> </u>	
					\		60" FES INV.: 5.1
		I					
No. Revision	Date	By Designer	Scale				
No. Revisior	<u>Date</u>	By Designer Drawn By License #	Date	" = 20' ember 2014	BEI	LE MEA	DEAP









PARTMENTS

County


North Carolina

WET DETENTION DETAILS EXISTING POND #1





ARE	A C-FACTOR	RUNOFF	CAPACITY	DIAMETER	SLOPE	INV. DN	INV. UP	HGLDn	HGLUp	RIM	MATERIAL
(ac)) (C)	(cfs)	(cfs)	(in)	(%)	(ft)	(ft)	(ft)	(ft)	(ft)	
0.00		62.90	292.00	60	1.26	5.19	6.12	15.64	15.68	20.87	EX. RCP
4.15		60.64	171.50	60	0.43	6.12	6.54	15.85	15.91	20.44	EX. RCP
0.00		48.39	110.99	60	0.18	6.54	6.84	16.07	16.13	20.97	EX. RCP
0.00		46.98	111.52	48	0.60	6.84	8.68	16.22	16.55	23.14	EX. RCP
0.10		47.42	113.06	48	0.62	8.68	9.14	16.58	16.66	20.90	EX. RCP
0.19		33.17 32.58	113.80 40.61	48 48	0.63	9.14 9.82	9.82 9.88	17.09 17.28	17.15 17.32	20.83 21.48	EX. RCP EX. RCP
0.00		33.21	105.46	48	0.08	9.82 9.88	10.65	17.39	17.32	19.00	EX. RCP
0.69		23.75	85.81	48	0.34	10.65	11.94	17.69	17.78	17.94	EX. RCP
0.66		13.41	52.04	36	0.61	11.94	13.63	17.87	17.98	18.10	EX. RCP
0.5		6.07	36.81	30	0.81	13.63	14.10	18.14	18.15	18.18	EX. RCP
0.28	3 0.71	3.90	11.30	18	1.16	10.62	11.29	15.93	16.01	18.01	EX. RCP
0.53	3 0.65	2.49	13.68	18	1.70	11.29	12.02	16.15	16.17	18.01	EX. RCP
0.24		4.06	17.17	18	2.67	15.14	16.12	16.24	16.89	20.45	EX. RCP
0.63	0.63	2.87	18.37	18	3.06	16.12	17.36	17.16	18.01	20.45	EX. RCP
0.07	0.70	45 70	70 47	70	0.70	44 4 4	11 70	1740	4747		
0.26		15.76	36.47	36	0.30	11.14	11.38	17.12 17.22	17.17	20.87	HDPE HDPE
0.25		14.89 13.58	22.46 12.40	30 24	0.30	11.38 12.00	12.00 12.12	17.22	17.49 17.70	20.38	HDPE
0.35		7.16	12.40	24	0.30	12.00	12.12	17.56	17.70	19.11	HDPE
0.20		5.88	12.33	24	0.30	12.12	12.23	18.45	18.61	19.29	HDPE
0.3		3.26	3.53	15	0.30	12.23	13.03	18.67	18.77	18.80	HDPE
0.19		1.72	3.48	15	0.29	13.03	13.17	18.91	18.94	19.08	HDPE
0.12	2 0.82	0.71	3.54	15	0.30	13.17	13.41	19.01	19.02	19.08	HDPE
0.25	5 0.91	4.95	5.80	18	0.30	12.12	12.27	18.31	18.42	19.29	HDPE
0.32		3.42	5.79	18	0.30	12.27	12.51	18.54	18.63	19.49	HDPE
0.15		1.45	3.54	15	0.30	12.51	12.87	18.75	18.81	21.20	HDPE
0.09	0.84	0.55	3.49	15	0.29	12.87	13.10	18.86	18.87	21.80	HDPE
0.22	2 0.71	1.13	3.53	15	0.30	12.91	13.10	18.71	18.73	19.04	HDPE
0.29	0.87	5.64	12.29	24	0.30	14.63	14.76	18.11	18.14	19.00	HDPE
0.11	0.61	3.94	5.78	18	0.30	14.76	14.95	18.16	18.25	19.00	HDPE
0.13	0.72	3.49	5.91	18	0.32	14.95	15.07	18.31	18.35	19.00	HDPE
0.26	<u> </u>	2.87	3.49	15	0.29	15.07	15.28	18.38	18.52	19.00	HDPE
0.2	0.83	1.26	3.56	15	0.30	15.28	15.68	18.72	18.77	18.98	HDPE
									/		
0.48		8.88	37.15	36	0.31	10.89	11.04	17.72	17.73	18.91	EX. RCP
0.08		7.09	12.48	24	0.30	12.04	12.10	17.74	17.76	21.00	
0.00		1.57 1.58	3.55 3.46	15 15	0.30	12.10 12.62	12.62 12.72	17.89 18.01	17.99 18.03	22.00 20.01	HDPE HDPE
0.05		1.58	3.46	15	0.29	12.62	12.72	18.01	18.03	20.01	HDPE
0.09		0.57	3.59	15	0.30	12.72	12.90	18.11	18.10	20.01	HDPE
0.08	3 0.95	5.11	12.50	24	0.31	12.10	12.32	17.87	17.91	21.00	HDPE
0.11	0.70	4.61	5.69	18	0.29	12.32	12.41	17.94	18.00	20.25	HDPE
0.30	0.81	4.14	5.73	18	0.30	12.41	12.65	18.15	18.27	19.51	HDPE
0.17		2.47	3.53	15	0.30	12.65	12.87	18.34	18.44	19.40	HDPE
0.13		1.49	3.56	15	0.30	12.87	13.25	18.58	18.65	20.01	HDPE
0.12	0.82	0.71	3.43	15	0.28	13.25	13.33	18.68	18.68	20.01	HDPE
0.00		0.07	47.00		0.07	40.70	10.00	47.07	47.07	17.00	
0.62		8.23	17.99	24	0.63	12.30	12.62	17.87	17.93	17.96	EX. RCP
0.20		5.52	5.77	18	0.30	12.62	12.80	18.04	18.21	19.15	
0.29		4.50 2.89	5.82 3.52	18 15	0.31	12.80 13.02	13.02 13.24	18.42 18.61	18.55 18.76	19.51 19.50	HDPE HDPE
0.28		1.30	3.52	15	0.30	13.02	13.24	18.96	18.76	19.50	HDPE
0.22		1.30	0.04		0.00	13.24	13.34	10.90	19.00	13.00	
0.20	0.79	3.59	3.55	15	0.30	14.60	14.78	18.18	18.36	21.03	HDPE
0.26		2.57	3.52	15	0.30	14.78	15.22	18.58	18.82	19.54	HDPE
0.22		1.30	3.55	15	0.30	15.22	15.87	18.97	19.06	19.64	HDPE




9. AFTER CONSTRUCTION OPERATIONS HAVE ENDED AND ALL DISTURBED AREAS HAVE BEEN STABILIZED, MECHANICAL SEDIMENT CONTROLS SHALL BE REMOVED. SEDIMENT FROM TEMPORARY SEDIMENT TRAPPING DEVICES SHALL BE DISPOSED OF BY SPREADING ON THE SITE OR HAULING AWAY IF NOT SUITABLE FOR FILL. ALL DENUDED AREAS ARE TO BE PERMANENTLY STABILIZED WITH PERMANENT VEGETATION.


AREAS WITH TEMPORARY VEGETATION IF LEFT UNDISTURBED FOR 15 WORKING DAYS AND ALL SLOPES WITHIN 21 CALENDAR DAYS.

4. ONCE PERIMETER CONTROLS AND SEDIMENT TRAPPING MEASURES ARE INSTALLED CLEAR AND GRUB SITE WITHIN LIMITS OF DISTURBANCE. THE SEDIMENT BASIN WILL BE PUMPED DOWN BY MECHANICAL MEANS AS NEEDED TO MUCK OUT SEDIMENT 5. UPON BRINGING THE SITE TO ROUGH GRADE, STABILIZE ALL

SEQUENCE OF CONSTRUCTION LIMITS OF CONSTRUCTION = 12.26 ACRES 1. INSTALL TEMPORARY CONSTRUCTION ENTRANCE AS SHOWN



TEMPORARY CONSTRUCTION ENTRANCE N. T. S.



Signed:

GSP CONSULTING, PLLC

ENGINEERING

6626 Gordon Road Unit C Wilmington, North Carolina 28411 tel: 910-442-7870 fax: 910-799-6659

Sheet No.

C-9