ABBREVIATIONS

ALT	ALTERNATE
AMP	AMPERE
ANCH	ANCHOR
Ac.	ACRE
BIT	BITUMINOUS
BLDG	BUILDING
BM	BEAM, BENCH MARK
BOTT	BOTTOM
CB	CATCH BASIN
C/C	CENTER TO CENTER
CDI	CURB DROP INLET
CFM	CUBIC FEET PER MINUTE
C&G	CURB & GUTTER
CI	CAST IRON
CIP	CAST IN PLACE
CL	CENTERLINE, CLASS
CMP	CORRUGATED METAL PIPE
CO	CLEANOUT
CONC	CONCRETE
CONC PVMT	CONCRETE PAVEMENT
COND	CONDUIT
CONST	CONSTRUCT, CONSTRUCTION
CTR	CENTER
CTV	CABLE TELEVISION
DB	DEED BOOK
DI	DROP INLET, DUCTILE IRON
DIA	DIAMETER
DISCH	DISCHARGE
DWG	DRAWING
E	EAST
EA	EACH
EAP	EXPOSED AGGREGATE PAVING
EL, ELEV	ELEVATION
ELEC	ELECTRIC, ELECTRICAL
EMER	EMERGENCY
EOP, EP	EDGE OF PAVEMENT
EQUIP	EQUIPMENT
ESMT	EASEMENT
EW	EACH WAY, END WALL
EXIST, EX	EXISTING
FL	FLOW LINE
FLG	FLANGE
FLR	FLOOR
FM	FORCE MAIN
FT	FOOT, FEET
G	GAS LINE, GUTTER
GA	GAGE
GAL	GALLON
GALV	GALVANIZED
GEN	GENERATOR
GPM	GALLONS PER MINUTE
h	HEIGHT
HP	HORSEPOWER
HWY	HIGHWAY
ID	INSIDE DIAMETER
INV	INVERT
IP	IRON PIPE, IRON PIN
IPF	IRON PIN FOUND
IR	IRON ROD
JB	JUNCTION BOX
KW	KILOWATTS
M	METER
MANUF, MFR	MANUFACTURER
MAT'L	MATERIAL
MAX	MAXIMUM
MGD	MILLION GALLONS PER DAY
MH	MANHOLE
MIN	MINIMUM
MON	MONUMENT
N	NORTH
N&C	NAIL AND CAP
NEC	NATIONAL ELECTRIC CODE
NGS	NATIONAL GEODETIC SURVEY
NIC	NOT IN CONTRACT
NO., #	NUMBER
NTS	NOT TO SCALE
OC	ON CENTER
OD	OUTSIDE DIAMETER
PI	POINT OF INTERSECTION
PL	PROPERTY LINE
PNL	PANEL
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PVC	POLYVINYL CHLORIDE/ POINT OF VERTICAL CURVE
PVMT	PAVEMENT
QTY, QUAN	QUANTITY
RCCP	REINFORCED CONCRETE CYLINDER PIPE
RCM	RECLAIMED WATER MAIN
RCP	REINFORCED CONCRETE PIPE
RED	REDUCER
REF	REFERENCE
REINF	REINFORCED, REINFORCING
REQ'D	REQUIRED
REV	REVISION
ROW, R/W	RIGHT OF WAY
RT	RIGHT
RU	REUSE WATER MAIN
RW	RAW WATER
S	SOUTH
SAN	SANITARY
SCHED	SCHEDULE
SD	STORM DRAIN
S.F.	SQUARE FEET
SHT	SHEET
SR	STATE ROUTE
STA	STATION
STD	STANDARD
S/W	SIDEWALK
TELE, TEL	TELEPHONE
TOB	TOP OF BANK
TOS	TOE OF SLOPE
TPS	TURN POINT SET
TS & V	TAPPING SLEEVE & VALVE
TYP	TYPICAL
UL	UNDERWRITERS LAB
UNO	UNLESS NOTED OTHERWISE
V	VOLT
VC	VITRIFIED CLAY
VERT	VERTICAL
VOL	VOLUME
w	WIDTH
W/	WITH
WM	WATER METER, WATER MAIN
WP	WATERPROOF, WEATHERPROOF
WSL	WATER SERVICE LINE
WV	WATER VALVE

LEGEND

DESCRIPTION	EXISTING	NEW
PROPERTY LINE		
ROAD RIGHT-OF-WAY		
UTILITY EASEMENT		
PAVED ROADWAY		
DIRT OR CRUSHED STONE ROADWAY		
STORM DRAINAGE	12"RCP	12"RCP
GAS LINE	12"G	
OVERHEAD ELECTRIC	OE	
OVERHEAD TELEPHONE	OHT	
OVERHEAD TELEVISION	OHTV	
UNDERGROUND ELECTRIC	UGE	
UNDERGROUND TELEPHONE	UGT	
UNDERGROUND TELEVISION	UGTV	
DIRECTION OF FLOW		
GROUND ELEVATION	7.26	7.64 (TOP OF CURB) 7.26 (EDGE OF PAVEMENT) / 7.64 (SPOT EL.)
CONTOUR (MAJOR)	15	15
CONTOUR (MINOR)		12
MANHOLE		
CATCH BASIN		
INLETS		
DROP INLET (THROAT OPENING)		
UTILITY POLE		
LIGHT POLE		
SUPPORT POLE		
LANDSCAPE LIGHTING		
UTILITY PEDESTAL		
GUY WIRE		
BOLLARD	BOL	
MAILBOX	MB	
SIGN		
BENCHMARK		
TREE LINE		
SHRUB		
EXISTING IRON ROD (DISTURBED)	EIR (D)	
EXISTING IRON ROD	EIR	
LIMITS OF DISTURBANCE		LOD
SILT FENCE		SF
TREE PROTECTION FENCE		TP TP
TEMPORARY DIVERSION DITCH		>TDD
SANITARY SEWER LINE		SS
SANITARY SEWER MANHOLE		S
WATER LINE		8"W
FIRE HYDRANT		
VALVE	WV	
STORMWATER PIPE		

REV.NO.	DESCRIPTIONS	DATE
A	CITY OF WILMINGTON TRC SUBMITTAL	04/08/2015

REVISIONS

FINAL DRAWINGS DO NOT USE FOR CONSTRUCTION

SEAL

NORTH CAROLINA PROFESSIONAL SEAL CIVIL 035107 ENGINEER NICHOLAS J. LAURETTA

04/08/15

McKIM&CREED
243 North Front Street
Wilmington, North Carolina 28401
Phone: (910)343-1048, Fax: (910)251-8282
License: F-1222
www.mckimcreed.com

NASH — NORTH AMERICA SEKISUI HOUSE, LLC

RIVERLIGHTS™ by Newland COMMUNITIES

RIVERLIGHTS MARINA VILLAGE

ABBREVIATIONS & LEGEND

DATE:	08APR15
MCE PROJ. #	2735-0124
DRAWN	EEM
DESIGNED	EEM
CHECKED	RMC
PROJ. MGR.	NJL

SCALE
HORIZONTAL: --
VERTICAL: --

M&C FILE NUMBER G-002
DRAWING NUMBER 2
2 OF28

STATUS: FINAL DESIGN
NOT FOR CONSTRUCTION
REVISION A