


GENERAL NOTES:

- The proposed left turn lane is required to meet City of Wilmington Technical Standards and MUTCD requirements.
- The Walk Wilmington plan and Comp Greenway plan call for a future MUP along the River Road frontage of the Marshes. There are no funded plans for the MUP connection from Independence to the Riverlights MUP. The City would prefer construction of this required sidewalk from Independence to the Phase 3 entrance to provide a more immediate connection between Phase 3 portion of the project and the neighborhood amenities and park project within Echo Farms.
- City staff is willing to accept a payment in lieu for the portion of the sidewalk between the Ph 3 entrance and the bridge. The developer desires to submit such a payment-in-lieu (PIL).











PHASE 3

PHASE 4


A PAYMENT IN LIEU OF CONSTRUCTION FOR THE ORIGINALLY APPROVED 5' SIDEWALK ON INDEPENDENCE IS IN PLACE

PROVIDE 5' SIDEWALK ON RIVER ROAD TO PHASE 3 DRIVEWAY

PROVIDE 85LF OF VERTICAL CURB & GUTTER ON RIVER RD. FOR GRADE SEPERATION



- DENOTES PROPOSED CONTOUR
- DENOTES EX. CONTOUR
- DENOTES PROPOSED GRADE
- DENOTES PROPOSED STORM DRAINAGE
- DENOTES DROP INLET OR CATCH BASIN W/ INLET PROTECTION
- DENOTES LIMITS OF DISTURBANCE
- DENOTES SILT FENCE
- DENOTES SEDIMENT TRAP
- DENOTES DRAINAGE DIRECTION
- DENOTES WETLAND LINES
- DENOTES DRAINAGE AREA
- DENOTES PROPOSED FIRE HYDRANT
- DENOTES PROPOSED MANHOLE
- DENOTES PROPOSED 8 IN SANITARY SEWER
- DENOTES PHASE LINE
- DENOTES SQUARE FOOTAGE OF STREET YARD
- DENOTES PROPOSED WATER
- DENOTES PROPOSED GATE VALVE
- DENOTES PARKING LOT LANDSCAPE AREA



For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

Approved Construction Plan  
Name \_\_\_\_\_ Date \_\_\_\_\_

Planning \_\_\_\_\_  
Public Utilities \_\_\_\_\_  
Traffic \_\_\_\_\_  
Fire \_\_\_\_\_

STORMWATER MANAGEMENT PLAN APPROVED  
CITY OF WILMINGTON  
ENGINEERING DEPARTMENT  
DATE \_\_\_\_\_ PERMIT # \_\_\_\_\_  
SIGNED \_\_\_\_\_


PROPOSED RIVER ROAD TURN LANE CONCEPT

## THE MARSHES

PHASE 3

WILMINGTON TOWNSHIP    CITY OF WILMINGTON    NORTH CAROLINA	DESIGNED: JHF
OWNER: RIVERS EDGE I, LLC	DRAWN: JHF
ADDRESS: 1224 PEMBROKE JONES DRIVE WILMINGTON, NC 28045	APPROVED: JHF
PHONE: (910) 619-8814	DATE: 6/05/19
STROUD ENGINEERING, P.A. 102 SUITE D CINEMA DRIVE WILMINGTON, NC 28403 (910) 815-0775	SCALE: 1" = 40'
	SHEET 5 OF 9

JAMES H. TRENTRESS, JR., P.E.  
 WILMINGTON, NC  
 DATE: 6/11/2020














Table 6.62b Specifications For Sediment Fence Fabric

Test Material	Units	Supported <sup>1</sup> Silt Fence	Un-Supported <sup>1</sup> Silt Fence	Type of Value
Grab Strength	ASTM D 4632	N (lbs)		
Machine Direction			400 (90)	MARV
X-Machine Direction			400 (90)	MARV
Permittivity <sup>2</sup>	ASTM D 4491	sec-1	0.05	MARV
Apparent Opening Size <sup>2</sup>	ASTM D 4751	mm (US Sieve #)	0.60 (30)	Max. ARV <sup>2</sup>
Ultraviolet Stability	ASTM D 4355	% Retained Strength	70% after 500h of exposure	70% after 500h of exposure

PERMANENT SEEDING TABLE 1

Seeding Dates	Recommended Planting	Rate (lb/ac)
Feb. 15 - Apr. 1	Tall Fescue Mixture	see table 2
Apr. 1 - Nov. 1	Tall Fescue Mixture	see table 2
Apr. 1 - Aug. 1	Hybrid Bermudagrass	see table 2
Apr. 1 - Jul. 15	Common Bermudagrass	see table 2
Mar. 1 - Jul. 1	Centipedegrass	see table 2

PERMANENT SEEDING TABLE 2a-LOW MAINTENANCE MIXTURES

Site Description	Recommended Planting	Rate (lb/ac)
Well to poorly drained soils	Tall Fescue Mixture	80
	Panicum Bahiagrass	40
	Kobe Lespedeza	50
Dry to well drained soils	Panicum Bahiagrass	50
	Common Bermudagrass	30
	German Millet	10
Swales	Common Bermudagrass	40-80

PERMANENT SEEDING TABLE 2b-HIGH MAINTENANCE MIXTURES

Site Description	Recommended Planting	Rate (lb/ac)
Well to poorly drained soils	Tall Fescue Mixture	200
	Rye Grain	25
Dry to well drained soils	Hybrid Bermudagrass	50
Well drained sandy loam to sand, loams.	Centipedegrass	10-20

TEMPORARY SEEDING TABLE

Seeding Dates	Recommended Planting	Rate (lb/ac)
Dec. 1 - Apr. 15	Kobe Lespedeza with Rye Grain	50
Apr. 15 - Aug. 15	German Millet	40
Aug. 15 - Dec. 1	Rye Grain	120

EROSION & SEDIMENT CONTROL MAINTENANCE PLAN

- All erosion and sediment control measures will be checked for stability and operation following every runoff-producing rainfall, but in no case, less than once every week and within 24 hours of every half inch rainfall.
- All points of egress will have construction entrances that will be periodically top-dressed with an additional 2 inches of #4 stone to maintain proper depth. They will be maintained in a condition to prevent mud or sediment from leaving the site. Immediately remove objectionable material spilled, washed or tracked onto the construction entrance or roadway.
- Sediment will be removed from hardware cloth and gravel inlet protection, block and gravel inlet protection, rock doughnut inlet protection and rock pipe inlet protection when the designed storage capacity has been half filled with sediment. Rock will be cleaned or replaced when the sediment pool no longer drains as designed. Silt racks will be emptied once a week and the rock and hardware cloth to allow proper drainage. Silt racks will be emptied once a week and after every rain event. Sediment will be removed from around wattles, beaver dams, and after every rain event. Sediment will be removed from around wattles, beaver dams, and after every rain event. Sediment will be removed from around wattles, beaver dams, and after every rain event.
- Diversion ditches will be cleaned out immediately to remove sediment or obstructions from the flow area. The diversion ridges will also be repaired. Swales must be temporarily stabilized within 21 calendar days of cease of any phase of activity associated with a swale.
- Sediment will be removed from behind the sediment fence when it becomes half filled. The stake spacing will be 8 feet max. with the use of extra strength fabric, without wire backing. Stake spacing will be 8 feet max. with the use of extra strength fabric, without wire backing. Stake spacing will be 8 feet max. with the use of extra strength fabric, without wire backing.
- Sediment will be removed from behind the sediment fence when the designed storage capacity has been half filled with sediment. No longer drains as designed or is damaged. Baffles will be replaced when the rock is dislodged. Baffles will be replaced when the rock is dislodged. Baffles will be replaced when the rock is dislodged.
- Sediment will be removed from behind the sediment fence when the designed storage capacity has been half filled with sediment. No longer drains as designed or is damaged. Baffles will be replaced when the rock is dislodged. Baffles will be replaced when the rock is dislodged. Baffles will be replaced when the rock is dislodged.
- All needed areas will be fertilized, reseeded as necessary and mulched according to specifications in the vegetative plan to maintain a vigorous, dense vegetative cover. All slopes will be stabilized within 21 calendar days. All other areas will be stabilized within 15 working days.
- Floculants will be used to address turbidity issues. The pumps, tanks, hoses and injection systems will be checked for problems or turbid discharges daily.

