POND DETAILS



POND SECTION
NOT TO SCALE



PAVEMENT REPAIR DETAIL
SD 1-16
NOT TO SCALE



POND OUTLET STRUCTURE SECTION
NOT TO SCALE

NOTE:
1. FOR MAINTENANCE EFFORTS OR IN CASE OF EMERGENCY, STORMWATER STORED BELOW PERMANENT POOL SHALL BE PUMPED.
2. ALL STORMWATER (INCLUDING ROOF DRAINAGE) MUST BE CONVEYED TO THE APPROPRIATE STORMWATER BMP.



CURB TRANSITION DETAIL
NOT TO SCALE



POND SECTION
NOT TO SCALE

SUITABLE PLANTS
PICKERELWEED (PONTEDERIA CORDATA)
DUCK POTATO (SAGGITARIA LATIFOLIA AND SAGGITARIA CARDINALIS)
SWAMP ROSE (HIBISCUS MOSHEUTOS)
BLUE FLAG (IRIS VIRGINICA)
CARDINAL FLOWER (LOBELIA CARDINALIS)

WET DETENTION POND PLANTING
CONTRACTOR TO INSTALL ON THE 10:1 SLOPED SHELF, EQUAL NUMBERS OF EACH OF THE LISTED SUITABLE PLANTS. DURING INSTALLATION, GROUP SIMILAR SPECIES OF PLANTS TOGETHER. INSTALL PLANTS 24" O.C. IN A CHECKERBOARD PATTERN.



PLAN



SEE SHEET 2 OF 2 FOR DIMENSION TABLE

SECTION X-X

NOTE:
1. STRUCTURAL DESIGN OF END SECTION SHALL CONFORM WITH THAT OF STANDARD REINFORCED CONCRETE.

PIPE DIAMETER	WALL THICKNESS	SLOPE	B	C	D	E	UNIT WEIGHT
12	2 1/4	3:1	24	49	73	24	730
15	2 1/4	3:1	27	46	73	30	910
18	2 1/2	3:1	27	46	73	36	1190
21	2 3/4	3:1	36	37	73	42	1370
24	3	3:1	42	31 1/2	73 1/2	48	1770
27	3 1/4	3:1	48	25 1/2	73 1/2	54	2130
30	3 1/2	3:1	54	19 3/4	73 3/4	60	2380
33	3 3/4	3:1	60	36	96	66	3870
36	4	3:1	63	34 3/4	97 3/4	72	5320
42	4 1/2	3:1	63	35	98	78	5920
48	5	3:1	72	26	98	84	7470
54	5 1/2	2.4:1	66	34	100	90	8810
60	6	2:1	60	39	99	96	11180
72	7	2:1	78	21	99	108	13980

DIMENSIONS IN INCHES WEIGHTS IN POUNDS

FLARED END SECTION - OUTLET
SD 1-17
NOT TO SCALE



EMERGENCY SPILLWAY DETAIL
NOT TO SCALE

For each open utility cut of City streets, a $325 permit shall be required from the City prior to occupancy and/or project acceptance.

Approved Construction Plan

	Name	Date
Planning		2-13-15
Traffic		2-17-15
Fire	S. Flowers	2.18.15

CITY OF WILMINGTON NORTH CAROLINA
Public Services • Engineering Division
APPROVED STORMWATER MANAGEMENT PLAN
Date: 2/17/15 Permit # 2015603
Signed:

NCDENR PWSS WATER PERMIT #: _____
WATER CAPACITY: _____ GPD
DWQ SEWER PERMIT #: _____
SEWER CAPACITY: _____ GPD
SEWER SHED # AND PLANT: _____
SEWER TO FLOW THROUGH NEI: YES or NO (CIRCLE ONE)

FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION

REVISIONS:

POND REVISION	1/7/14
PER CITY STORMWATER COMMENTS	12/18/14

CLIENT INFORMATION:
LOT 2 DEVELOPMENT
1015 ASHES DR., SUITE 202
WILMINGTON, NC 28405

PARAMOUNTE ENGINEERING
WILMINGTON, NC FAYETTEVILLE, NC
5911 Oleander Drive, Suite 201
Wilmington, North Carolina 28403
(910) 799-6707 (O), (910) 791-0760 (F)
NC License #: C-2946

DETAILS
MELTON OAKS SUBDIVISION
WILMINGTON
NORTH CAROLINA

PROJECT STATUS:
CONCEPTUAL LAYOUT:
PRELIMINARY LAYOUT:
FINAL DESIGN:
RELEASED FOR CONST:

DRAWING INFORMATION

DATE:	10/31/14
SCALE:	N/A
DESIGNED:	GMM
DRAWN:	GLM
CHECKED:	RPB

SEAL
NORTH CAROLINA PROFESSIONAL SEAL 16729 ENGINEER DAVID B. BOWMAN

C-5.2

PEI JOB#: 14149.PE