

WOODLANDS ROAD IMPROVEMENTS

INDEPENDENCE BLVD., ECHO FARMS RD., CAROLINA BEACH RD. (US 421), AND GEORGE ANDERSON DR. WILMINGTON, NC

TYPE OF WORK: ROAD WIDENING (PAVING, DRAINAGE, AND PAVEMENT MARKINGS)

INDEX MAP

SCALE 1"=500'

UTILITY CONTACTS:

2012 OPERATIONS CENTER DR. CONTACT: DENISE FREUND, PE CONSTRUCTION PROJECT MANAGER

235 GOVERNMENT CENTER DR.

5700 HOLLY SHELTER RD. CASTLE HAYNE, NC 28429 CONTACT: KEVIN LEATHERWOOD KEVIN.LEATHERWOOD@DUKE-ENERGY.COM

NATURAL GAS PIEDMONT NATURAL GAS P.O. BOX 4489 WILMINGTON, NC 28406 (910) 251-2818 CONTACT: CARL PAQUET

102 N. 4TH STREET (910) 341-0741 CONTACT: STEVE DAYVAULT

DISTRICT OFFICE 300 DIVISION DR. WILMINGTON, NC 28401 251-2655 CONTACT: BEN HUGHES, PE DISTRICT ENGINEER BHUGHES@NCDOT.GOV

SURVEYOR:

SURVEY PROVIDED BY: BATEMAN CIVIL SURVEY CO. THE MILFORD BUILDING 406 NORTH THIRD STREET WILMINGTON, NC 28401 (910) 772-9113

SITE DATA:

TOTAL DISTURBED AREA = 1.79 AC / 78,113 SF TOTAL NEW IMPERVIOUS AREA = 18,403 SF

SHEET INDEX:

CO - COVER SHEET

C1 - TYPICAL CROSS SECTIONS

C2 - INDEPENDENCE BLVD. NORTH OF ECHO FARMS BLVD. C3 - INDEPENDENCE BLVD. SOUTH OF ECHO FARMS BLVD.

C4 - ECHO FARMS BLVD. @ INDEPENDENCE BLVD. C5 - CAROLINA BEACH ROAD @ INDEPENDENCE BLVD.

C6 - INDEPENDENCE BLVD. @ CAROLINA BEACH RD. C7 - ECHO FARMS BLVD. @ CAROLINA BEACH RD. C8 - GEORGE ANDERSON DR. @ CAROLINA BEACH RD.

C9 - CAROLINA BEACH RD. NORTH OF ECHO FARMS BLVD. C10 - CAROLINA BEACH RD. SOUTH OF ECHO FARMS BLVD. C11 - DETAILS

LIST OF APPLICABLE NCDOT STANDARD DRAWINGS:

(NCDOT STANDARDS ARE AVAILABLE ON THE NCDOT WEBSITE)

200.02 METHOD OF CLEARING - METHOD II 225.02 GUIDE FOR GRADING SUBGRADE - SECONDARY AND LOCAL

300.01 METHOD OF PIPE INSTALLATION 'A' 654.01 PAVEMENT REPAIRS

840.00 CONCRETE BASE PAD FOR DRAINAGE STRUCTURES

840.01 BRICK CATCH BASIN - 12" THRU 54" PIPE 840.02 CONCRETE CATCH BASIN - 12" THRU 54" PIPE

840.03 FRAME, GRATES AND HOOD - FOR USE ON STANDARD CATCH BASIN 840.04 CONCRETE CATCH BASIN WITH SINGLE AND MULTIPLE PIPES - 12" THRU 48" PIPE

840.34 BRICK JUNCTION BOX - 12" THRU 66" PIPE

840.45 PRECAST DRAINAGE STRUCTURE

840.46 TRAFFIC BEARING PRECAST DRAINAGE STRUCTURE 840.54 MANHOLE FRAME AND COVER

840.66 DRAINAGE STRUCTURE STEPS

840.71 CONCRETE AND BRICK PIPE PLUG

846.01 CONCRETE CURB, GUTTER AND CURB & GUTTER

848.01 CONCRETE SIDEWALK

848.02 DRIVEWAY TURNOUT - RADIUS TYPE

848.04 STREET TURNOUT 848.05 WHEELCHAIR RAMP - CURB CUT

848.06 WHEELCHAIR RAMP - RETROFITTING OF EXISTING CURB

852.06 METHOD FOR PLACEMENT OF DROP INLETS IN CONCRETE ISLANDS

1205.02 PAVEMENT MARKINGS - DIVIDED AND UNDIVIDED ROADWAYS

1205.04 PAVEMENT MARKINGS - INTERSECTIONS

1205.05 PAVEMENT MARKINGS - TURN LANES

1205.06 PAVEMENT MARKINGS - THRU LANE DROPS

1205.07 PAVEMENT MARKINGS - PEDESTRIAN CROSSWALKS

1205.08 PAVEMENT MARKINGS - SYMBOLS AND WORD MESSAGES 1205.09 PAVEMENT MARKINGS - PAINTED ISLANDS

1250.01 PAVEMENT MARKER SPACING

1251.01 RAISED PAVEMENT MARKERS - PERMANENT AND TEMPORARY

1253.01 SNOWPLOWABLE RAISED PAVEMENT MARKERS

1605.01 TEMPORARY SILT FENCE

LIST OF APPLICABLE CITY OF WILMINGTON STANDARD DRAWINGS:

SD 1-04 TYPICAL ROAD REBUILD

SD 1-05 PAVEMENT REPAIRS

SD 1-07 PIPE TRENCH

SD 3-03 RESIDENTIAL DRIVEWAY SD 3-09 INTERSECTION LAYOUT

SD 3-10 SIDEWALK

SD 3-11 CURBING

SD 8-18 DRIVEWAY RIGHT TURN LANE WITH CURB

SD 8-20 LEFT TURN LANE WIDENING

SD 8-22 LEFT TURN LANES

SD 11-01 PAVEMENT MARKINGS LINE TYPES

SD 11-02 PAVEMENT MARKING OFFSETS

SD 11-03 GUIDELINES FOR PAVEMENT MARKINGS AND SYMBOLS SD 11-04 PAVEMENT MARKINGS NON-SIGNAL INTERSECTIONS

SD 11-06 PAVEMENT MARKINGS SIGNALED INTERSECTIONS

SD 11-09 PAVEMENT MARKINGS TURN LANES

SD 11-10 PAVEMENT MARKINGS TURN LANES

SD 15-03 STREET & TRAFFIC SIGNS

NOTES

THE CITY ENGINEERING DEPARTMENT PREFERS THE USE OF NCDOT ROADWAY STAND DRAWINGS FOR PUBLIC DRAINAGE INFRASTRUCTURE WITHIN CITY STREETS.

SD 1-17 FLARED END SECTION

SD 2-01 CATCH BASIN

SD 2-15 PIPE OUTLET PROTECTION

SD 2-24 PRECAST DRAINAGE BOX SOLID

SD 2-24a PRECAST DRAINAGE STRUCTURE SOLID BOX GENERAL NOTES

CALL 811 (3) WORKING DAYS BEFORE YOU DIG. Approved Construction Plan 1-22-20

Public Services • Engineering Division

City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

DESCRIPTION

REVISIONS ©2019 NORRIS & TUNSTALL


NORRIS & CONSULTING


18100

DES. JST CKD. TJC DRWN. SLF

DATE: 05/21/19








DRIVEWAY PROFILE


HORIZ. SCALE 1"=10' VERT. SCALE 1"=2'.

SEE SHEET C2




BIKE LANE MARKINGS
FHWA DOT
(NOT DRAWN TO SCALE)

*WHEN THE RIGHT THROUGH LANE IS DROPPED TO BECOME A RIGHT TURN ONLY LANE, THE BICYCLE LANE MARKINGS SHOULD STOP AT LEAST 100 FEET BEFORE THE BEGINNING OF THE RIGHT-TURN LANE. THROUGH BICYCLE LANE MARKINGS SHOULD RESUME TO THE LEFT OF THE RIGHT TURN ONLY LANE.



PROFILE
HORIZ. SCALE 1"=10'

VERT. SCALE 1"=2'.



HORIZ. SCALE 1"=10' VERT. SCALE 1"=2'.

Public Services • Engineering Division

APPROVED STORMWATER MANAGEMENT PLAN

Date: 123 200 Permit # 2018027 18 R 2

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

NORRIS &
— CONSULTING
— CONSULTING
1900 EASTWOOD ROAD,
SUITE 11
WILMINGTON, NC 28401


TUNSTALL ENGINEERS P.C.

TYPICAL CROSS SECTIONS WOODLANDS ROAD IMPROVEMENTS WILMINGTON, NC


DES. JST CKD. TJC DRWN. SLF



C1.



1900 EAST SUITE 11 WILMING



LEGEND:

SET IRON CONC. MONUMENT FIRE HYDRANT BACK FLOW PREVENTER SANITARY SEWER MANHOLE STORM DRAINAGE MANHOLE CURB INLET DROP INLET WATER METER WATER VALVE GAS VALVE IRRIGATION CONTROL VALVE ELECTRIC PEDESTAL TELEPHONE PEDESTAL CABLE TV PEDESTAL FIBER OPTIC MARKER BURIED CABLE MARKER LIGHT POLE POWER POLE W/GUY ADJACENT PROPERTY LINE ---- EASEMENT LINE SUBJECT TRACT BOUNDARY LINE

LEGEND: PROPOSED

______ STORM DRAIN --- UG ---- UG ---- UNDERGROUND GAS LINE

CURB INLET W/ EROSION CONTROL JUNCTION BOX

- TRF - TRF - UNDERGROUND TRAFFIC SIGNAL LINE

NOTES:


1. INDEPENDENCE BLVD. AND ECHO FARMS BLVD. ARE CITY OF WILMINGTON STREETS. ALL WORK SHALL BE DONE IN ACCORDANCE WITH CITY STANDARDS. COORDINATE ALL WORK WITH THE CITY OF WILMINGTON.


2. TRAFFIC CONTROL PLAN SHALL BE PREPARED BY LICENSED NC ENGINEER AND PROVIDED BY THE CONTRACTOR. CONTRACTOR WILL BE RESPONSIBLE FOR OBTAINING CITY OF WILMINGTON RIGHT OF WAY PERMIT PRIOR TO ANY WORK IN CITY RIGHT OF WAY.


3. PRE-CONSTRUCTION MEETING WITH CITY OF WILMINGTON ENGINEERING TRAFFIC DEPARTMENT WILL BE REQUIRED PRIOR TO ANY CONSTRUCTION.

4. ALL WORK SHALL BE DONE IN ACCORDANCE WITH CITY STANDARDS. COORDINATE ALL WORK WITH THE CITY OF WILMINGTON.

5. ADJUST ALL UTILITY (WATER, SEWER & STORMWATER) VALVE BOXES & MANHOLES AS REQUIRED FOR ASPH. OVERLAY, NEW ASPH OR W/IN SHOULDER & SLOPES







SCALE: 1"=30"

Approved Construction Plan 122/20

W 5milos 1-22-20 Date: 1 23 /2020 Permit # 2018027 PR

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

NORRIS &


CONSULTING

18100 DES. JST CKD. TJC

DRWN. SLF DATE: 9/25/19



C3



LEGEND:

EXISTING IRON SET IRON CONC. MONUMENT FIRE HYDRANT BACK FLOW PREVENTER SANITARY SEWER MANHOLE SANITARY SEWER CLEANOUT STORM DRAINAGE MANHOLE CURB INLET DROP INLET WATER METER WATER VALVE GAS VALVE IRRIGATION CONTROL VALVE ELECTRIC PEDESTAL TELEPHONE PEDESTAL

CABLE TV PEDESTAL FIBER OPTIC MARKER BURIED CABLE MARKER LIGHT POLE SPOT LIGHT POWER POLE W/GUY

ADJACENT PROPERTY LINE ---- EASEMENT LINE SUBJECT TRACT BOUNDARY LINE ---- x---- x---- FENCE LINE

STORM DRAIN --- UG ---- UG --- UNDERGROUND GAS LINE - TRF --- TRF --- TRF -- UNDERGROUND TRAFFIC SIGNAL LINE

LEGEND: PROPOSED

CURB INLET W/ EROSION CONTROL DROP INLET W/ EROSION CONTROL JUNCTION BOX

NOTES:

1. INDEPENDENCE BLVD. AND ECHO FARMS BLVD. ARE CITY OF WILMINGTON STREETS. ALL WORK SHALL BE DONE IN ACCORDANCE WITH CITY STANDARDS. COORDINATE ALL WORK WITH THE CITY OF WILMINGTON.

2. TRAFFIC CONTROL PLAN SHALL BE PREPARED BY LICENSED NC ENGINEER AND PROVIDED BY THE CONTRACTOR. CONTRACTOR WILL BE RESPONSIBLE FOR OBTAINING CITY OF WILMINGTON RIGHT OF WAY PERMIT PRIOR TO ANY WORK IN CITY RIGHT OF WAY.


3. PRE-CONSTRUCTION MEETING WITH CITY OF WILMINGTON ENGINEERING TRAFFIC DEPARTMENT WILL BE REQUIRED PRIOR TO ANY CONSTRUCTION.

4. ALL WORK SHALL BE DONE IN ACCORDANCE WITH CITY STANDARDS. COORDINATE ALL WORK WITH THE CITY OF WILMINGTON.

5. ADJUST ALL UTILITY (WATER, SEWER & STORMWATER) VALVE BOXES & MANHOLES AS REQUIRED FOR ASPH. OVERLAY, NEW ASPH OR W/IN SHOULDER & SLOPES

SEE SHEET C3 FOR INDEPENDENCE BLVD. SOUTH


IMPROVEMENTS



:=(N)======: (60' ROW - CITY OF WILMINGTON ROAD)

EXISTING CONDITIONS - ECHO FARMS BLVD.

SCALE: 1"=20'



PROPOSED ROAD IMPROVEMENTS - ECHO FARMS BLVD.

SCALE: 1"=20'

ECHO FARMS BLVD. & INDEPENDENCE BLVD. woodlands Road IMPROVEMENTS WILMINGTON, NC

BY

DESCRIPTION

SYMBOL DATE

NORRIS & — CONSULTING


18100


DES. JST CKD. TJC DRWN. SLF

DATE: 05/21/19


APPROVED STORMWATER MANAGEMENT PLAN







G:\projects\2018\18100 Echo Forms Offsite Improve\18100 Plans\dwg\18100_Master_r4.dwg, 9/25/2019 1



SET IRON CONC. MONUMENT FIRE HYDRANT BACK FLOW PREVENTER SANITARY SEWER MANHOLE SANITARY SEWER CLEANOUT STORM DRAINAGE MANHOLE CURB INLET DROP INLET WATER METER WATER VALVE GAS VALVE IRRIGATION CONTROL VALVE ELECTRIC PEDESTAL TELEPHONE PEDESTAL CABLE TV PEDESTAL FIBER OPTIC MARKER BURIED CABLE MARKER

SPOT LIGHT

SPOT LIGHT

POWER POLE W/GUY

CENTER LINE

R/W LINE

ADJACENT PROPERTY LINE

EASEMENT LINE

SUBJECT TRACT BOUNDARY LINE

LEGEND: PROPOSED

FES
CURB INLET W/ EROSION CONTROL
DROP INLET W/ EROSION CONTROL
JUNCTION BOX
CENTER LINE

R/W LINE
SILT FENCE LINE
LOD
STORM DRAIN PIP

2

TREE TO BE REMOVED

NOTES:


1. INDEPENDENCE BLVD. AND ECHO FARMS BLVD. ARE CITY OF WILMINGTON STREETS. ALL WORK SHALL BE DONE IN ACCORDANCE WITH CITY STANDARDS. COORDINATE ALL WORK WITH THE CITY OF WILMINGTON.

2. TRAFFIC CONTROL PLAN SHALL BE PREPARED BY LICENSED NC ENGINEER AND PROVIDED BY THE CONTRACTOR. CONTRACTOR WILL BE RESPONSIBLE FOR OBTAINING CITY OF WILMINGTON RIGHT OF WAY PERMIT PRIOR TO ANY WORK IN CITY RIGHT OF WAY.

3. PRE-CONSTRUCTION MEETING WITH CITY OF WILMINGTON ENGINEERING TRAFFIC DEPARTMENT WILL BE REQUIRED PRIOR TO ANY CONSTRUCTION.

4. ALL WORK SHALL BE DONE IN ACCORDANCE WITH CITY STANDARDS. COORDINATE ALL WORK WITH THE CITY OF WILMINGTON.

5. ADJUST ALL UTILITY (WATER, SEWER & STORMWATER) VALVE BOXES & MANHOLES AS REQUIRED FOR ASPH. OVERLAY, NEW ASPH OR W/IN SHOULDER & SLOPES



ECHO FARMS BLVD. & GEORGE ANDERSON DR. INTERSECTION

SCALE: 1"=30'

Approved Construction Plan

Planning

Planning

Traffic

Fire

What

Plan | 1 | 22 | 25 |

Approved Construction Plan

Public Services • Engineerin

Approved STORMWATER MANAGE

Approved Construction Plan

Public Services • Engineerin

Approved Construction Plan

Signed:

Approved Construction Plan

Public Services • Engineerin

Approved Construction Plan

Public Services • Engineerin

Approved Construction Plan

Public Services • Engineerin

Approved Construction Plan

Approved Construction Plan

Public Services • Engineerin

Approved Construction Plan

Approved Construction Plan

Approved Construction Plan

Public Services • Engineerin

Approved Construction Plan


Approved Construction Plan

Approved Construction Plan

Public Services • Engineerin

Approved Construction Plan

Appro



PROPOSED ROAD IMPROVEMENT
ECHO FARMS BLVD. & GEORGE ANDERSON DR. INTERSECTION

SCALE: 1"=30"



NORRIS & TUNSTALL

NORRIS & TUNSTALL

FORS

52 56 00

1900 EASTWOOD ROAD, 1429 ASH-LITTLE RIVER RD. NW
SUITE 11 ASH, NC 28420

For each open utility cut of

City streets, a \$325 permit


shall be required from the City prior to occupancy and/or project acceptance.

ojects\2018\18100 Echo Farms Offsite improve\18100 Pians\


C7


DRWN. SLF

DATE: 9/25/19



C8






IMPROVEMENTS

NOTES:

1. CAROLINA BEACH ROAD IS A NCDOT HIGHWAY.

2. PRIOR TO ANY WORK WITHIN NCDOT RIGHT OF WAY, A PRE-CONSTRUCTION MEETING SHALL BE HELD WITH NCDOT.

3. TRAFFIC CONTROL PLANS BY A NC REGISTERED ENGINEER MAYBE REQUIRED BY NCDOT.



SCALE: 1"=30"

TUNSTALI ENGINEERS P.C. —

NORRIS &

CONSULTING

18100

DES. JST CKD. TJC DRWN. SLF

DATE: 05/21/19



1/22/20

Traffic W Sompos 7-22-20

SCALE: 1" = 30'

1. THE CONTRACTOR SHALL VISIT THE SITE TO BECOME FAMILIAR WITH FIELD

2. CONTRACTOR SHALL COORDINATE WORK WITHIN NCDOT AND LOCAL CITY RIGHT OF WAYS WITH PROPER AUTHORITIES AND SHALL MEET ANY REQUIREMENTS AS TO TRAFFIC CONTROL AND CONNECTION TO EXISTING STREETS.

3. CLEARING AND GRUBBING: SEE SPECIFICATIONS.

4. STRIPPING: SEE SPECIFICATIONS.

5. MUCKING: SEE SPECIFICATIONS.

6. DISPOSAL: SEE SPECIFICATIONS.

7. BORROW MATERIAL: THE CONTRACTOR SHALL FURNISH BORROW MATERIAL REQUIRED FROM OFF SITE AND OBTAIN ALL REQUIRED PERMITS ASSOCIATED WITH BORROW OPERATIONS.

8. FILL AND COMPACTION: SEE SPECIFICATIONS.

9. LAYOUT: THE CONTRACTOR SHALL PROVIDE ALL LAYOUT REQUIRED TO

10. THE CONTRACTOR IS RESPONSIBLE FOR THE LOCATION AND PROTECTION OF EXISTING UTILITIES DURING CONSTRUCTION.

11. EXISTING BOUNDARY AND TOPOGRAPHIC INFORMATION FROM SURVEY BY

BATEMAN CIVIL SURVEY COMPANY, AND PROVIDED BY OWNER.

12. THE CONTRACTOR SHALL VERIFY DIMENSIONS AT JOBSITE.

13. THE CONTRACTOR IS RESPONSIBLE FOR THE COORDINATION OF RELOCATION OR DISCONNECTION OF ALL EXISTING UTILITIES WITH APPLICABLE

14. ALL PAVEMENT AND BASE MATERIALS AND WORKMANSHIP SHALL CONFORM TO NCDOT STANDARDS.

15. WATER AND SEWER SERVICES SHALL BE INSTALLED TO MEET LOCAL AND STATE PLUMBING CODES. METER AND TAPS SHALL MEET ALL LOCAL

16. ALL AREAS SHALL BE GRADED FOR POSITIVE DRAINAGE.

17. CONTRACTOR SHALL NOTE THAT EARTHWORK QUANTITIES ARE HIS RESPONSIBILITY. PLANS DO NOT REPRESENT A BALANCED EARTHWORK

18. REINF. CONC. PIPE SHALL BE CLASS III W/RUBBER GASKETED JOINT OR "RAM NECK". INSTALL PER MANUFACTURER'S REQUIREMENTS.

EROSION CONTROL NOTES AND MAINTENANCE PLAN:

1. ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL, BUT IN NO CASE, LESS THAN ONCE EVERY WEEK AND WITHIN 24 HOURS OF EVERY HALF-INCH RAINFALL.

2. ALL POINTS OF EGRESS WILL HAVE CONSTRUCTION ENTRANCES THAT WILL BE PERIODICALLY TOP-DRESSED WITH AN ADDITIONAL 2 INCHES OF #4 STONE TO MAINTAIN PROPER DEPTH. THEY WILL BE MAINTAINED IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM LEAVING THE SITE. IMMEDIATELY REMOVE OBJECTIONABLE MATERIAL SPILLED WASHED OR TRACKED ONTO THE CONSTRUCTION ENTRANCE OR ROADWAYS.


SEDIMENT WILL BE REMOVED FROM HARDWARE CLOTH AND GRAVEL INLET PROTECTION, BLOCK AND GRAVEL INLET PROTECTION, ROCK DOUGHNUT INLET PROTECTION AND ROCK PIPE INLET PROTECTION WHEN THE DESIGNED STORAGE CAPACITY HAS BEEN HALF FILLED WITH SEDIMENT. ROCK WILL BE CLEANED OR REPLACED WHEN THE SEDIMENT POOL NO LONGER DRAINS AS DESIGNED. DEBRI WILL BE REMOVED FROM THE ROCK AND HARDWARE CLOTH TO ALLOW PROPER DRAINAGE. SILT SACKS WILL BE EMPTIED ONCE A WEEK AND AFTER EVERY RAIN EVENT. SEDIMENT WILL BE REMOVED FROM AROUND WATTLES, BEAVER DAMS, DANDY SACKS AND SOCKS ONCE A WEEK AND AFTER EVERY RAIN EVENT.

4. DIVERSION DITCHES WILL BE CLEANED OUT IMMEDIATELY TO REMOVE SEDIMENT OR OBSTRUCTIONS FROM THE FLOW AREA. THE DIVERSION RIDGES WILL ALSO BE REPAIRED. SWALES MUST BE TEMPORARILY \$TABILIZED WITHIN 21 CALENDAR DAYS OF CEASE OF ANY PHASE OF ACTIVITY ASSOCIATED WITH A

SEDIMENT WILL BE REMOVED FROM BEHIND THE SEDIMENT FENCE WHEN IT BECOMES HALF FILLED. THE SEDIMENT FENCE WILL BE REPAIRED AS NECESSARY TO MAINTAIN A BARRIER. STAKES MUST BE STEEL. STAKE SPACING WILL BE 6 FEET MAX. WITH THE USE OF EXTRA STRENGTH FABRIC, WITHOUT WIRE BACKING STAKE SPACING WILL BE 8 FEET MAX. WHEN STANDARD STRENGTH FABRIC AND WRE BACKING ARE USED. IF ROCK FILTERS ARE DESIGNED AT LOW POINTS IN THE SEDIMENT FENCE, THE ROCK WILL BE REPAIRED OR REPLACED IF IT BECOMES HALF-FULL OF SEDIMENT, NO LONGER DRAINS AS DESIGNED OR IS DAMAGED.

6. LAND QUALITY REQUIRES;
ALL SEEDED AREAS WILL BE FERTILIZED, RESEEDED AS NECESSARY, AND MULCHED, ACCORDING TO SPECIFICATIONS IN THE VEGETATIVE PLAN, TO MAINTAIN A VIGOROUS, DENSE VEGETATIVE COVER. ALL SLOPES WILL BE STABILIZED WITHIN 21 CALENDAR DAYS. ALL OTHER AREAS WILL BE STABILIZED WITHIN 15 WORKING

WATER QUALITY REQUIRES;
ALL SEEDED AREAS WILL BE FERTILIZED, RESEEDED AS NECESSARY AND MULCHED ACCORDING TO SPECIFICATIONS IN THE VEGETATIVE PLAN TO MAINTAIN A VIGOROUS, DENSE VEGETATIVE COVER. ALL PERIMETER DIKES, SWALES, DITCHES, PERIMETER SLOPES, ALL SLOPES STEEPER THAN 3' HORIZONTAL TO 1' VERTICAL (3:1) AND ALL HIGH QUALITY WATER (HQW) ZONES SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN SEVEN (7) CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY. ALL OTHER DISTURBED AREAS SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN FOURTEEN (14) CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY.



TEMPORARY ROCK DAM DETAIL

TEMPORARY SEEDING RECOMMENDATIONS FOR FALL SEEDING MIXTURE RATE (lb/gcre)

SEEDING DATES: MOUNTAINS - AUG. 15 - DEC. 15 COASTAL PLAIN AND PIEDMONT - AUG. 15 - DEC. 15

SOIL AMENDMENTS: FOLLOW SOIL TEST OR APPLY 2,000 Ib/acre GROUND AGRICULTURAL LIMESTONE AND 1,000 lb/acre 10-10-10 FERTILIZER.

APPLY 4,000 Ib/acre STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.

MAINTENANCE: REPAIR AND REFERTILIZE DAMAGE AREAS IMMEDIATELY. TOP DRESS WITH MILLET OR 15 lbs/dcre SUDANGRASS. PRIOR TO MAY 1 OR AFTER AUG. 15 50 Ib/acre OF NITROGEN IN MARCH, IF IT IS NECESSARY TO EXTEND TEMPORARY COVER BEYOND JUNE 15, OVERSEED WITH 50 Ib/acre KOBE ADD 25 Ibs/acre RYE (GRAIN). (PIEDMONT AND COASTAL PLAIN) OR KOREAN (MOUNTAINS) LESPEDEZA II LATE FEBRUARY OR EARLY MARCH.

TEMPORARY SEEDING RECOMMENDATIONS FOR SUMMER

SEEDING MIXTURE

RATE (lb/gcre) (lb/1000 sf)

THE PIEDMONT AND MOUNTAINS, A SMALL-STEMMED SUDANGRASS MAY MULCH: BE SUBSTITUTED AT A RATE OF 50 lb/acre.

SEEDING DATES; MOUNTAINS - MAY 15 - AUG. 15 PIEDMONT - MAY 1 - AUG. 15 COASTAL PLAIN - APR. 15 - AUG. 15

SOIL AMENDMENTS: FOLLOW RECOMMENDATIONS OF SOIL TESTS OR APPLY 2,000 lb/gcre GROUND AGRICULTURAL LIMESTONE AND 750 lb/ocre 10-10-10 FERTILIZER.

APPLY 4,000 Ib/acre STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT,
NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET
AND EARLY SUMMER

AND EARLY SUMMER

REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.

TEMPORARY SEEDING RECOMMENDATIONS FOR LATE WINTER

AND EARLY SPRING

N MOUNTAINS)

SPECIES RATE (lb/gcre) (lb/1000 af) ANNUAL LESPEDEZA (KOBE IN PIEDMONT AND COASTAL PLAIN, KOREAN

OMIT ANNUAL LESPEDEZA WHEN DURATION OF TEMPORARY COVER IS NOT TO EXTEND BEYOND JUNE.

ABOVE 2,500 FEET: FEB. 15 - MAY 15 BELOW 2,500 FEET: FEB. 1 - MAY 1 PIEDMONT -JAN. 1 - MAY 1 COASTAL PLAIN DEC. 1 - APRIL 15

SOIL AMENDMENTS: FOLLOW RECOMMENDATIONS OF SOIL TESTS OR APPLY 2,000 lb/gcre GROUND AGRICULTURAL LIMESTONE AND 750 lb/acre 10-10-10 FERTILIZER.

APPLY 4,000 Ib/gcre STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, WHERE A NEAT APPEARANCE IS DESIRED, OMIT SERICEA AND MOW AS OFTEN AS NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.

EFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.

ROCK DAM NOTES:

CLEAR THE AREAS UNDER THE EMBANKMENT AND STRIP OF ROOTS AND OTHER OBJECTIONABLE MATERIAL DELAY CLEANING THE RESEVIOR AREA UNTIL THE DAM IS IN PLACE.

2. COVER THE FOUNDATION AREA INCLUDING THE ABUTMENTS WITH EXTRA-STRENGTH FILTER FABRIC BEFORE BACKFILLING WITH ROCK. IF A CUTOFF TRENCH IS REQUIRED, EXCAVATE AT CENTERLINE OF DAM, EXTENDING ALL THE WAY UP THE EARTH ABUTMENTS. APPLY FILTER FABRIC UNDER THE ROCKFILL EMBANKMENT FROM THE UPSTREAM EDGE OF THE DAM TO THE DOWNSTREAM EDGE OF THE APRON, OVERLAP FILL MATERIAL A MINIMUM OF 1 FOOT AT ALL JOINTS, WITH THE UPSTREAM STRIP.

3. CONSTRUCT THE EMBANKMENT WITH WELL-GRADED ROCK AND GRAVEL TO THE SIZE AND DIMENSIONS SHOWN ON THE DRAWINGS. IT IS IMPORTANT THAT ROCK ABUTMENTS BE AT LEAST 2 FEET HIGHER THAN THE SPILLWAY CREST AND AT LEAST 1 FOOT HIGHER THAN THE DAM, ALL THE WAY TO THE DOWNSTREAM TOE, TO PREVENT SCOUR AND EROSION AT THE ABUTMENTS.

4. SEDIMENT—LADEN WATER FROM THE CONSTRUCTION SITE SHOULD BE DIVERTED INTO THE BASIN RESERVOIR AT THE FURTHEST AREA FROM THE DAM.

5. CONSTRUCT THE ROCK DAM BEFORE THE BASIN AREA IS CLEARED TO MINIMIZE SEDMENT YIELD FROM CONSTRUCTION OF THE BASIN. IMMEDIATELY STABILIZE ALL AREAS DISTURBED DURING THE

CHECK SEDIMENT BASINS AFTER EACH RAINFALL REMOVE SEDIMENT AND RESTORE ORIGINAL VOLUME WHEN SEDIMENT ACCUMULATES TO ABOUT ONE—HALF THE DESIGN VOLUME, SEDIMENT SHOULD BE PLACED ABOVE THE BASIN AND ADEQUATELY STABILIZED.

CHECK THE STRUCTURE FOR EROSION, PIPING, AND ROCK DISPLACEMENT WEEKLY AND AFTER EACH SIGNIFICANT (1/2" OR

REMOVE THE STRUCTURE AND ANY UNSTABLE SEDIMENT IMMEDIATELY AFTER THE CONSTRUCTION SITE HAS BEEN PERMANENTLY STABILIZED, SMOOTH THE BASIN SITE TO BLEND WITH THE SURROUNDING AREA AND STABILIZE ALL WATER AND SEDIMENT SHOULD BE REMOVED FROM THE BASIN PRIOR TO DAM REMOVAL SEDIMENT SHOULD BE PLACED IN DESIGNATED DISPOSAL AREA SAND NOTAL MICHAEL TO BE OWNED STREAMS OF PROMISES.

ND NOT ALLOWED TO FLOW INTO STREAMS OR DRAINAGE AREAS URING STRUCTURE REMOVAL

GREATER) RAINSTORM AND REPAIR IMMEDIATELY.

6. SAFETY — SEDIMENT BASINS SHOULD BE CONSIDERED DANGEROUS BECAUSE THEY ATTRACT CHILDREN. STEEP SIDE SLOPES SHOULD BE AVOIDED, FENCES WITH WARNING SIGNS MAY BE NEEDED IF TRESPASSING IS LIKELY, ALL STATE AND LOCAL REQUIREMENTS MUST BE FOLLOWED.

PERMANENT SEEDING RECOMMENDATIONS FOR FALL AND **EARLY SPRING** SEEDING MIXTURE SPECIES TALL FESCUE RATE (lb/gcre) (lb/1000 sf PENSACOLA BAHIAGRASS SERICEA LESPEDEZA KOBE LESPEDEZA

1. FROM SEPT. 1 THRU MAR. 1, USE UNSCARIFIED SERICEA SEED. 2. ON POORLY DRAINED SITES OMIT SERICEA AND INCREASE KOBE TO 30 lbs/gcre.
3. WHERE A NEAT APPEARANCE IS DESIRED, OMIT SERICEA AND INCREASE

KOBE TO 40 lbs/acre. NURSE PLANTS: BETWEEN APR. 15 AND AUG. 15, ADD 10 lbs/gcre GERMAN

BEST POSSIBLE
FEB 15-MAR. 20 FEB.15-APR. 30
SEPT. 1-SEPT. 30 SEPT. 1-OCT. 31

APPLY LIME AND FERTILIZE ACCORDING TO SOIL TESTS, OR APPLY 3,000-5,000 lbs/acre (68.9-114.8 lbs/1,000 sf) GROUND AGRICULTURAL LIMESTONE (USE THE LOWER RATE ON SANDY SOILS) AND 1,000 lbs/acre (22.9 lbs/1,000 sf) 10-10-10 FERTILIZER.

APPLY 4,000 Ib/ocre (91.8 Ibs/1,000 sf) GRAIN STRAW OR EQUIVALENT COVER OF ANOTHER SUITABLE MULCH. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR ROVING OR BY CRIMPING WITH A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING

MAINTENANCE: IF GROWTH IS LESS THAN FULLY ADEQUATE, REFERTILIZE IN THE SECOND YEAR, ACCORDING TO SOIL TESTS OR TOPDRESS WITH 500 lbs/ggre (11.5 lbs/1,000 f) 10-10-10 FERTILIZER. MOW AS NEEDED WHEN SERICEA IS OMITTED FROM THE MIXTURE. RESEED, FERTILIZE, AND MULCH DAMAGED AREAS IMMEDIATELY.

SEEDING MIXTURE

SPECIES RATE (Ib/ggre)
PENSACOLA BAHIAGRASS 50 (lb/1000 af) SERICEA LESPEDEZA COMMON BERMUDA


. WHERE A NEAT APPEARANCE IS DESIRED, OMIT SERICEA. 2. USE COMMON BERMUDAGRASS ONLY ON ISOLATED SITES WHERE IT CANNOT BECOME A PEST. BERMUDAGRASS MAY BE REPLACED WITH 5 lbs/ocre

SEEDING DATES: APRIL 1-JULY 15 SOIL AMENDMENTS

APPLY LIME AND FERTILIZE ACCORDING TO SOIL TESTS, OR APPLY 3,000 lbs/gcre (68.9 lbs/1,000 sf) GROUND AGRICULTURAL LIMESTONE AND 500 lbs/gcre (11.5 lbs/1,000 sf) 10-10-10 FERTILIZER.

APPLY 4,000 Ib/acre (91.8 Ibs/1,000 sf) GRAIN STRAW OR EQUIVALENT COVER OF ANOTHER SUITABLE MULCH. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR ROVING OR BY CRIMPING WITH A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING

REFERTILIZE THE FOLLOWING APRIL WITH 50 lbs/acre (1.15 lbs/1,000 st)
NITROGEN. REPEAT AS GROWTH REQUIRES. MAY BE MOWED ONLY ONCE A YEAR.



2. BUILDING WASTES HANDLING

NO PAINT OR LIQUID WASTES IN STREAM OR STORM DRAINS DEDICATED AREA FOR DEMOLITION, CONSTRUCTION AND OTHER WASTES MUST BE LOCATED 50' FROM STORM DRAINS

AND STREAMS UNLESS NO ALTERNATIVE IS AVAILABLE. EARTHEN MATERIALS STOCKPILES MUST BE LOCATED 50' FROM STORM DRAINS AND STREAMS UNLESS NO REASONABLE ALTERNATIVE IS AVAILABLE

CONCRETE MATERIALS MUST BE CONTROLLED TO AVOID CONTACT WITH SURFACE WATERS, WETLANDS, OR BUFFERS.

 SAME WEEKLY INSPECTION REQUIREMENTS . SAME RAIN GAUGE AND INSPECTIONS AFTER 0.5" RAIN


INSPECTIONS ARE ONLY REQUIRED DURING "NORMAL

BUSINESS HOURS' . RECORDS MUST BE KEPT FOR 3 YEARS AND AVAILABLE

UPON REQUEST . ELECTRONICALLY AVAILABLE RECORDS MAY BE SUBSTITUTED

UNDER CERTAIN CONDITIONS

 OUTLET STRUCTURES MUST WITHDRAW FROM BASIN SURFACE UNLESS DRAINAGE AREA IS LESS THAN ONE ACRE USE ONLY DWQ APPROVED FLOCCULANTS



1. SYN. FENCE FABRIC SHALL BE MIN. OF 30" IN WIDTH WITH 30 LB/IN TENSILE STRENGTH FOR STANDARD FABRIC AND 50 LB/IN FOR EXTRA STRENGTH.

2. FABRIC SHALL BE CONTINUOUS LENGTH, IF JOINTS ARE NECESSARY, LAP FABRIC POST TO POST.

3. STEEL POST SHALL BE MIN 4' IN HEIGHT AND BE OF THE SELF-FASTENER STEEL ANGLE TYPE.


TEMPORARY SILT FENCE N.T.S.

CONSTRUCTION SEQUENCE: 1. UNIFORMLY GRADE A SHALLOW DEPRESSION APPROACHING THE INLET. 2. DRIVE 5' STEEL POST 2' INTO THE GROUND SURROUNDING THE INLET. SPACE POST EVENLY AROUND THE PERIMETER OF THE INLET. A MAXIMUM OF 4' APART. S. SURROUND THE POST WITH WIRE MESH HARDWARE CLOTH. SECURE THE WIRE MESH TO THE STEEL POST AT THE TOP, MIDDLE AND BOTTOM, PLACING A 2' FLAP OF THE WIRE MESH UNDER THE GRAVEL FOR ANCHORING IS RECOMMENDED. 4. PLACE CLEAN GRAVEL (NCDOT #5 OR #57 STONE) ON A 2:1 SLOPE WITH A HEIGHT OF 16" TO 18" AROUND THE WIRE, AND SMOOTH TO AN EVEN GRADE. 5. ONCE THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE ACCUMULATED SEDIMENT,

AND ESTABLISH FINAL GRADING ELEVATIONS.

WITH GROUNDCOVER.

6. COMPACT THE AREA PROPERLY AND STABILIZE IT



SECTION A-A

NCDOT #5 OR --

CLEAR THE MESH WIRE OF ANY DEBRIS OR OTHER OBJECTS TO PROVIDE ADEQUATE FLOW FOR SUBSEQUENT RAINS. TAKE CARE NOT TO DAMAGE OR UNDERCUT THE WIRE MESH DURING SEDIMENT REMOVAL. REMOVE SEDIMENT WHEN ACCUMULATION REACHES HALF THE DEPTH OF ROCK. REPLACE STONE WHEN IT NO LONGER DRAINS AS

MAINTENANCE: INSPECT INLETS AT LEAST WEEKLY

AND AFTER EACH SIGNIFICANT (1/2

INCH OR GREATER) RAINFALL EVENT.

HARDWARE CLOTH AND GRAVEL INLET PROTECTION

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

SYMBOL DATE BY DESCRIPTION REVISIONS ©2019 NORRIS & TUNSTALL

Public Services • Engineering Division PPROVED STORMWATER MANAGEMENT PLAN 1/23 2020) Permit # 2018027 PA



NPDES-SPECIFIC PLAN SHEET NOTES

1. THIS PAGE IS SUBMITTED TO COMPLY WITH NPDES GENERAL STORMWATER PERMIT NC0010000.

2. THIS PAGE CAN BE APPROVED BY THE COUNTY PURSUANT TO NPDES GENERAL STORMWATER PERMIT NC0010000 ONLY.

3. THIS PAGE OF THE APPROVED PLANS IS ENFORCEABLE EXCLUSIVELY PURSUANT TO NPDES GENERAL STORMWATER PERMIT NC0010000. 4. THE COUNTY IS NOT AUTHORIZED TO ENFORCE THIS PAGE OF THE PLANS

AND IT IS NOT PART OF THE APPROVED PLANS FOR THE PURPOSES OF ENFORCEMENT ACTION UNDER THE CITY CODE. THE CRITICAL ROOT ZONE (CRZ) OF A TREE CROWN OF THE TREE IS NEEDED FOR LEAF S WHERE THE MAJORITY OF A TREE'S ROOTS GROWTH TO PRODUCE OXYGEN, FILTER THE AIR, REDUCE WIND AND SOFTEN NOISE AY. 85% OF MOST TREE ROOTS ARE FOUND O NOT DISFIGURE CROWN WITH INTENSIVE PRUNING.

THE TOP 24" OF THE SOIL AND SUPPLY THE MAJORITY OF NUTRIENTS AND WATER. GENERALLY, ROOTS SPREAD OUT 2-3X THE HEIGHT OF THE TREE DRANGE SAFETY FENCE OR ORANGE SILT FENCE (TYPICAL)


 PROTECT CRITICAL ROOT ZONE (CRZ) OF TREES PRIOR TO CONSTRUCTION. CLEARLY MARK THE TREES AND ERECT A PROTECTIVE BARRIER AT THE CRZ. BARRIER SHALL BE MAINTAINED UNTIL CONSTRUCTION IS COMPLETE. 2. CRZ RADIUS IS 1 FT PER INCH OF TREE DIAMETER AT BREAST HEIGHT (DBH).

3. IF CONSTRUCTION OCCURS WITHIN THE CRZ. AT LEAST 12" OF MULCH AND/OR LOGGING MATTS SHALL BE PLACED WHERE MACHINERY MANEUVERS TO REDUCE SOIL 4. WHERE SIDEWALKS AND PATHWAYS PASS WITHIN CRZ, EXTRA CARE SHALL BE TAKEN

TO AVOID DAMAGE TO THE ROOTS. ALTERNATE CONSTRUCTION METHODS, SUCH AS A REINFORCED SIDEWALK, SHALL BE IMPLEMENTED AS NECESSARY.

5. FOR ALL TREES, CUTTING OF LARGE STRUCTURAL ROOTS LOCATED NEAR THE BASE OF THE TRUNK IS PROHIBITED. DO NOT COMPACT SOIL BENEATH TREES. NO VEHICLE SHALL BE ALLOWED TO PARK UNDER TREES. NO MATERIALS OR EQUIPMENT SHALL BE STORED BENEATH TREES, DAMAGING THE BARK WITH LAWNMOWERS, CONSTRUCTION EQUIPMENT, OR ANYTHING ELSE IS PROHIBITED.

CONTRACTOR SHALL REPAIR DAMAGE TO TREES. . FAILING TO INSTALL OR MAINTAIN PROTECTION MEASURES SHALL RESULT IN A STOP WORK ORDER AND FINE OF \$500/DAY. DISTURBANCE OTHER THAN THAT ALLOWED ON THE APPROVED PLAN WILL REQUIRE OWNER TO POST A LETTER OF CREDIT FOR YRS FOR TREE MITIGATION.



TREE PROTECTION DETAIL

N.T.S.

TREE PROTECTION FENCING AND SIGNAGE SHALL BE REMOVED AFTER CONSTRUCTION.

ADDITIONAL SIGNS MAY BE REQUIRED BY CITY OF WILMINGTON, BASED ON ACTUAL

DETAILS AND NOTES WOODLANDS ROAD IMPRIMINGTON, NC

RRIS & CONSULTING

JORRI

18100

DES. JST CKD. TJC DRWN. SLF

DATE: 05/21/19

activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction

	Re	equired Ground Stabil	ization Timeframes	
Site Area Description		Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations	
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None	
(b)	High Quality Water (HQW) Zones	7	None	
(c)	Slopes steeper than 3:1	7	If slopes are 10° or less in length and are not steeper than 2:1, 14 days are allowed	
(d)	Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed	
(e)	Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zone: -10 days for Falls Lake Watershed unless there is zero slope	

ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing ictivity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

Shrubs or other perm

retaining walls

SROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

- Iemporary grass seed covered with straw or
 Permanent grass seed covered with straw or
- Hydroseeding Rolled erosion control products with or
- without temporary grass seed
- Appropriately applied straw or other mulch
- with mulch sufficient to restrain e . Structural methods such as concrete, asphalt or
- Rolled erosion control products with grass seed POLYACRYLAMIDES (PAMS) AND FLOCCULANTS
- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures Apply flocculants at the concentrations specified in the NC DWR List of Approved
- PAMS/Flocculants and in accordance with the manufacturer's instructions. Provide ponding area for containment of treated Stormwater before discharging
- Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

- Maintain vehicles and equipment to prevent discharge of fluids. Provide drip pans under any stored equipment.
- 3. Identify leaks and repair as soon as feasible, or remove leaking equipment from the Collect all spent fluids, store in separate containers and properly dispose as
- hazardous waste (recycle when possible) Remove leaking vehicles and construction equipment from service until the problem
- Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum produc to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WAST

- Never bury or burn waste. Place litter and debris in approved waste containers.
- receptacle) on site to contain construction and domestic waste Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland. Cover waste containers at the end of each workday and before storm events or
- provide secondary containment. Repair or replace damaged waste containers. Anchor all lightweight items in waste containers during times of high winds. Empty waste containers as needed to prevent overflow. Clean up immediately if
- containers overflow.

waters unless no other alternatives are reasonably available.

Dispose waste off-site at an approved disposal facility. 9. On business days, clean up and dispose of waste in designated waste containers.

- **PAINT AND OTHER LIQUID WASTE** . Locate paint washouts at least 50 feet away from storm drain inlets and surface
- Contain liquid wastes in a controlled area. . Containment must be labeled, sized and placed appropriately for the needs of site. 5. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelera erosion on disturbed soils for temporary or permanent control needs.



- Do not discharge concrete or cement slurry from the site.
- Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
- Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project. Locate washouts at least 50 feet from storm drain inlets and surface waters unless it
- can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority. Install at least one sign directing concrete trucks to the washout within the project
- limits. Post signage on the washout itself to identify this location. Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
- At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

- . Store and apply herbicides, pesticides and rodenticides in accordance with label
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately. 4. Do not stockpile these materials onsite.

- Place hazardous waste containers under cover or in secondary containment Do not store hazardous chemicals, drums or bagged materials directly on the ground.



EFFECTIVE: 04/01/19

PART III

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspection were delayed shall be noted in the Inspection Record.

SELF-INSPECTION, RECORDKEEPING AND REPORTING

Inspect	(during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend of holiday periods, and no individual-day rainfall information it available, record the cumulative rain measurement for those un attended days (and this will determine if a size impection inceded). Days on which no rainfall occurred shall be recorded a "zero." The permettee may use another rain-monitoring device approved by the Division.
(2) EBSC Measures	At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours	Identification of the measures inspected, Oute and time of the inspection, Name of the person performing the inspection, Indication of whether the measures were operating properly, Description of maintenance needs for the measure, Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	Identification of the discharge outfalls inspected, Date and time of the inspection, Name of the person performing the inspection, Evidence of indicators of stormwater pollution such as off sheen, floating or suspended solids or discoloration, Indication of visible ecdiment learing the site, Description, evidence, and date of corrective actions taken,
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours.	If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean upon stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future release.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wedand has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit of this permit.
(6) Ground stabilization measures	After each phase of grading	The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all larid-disturbing activity, construction or redevelopment, permanent ground cover). Documentation that the required ground stabilization measures have been provided within the required timeframe or an account of the stabilization of the st

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be documented in the manner

SELF-INSPECTION, RECORDKEEPING AND REPORTING

Item to Document	Documentation Requirements
(a) Each E&SC Measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC Plan.	Initial and date each E&SC Measure on a copy of the approved E&SC Plan or complete, date and sign an inspection report that lists each E&SC Measure shown on the approved E&SC Plan. This documentation is required upon the initial installation of the E&SC Measures or if the E&SC Measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC Plan.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC Measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC Measures.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

requirement not practical:

In addition to the E&SC Plan documents above, the following items shall be kept on the and available for agency inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this

- (a) This general permit as well as the certificate of coverage, after it is received.
- (b) Records of inspections made during the previous 30 days. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.
- All data used to complete the Notice of Intent and older inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION C: REPORTING 1. Occurrences that must be reported

Permittees shall report the following occurrences: (a) Visible sediment deposition in a stream or wetland.

- They are 25 gallons or more,
- They are less than 25 gallons but cannot be cleaned up within 24 hours, They cause sheen on surface waters (regardless of volume), or
- Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.
- Anticipated bypasses and unanticipated bypasses.
- (c) Noncompliance with the conditions of this permit that may endanger health or the

. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Division's Emergency Response personnel at (800) 662-7956, (800) 858-0368 or (919) 733-3300.


O'CCMI BIRCE	heaporture remembres (virter procuvery) and Other Medintements
(a) Visible sediment deposition in a stream or wetland (b) Oil spills and release of hazardous substances per Item 1(b)-(c) above	Within 24 hours, an oral or electronic notification. Within 7 calender days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permitter may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions. Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.
(c) Anticipated bypasses [40 CFR 122.41(m)(3)]	 A report of least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and effect of the bypass.
(d) Unanticipated bypasses (40 CFR 122.41(m)(3))	Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass.
(e) Noncompliance with the conditions of this permit that may endanger health or the environment[40 CFR 122.41(i)(7)]	Within 24 hours, an oral or electronic notification Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. (40 CFR 122 41(1)(6) Division staff may waive the requirement for a written report on a case-by-case basis.



NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

SYMBOL DATE BY DESCRIPTION REVISIONS ©2019 NORRIS & TUNSTALL



Approved Construction Plan

18100

DETAILS AND NOTES
WOODLANDS ROAD IMPROVEMENTS
WILMINGTON, NC

DES. JST CKD. TJC DRWN. SLF

DATE: 10/01/19



APPROVED STORMWATER MANAGEMENT PLAN For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

