


WOODLANDS AT ECHO FARMS TRACT 2


4114 ECHO FARMS BLVD.
WILMINGTON, NORTH CAROLINA 28412

CONSTRUCTION DOCUMENTS AUGUST 2019

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.	NCDENR PWSS WATER PERMIT #:	_____
	WATER CAPACITY:	_____ GPD
	DWG SEWER PERMIT #:	_____
	SEWER CAPACITY:	_____ GPD
	SEWER SHED # AND PLANT:	_____
	SEWER TO FLOW THROUGH NEI:	YES or NO (CIRCLE ONE)
Approved Construction Plan		
Name _____		Date _____
Planning _____		
Traffic _____		
Fire _____		
Signed: _____		Permit # _____



VICINITY MAP
SCALE: 1"=1000'



SOILS MAP
SCALE: 1"=500'

NOTICE REQUIRED

ALL EXISTING UNDERGROUND UTILITIES SHALL BE PHYSICALLY LOCATED PRIOR TO THE BEGINNING OF ANY CONSTRUCTION IN THE VICINITY OF SAID UTILITIES.

CONTRACTORS SHALL NOTIFY OPERATORS WHO MAINTAIN UNDERGROUND UTILITY LINES IN THE AREA OF PROPOSED EXCAVATION AT LEAST TWO WORKING DAYS, BUT NOT MORE THAN TEN WORKING DAYS PRIOR TO COMMENCEMENT OF EXCAVATION OR DEMOLITION.

CONTRACTORS SHALL CONTACT OVERHEAD ELECTRIC PROVIDER TO COMPLY WITH FEDERAL OSHA 1910.333 MINIMUM APPROACH DISTANCE TO ENERGIZED POWERLINES AND OSH 29 CFR 1926.1407-1411 MUST BE FOLLOWED.

CONTRACTOR SHALL CONTACT AT&T PRIOR TO ANY DEMOLITION TO ALLOW FOR AT&T TO DISCONNECT COMMUNICATIONS CABLES COMING INTO THE SITE.

CONTACT THESE UTILITIES

CITY OF WILMINGTON PLANNING & DEVELOPMENT
ATTN: BRIAN CHAMBERS, PLANNER
PH: 910-342-2782

ATTN: ZONING INSPECTIONS
PH: 910-254-0900

PIEDMONT NATURAL GAS
ATTN: CATHY PLEASANT
PH: 910-291-2827

EMERGENCY DIAL 911
POLICE - FIRE - RESCUE
ATTN: CITY OF WILMINGTON FIRE & LIFE SAFETY
PH: 910-343-0896

CAPE FEAR PUBLIC UTILITY AUTHORITY (WATER & SEWER)
ENGINEERING/INSPECTIONS
PH: 910-332-6560

OPERATIONS/MAINTENANCE
PH: 910-322-6550

DUKE ENERGY
DISTRIBUTION CONSTRUCTION SERVICE
DEP CSC PH: 1-800-452-2777

TRANSMISSION AGENT
BILL WILDER
PH: 910-772-4903

AT&T/BELL SOUTH
ATTN: STEVE DAYVAULT (BUILDING ENGINEERING)
PH: 910-341-0741

ATTN: JAMES BATSON, ENGINEERING
PH: 910-341-1621

SPECTRUM
GENERAL PH: 800-892-4357

OWNER / DEVELOPER:
ECHO FARMS, LLC C/O MATRIX DEVELOPMENT GROUP
400 CN FORSGATE DRIVE
CRANBURY, NEW JERSEY 08512
(732) 521-2900

ENGINEER (CIVIL):
PARAMOUNTE ENGINEERING, INC.
122 CINEMA DRIVE
WILMINGTON, NORTH CAROLINA 28403
ATTN: ROB BALLAND, P.E. (910) 791-6707

SHEET INDEX	
SHEET NUMBER	SHEET TITLE
C-0.0	COVER SHEET
C-1.0 & C-1.1	GENERAL NOTES
C-2.0-2.2	SITE PLANS
C-2.3	SITE INVENTORY PLAN
C-3.0 & C-3.1	PH. I EROSION CONTROL PLANS
C-3.2 & C-3.3	GRADING & DRAINAGE PLANS
C-4.0 - C-4.3	UTILITY PLAN & PROFILES
C-5.0 - C-5.5	DETAILS

PREPARED BY:

PARAMOUNTE
ENGINEERING, INC.

122 Cinema Drive
Wilmington, North Carolina 28403
(910) 791-6707 (O) (910) 791-6760 (F)
NC License #: C-2846
PROJECT # 17358.PE



Professional Seal
redacted on electronic
copy per City of
Wilmington Policy

FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

Site Area Description	Required Ground Stabilization Timeframes	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7	None	
(b) High Quality Water (HQW) Zones	7	None	
(c) Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed.	
(d) Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed	
(e) Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope	

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Temporary Stabilization	Permanent Stabilization
<ul style="list-style-type: none"> Temporary grass seed covered with straw or other mulches and tackifiers Hydroseeding Roller erosion control products with or without temporary grass seed Appropriately applied straw or other mulch Plastic sheeting 	<ul style="list-style-type: none"> Permanent grass seed covered with straw or other mulches and tackifiers Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Shrubs or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or retaining walls Roller erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants.
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions.
- Provide ponding area for containment of treated stormwater before discharging offsite.
- Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- Provide drip pans under any stored equipment.
- Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
- Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- Remove leaking vehicles and construction equipment from service until the problem has been corrected.
- Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers.
- Provide a sufficient number and size of waste containers (e.g. dumpster, trash receptacle) on site to contain construction and domestic wastes.
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
- Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
- Dispose waste off-site at an approved disposal facility.
- On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE


- Do not dump paint and other liquid waste into storm drains, streams or wetlands.
- Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site.
- Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

PORTABLE TOILETS

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.
- Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.



CONCRETE WASHOUTS

- Do not discharge concrete or cement slurry from the site.
- Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
- Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
- Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
- Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
- Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
- At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by washout.

HERBICIDES, PESTICIDES AND RODENTICIDES

- Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE

- Create designated hazardous waste collection areas on-site.
- Place hazardous waste containers under cover or in secondary containment.
- Do not store hazardous chemicals, drums or bagged materials directly on the ground.

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

EFFECTIVE: 04/01/19

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit of this permit.
(6) Ground stabilization measures	After each phase of grading	1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land disturbing activity, construction or redevelopment, permanent ground cover), 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION B: RECORDKEEPING

1. E&SC Plan Documentation
The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be documented in the manner described:

Item to Document	Documentation Requirements
(a) Each E&SC Measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC Plan.	Initial and date each E&SC Measure on a copy of the approved E&SC Plan or complete, date and sign an inspection report that lists each E&SC Measure shown on the approved E&SC Plan. This documentation is required upon the initial installation of the E&SC Measures or if the E&SC Measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC Plan.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC Measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC Measures.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

2. Additional Documentation
In addition to the E&SC Plan documents above, the following items shall be kept on the site and available for agency inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- This general permit as well as the certificate of coverage, after it is received.
- Records of inspections made during the previous 30 days. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.
- All data used to complete the Notice of Intent and older inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION C: REPORTING

1. Occurrences that must be reported
Permittees shall report the following occurrences:

- Visible sediment deposition in a stream or wetland.
- Oil spills if:
 - They are 25 gallons or more,
 - They are less than 25 gallons but cannot be cleaned up within 24 hours,
 - They cause sheen on surface waters (regardless of volume), or
 - They are within 100 feet of surface waters (regardless of volume).

(a) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref. 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref. 40 CFR 302.4) or G.S. 143-215.85.

(b) Anticipated bypasses and unanticipated bypasses.

(c) Noncompliance with the conditions of this permit that may endanger health or the environment.

2. Reporting Timeframes and Other Requirements
After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Division's Emergency Response personnel at (800) 662-7956, (800) 858-0368 or (919) 733-3300.

Occurrence	Reporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment (b) Oil spills and release of hazardous substances per Item 1(b)-(c) above	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. If the stream is named on the NC 303(b) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired waters conditions.
(b) Oil spills and release of hazardous substances per Item 1(b)-(c) above	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.
(c) Anticipated bypasses [40 CFR 122.41(m)(3)]	<ul style="list-style-type: none"> A report at least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and effect of the bypass.
(d) Unanticipated bypasses [40 CFR 122.41(m)(3)]	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass.
(e) Noncompliance with the conditions of this permit that may endanger health or the environment [40 CFR 122.41(l)(7)]	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance. [40 CFR 122.41(l)(6)]. Division staff may waive the requirement for a written report on a case-by-case basis.

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

REVISIONS:

CLIENT INFORMATION:
ECHO FARMS, LLC
c/o MATRIX DEVELOPMENT GROUP
CN-4000 FORSGATE DRIVE
CRANBURY, NJ 08512

PARAMOUNT
ENGINEERING
122 Cinema Drive
Wilmington, North Carolina 28403
(910) 791-6707 (O) (910) 791-6760 (F)
NC License #: C-2846

GENERAL NOTES
TRACT 2
WOODLANDS @ ECHO FARMS
NEW HANOVER COUNTY
NORTH CAROLINA

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

NCDENR PWSS WATER PERMIT #: _____
WATER CAPACITY: _____ GPD
DWQ SEWER PERMIT #: _____
SEWER CAPACITY: _____ GPD
SEWER SHED # AND PLANT: _____
SEWER TO FLOW THROUGH NEI: YES or NO (CIRCLE ONE)

WILMINGTON
NORTH CAROLINA
Public Services • Engineering Division
APPROVED STORMWATER MANAGEMENT PLAN
Date: _____ Permit # _____
Signed: _____

Approved Construction Plan
Name _____ Date _____
Planning _____
Traffic _____
Fire _____

PROJECT STATUS
CONCEPTUAL LAYOUT:
PRELIMINARY LAYOUT:
RELEASED FOR CONSTRUCTION

DRAWING INFORMATION
DATE: _____
DESIGNED: _____
DRAWN: _____
RFB: _____
RFB: _____
CHECKED: _____


Professional Seal
redacted on electronic
copy per City of
Wilmington Policy

C-1.1

PEI JOB#: 17358.PE



FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION



CITY OF WILMINGTON
NORTH CAROLINA
Public Services • Engineering Division
APPROVED STORMWATER MANAGEMENT PLAN

Date: _____ Permit # _____
Signed: _____



NOTATION:
CI = CURB INLET
DI = DROP INLET
CO = CLEANOUT
DDI = DOUBLE DROP INLET
MH = STORM DRAIN MANHOLE
RD = ROOF DRAIN CLEANOUT
FFE = FINISHED FLOOR ELEVATION
BPE = BUILDING PAD ELEVATION

LEGEND:

- 16--- EXISTING CONTOUR
- 29--- PROPOSED CONTOUR
- EG=25.05 EXISTING GRADE SPOT ELEVATION
- EP=25.05 PROPOSED EDGE OF PAVEMENT
- TW=25.05 PROPOSED SIDEWALK ELEVATION
- GL=25.05 PROPOSED GUTTER FLOW LINE
- TC=25.05 PROPOSED TOP OF CURB ELEVATION
- INLET PROTECTION
- LIMITS OF DISTURBANCE
- SILT FENCE
- TREE PROTECTION FENCING
- DRAINAGE FLOW PATH
- DRAINAGE INLET LABEL
- SPILL GUTTER
- ROCK INLET PROTECTION
- GEOTECH BORING LOCATION
- DRAINAGE FLOW PATH & SLOPE

Approved Construction Plan


Name	Date
Planning _____	_____
Traffic _____	_____
Fire _____	_____

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

NCDENR PWSS WATER PERMIT #: _____
WATER CAPACITY: _____ GPD
DWO SEWER PERMIT #: _____
SEWER CAPACITY: _____ GPD
SEWER SHED # AND PLANT: _____
SEWER TO FLOW THROUGH NEI: YES or NO (CIRCLE ONE)

- GENERAL NOTES:**
- ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL STATE OF NC, CITY OF WILMINGTON, AND NEW HANOVER COUNTY STANDARDS AND SPECIFICATIONS.
 - THE CONTRACTOR SHALL PLACE INLET PROTECTION AROUND ALL STORM DRAIN INLETS TO PROTECT THE SYSTEM FROM COLLECTING SEDIMENTATION DURING CONSTRUCTION. INLET PROTECTION SHALL REMAIN IN PLACE UNTIL THE ROADS ARE PAVED.
 - CONTRACTOR SHALL ADJUST ALL FRAMES OF EX. UTILITY INFRASTRUCTURE WITHIN ASPHALT OVERLAY AND NEW ASPHALT AREAS TO MATCH PROPOSED GRADES.
 - ALL PROPOSED SPOT ELEVATIONS SHOWN ARE PROPOSED EDGE OF PAVEMENT UNLESS NOTED OTHERWISE.
 - ALL ROOF DRAINS AND IMPERVIOUS SURFACES SHALL BE DIRECTED TOWARDS ON-SITE COLLECTION SYSTEM. NO ROOF DRAINS OR IMPERVIOUS AREA SHALL BE DIRECTED OFF-SITE WITHOUT ENTERING THE ON-SITE COLLECTION SYSTEM FIRST.
 - ALL SIDEWALK CROSS SLOPES HAVE BEEN GRADED TO MEET ADA REGULATIONS. CONTRACTOR SHALL CONFIRM GRADES BEFORE PLACING PAVEMENT OR SIDEWALKS AND REPORT ANY DISCREPANCIES TO OWNER AND/OR ENGINEER.
 - THE CONTRACTOR SHALL USE EITHER RCP (CL. III or CL. IV) OR ADS HP STORM PIPE FOR THE STORM DRAINAGE SYSTEM UNLESS NOTED OTHERWISE. IF THE CONTRACTOR CHOOSES TO USE ADS HP STORM PIPE, IT SHALL BE INSTALLED TO MANUFACTURER SPECIFICATIONS. IN ADDITION, THE CONTRACTOR SHALL BE SURE TO PROVIDE CONCRETE COLLARS AROUND EACH F.E.S. TO PREVENT FLOATATION IF PP PIPE IS CHOSEN.
 - CONTRACTOR SHALL COORDINATE WITH OWNER TO DETERMINE IF A GEOTECHNICAL ENGINEERING REPORT WAS COMPLETED FOR THE SITE.
 - CONTRACTOR SHALL STAKE SILT FENCE ALONG LIMITS OF DISTURBANCE LINE. THE SILT FENCE LINETYPE IS OFFSET ON THE DRAWING FOR CLARITY.

- ASPHALT AREA NOTE:**
- SITE CONTRACTOR SHALL STRIP TOPSOIL AND ANY UNSUITABLE MATERIAL AND PROVIDE CUT/FILL OPERATIONS TO PROVIDE A COMPACTED CONTROLLED SUBGRADE, IN ACCORDANCE WITH THE SUBSURFACE GEOTECHNICAL EXPLORATION AND TECHNICAL SPECIFICATIONS.
- BUILDING PAD NOTE:**
- SITE CONTRACTOR SHALL STRIP TOPSOIL AND ANY UNSUITABLE MATERIAL AND PROVIDE CUT/FILL OPERATIONS TO PROVIDE A COMPACTED CONTROLLED BUILDING PAD, IN ACCORDANCE WITH STRUCTURAL DRAWINGS.
- STORMWATER NOTE:**
- THIS PROJECT DRAINS TO A PROPOSED ON-SITE STORM WATER WET DETENTION BASIN.
 - ONCE SITE IS STABILIZED AND SEDIMENT BASIN IS CONVERTED TO A WET DETENTION BASIN, CONTRACTOR SHALL REMOVE ALL SEDIMENT FROM BASIN AND RESTORE TO DESIGN ELEVATIONS.
- CONSTRUCTION NOTES FOR WORK IN ENVIRONMENTAL SETBACKS:**
- ANY CONSTRUCTION ACTIVITY AND DISTURBANCE WITHIN THE CONSERVATION SETBACKS SHALL BE KEPT TO AN ABSOLUTE MINIMUM.
 - THERE SHALL BE NO STOCKPILING OF MATERIAL WITHIN THE CONSERVATION SETBACKS.
 - ONCE DISTURBANCE IS COMPLETE WITHIN CONSERVATION SETBACKS, THEY SHALL BE SEEDED AND MULCHED TO ESTABLISH VEGETATION.



REVISIONS:

CLIENT INFORMATION:
ECHO FARMS, LLC
c/o MATRIX DEVELOPMENT GROUP
CN 4000 FORSCATE DRIVE
CRANBURY, NJ 08512

PARAMOUNT ENGINEERING
122 Cinema Drive
Wilmington, North Carolina 28403
(910) 791-6707 (O) (910) 791-6760 (F)
NC License #: C-2846

PH I EROSION CONTROL PLAN
TRACT 2
WOODLANDS @ ECHO FARMS
CITY OF WILMINGTON
NORTH CAROLINA


PROJECT STATUS:
CONCEPTUAL LAYOUT:
PRELIMINARY LAYOUT:
RELEASED FOR CONST.:


DRAWING INFORMATION:
DATE: 08/08/19
DRAWN: JFB
DESIGNED: RFB
CHECKED: RFB

Professional Seal
redacted on electronic
copy per City of
Wilmington Policy

C-3.0
PEI JOB#: 17358.PE

FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION





CITY OF WILMINGTON
NORTH CAROLINA
Public Services • Engineering Division
APPROVED STORMWATER MANAGEMENT PLAN

Date: _____ Permit # _____
Signed: _____



For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

Approved Construction Plan

Name	Date
Planning _____	_____
Traffic _____	_____
Fire _____	_____

NCDENR PWSS WATER PERMIT #:	_____
WATER CAPACITY:	_____ GPD
DWQ SEWER PERMIT #:	_____
SEWER CAPACITY:	_____ GPD
SEWER SHED # AND PLANT:	_____
SEWER TO FLOW THROUGH NEI:	YES or NO (CIRCLE ONE)

VICINITY MAP
SCALE: 1" = 2,000'

LEGEND:

16	EXISTING CONTOUR
29	PROPOSED CONTOUR
EG+25.05	EXISTING GRADE SPOT ELEVATION
EP+25.05	PROPOSED EDGE OF PAVEMENT
TW+25.05	PROPOSED SIDEWALK ELEVATION
GL+25.05	PROPOSED GUTTER FLOW LINE
TC+25.05	PROPOSED TOP OF CURB ELEVATION
[Symbol]	INLET PROTECTION
[Symbol]	LIMITS OF DISTURBANCE
[Symbol]	SILT FENCE
[Symbol]	TREE PROTECTION FENCING
[Symbol]	DRAINAGE FLOW PATH
[Symbol]	DRAINAGE INLET LABEL
[Symbol]	SPILL GUTTER
[Symbol]	ROCK INLET PROTECTION
[Symbol]	GEOTECH BORING LOCATION
[Symbol]	DRAINAGE FLOW PATH & SLOPE
[Symbol]	PROTECTIVE TREE FENCING

NOTATION:

CI	= CURB INLET
DI	= DROP INLET
CO	= CLEANOUT
DDI	= DOUBLE DROP INLET
MH	= STORM DRAIN MANHOLE
RD	= ROOF DRAIN CLEANOUT
FFE	= FINISHED FLOOR ELEVATION
BPE	= BUILDING PAD ELEVATION




ASPHALT AREA NOTE:
1. SITE CONTRACTOR SHALL STRIP TOPSOIL AND ANY UNSUITABLE MATERIAL AND PROVIDE CUT/FILL OPERATIONS TO PROVIDE A COMPACTED CONTROLLED SUBGRADE, IN ACCORDANCE WITH THE SUBSURFACE GEOTECHNICAL EXPLORATION AND TECHNICAL SPECIFICATIONS.

BUILDING PAD NOTE:
1. SITE CONTRACTOR SHALL STRIP TOPSOIL AND ANY UNSUITABLE MATERIAL AND PROVIDE CUT/FILL OPERATIONS TO PROVIDE A COMPACTED CONTROLLED BUILDING PAD, IN ACCORDANCE WITH STRUCTURAL DRAWINGS.

STORMWATER NOTE:
1. THIS PROJECT DRAINS TO A PROPOSED ON-SITE STORM WATER WET DETENTION BASIN.
2. ONCE SITE IS STABILIZED AND SEDIMENT BASIN IS CONVERTED TO A WET DETENTION BASIN, CONTRACTOR SHALL REMOVE ALL SEDIMENT FROM BASIN AND RESTORE TO DESIGN ELEVATIONS.

CONSTRUCTION NOTES FOR WORK IN ENVIRONMENTAL SETBACKS:
1. ANY CONSTRUCTION ACTIVITY AND DISTURBANCE WITHIN THE CONSERVATION SETBACKS SHALL BE KEPT TO AN ABSOLUTE MINIMUM.
2. THERE SHALL BE NO STOCKPILING OF MATERIAL WITHIN THE CONSERVATION SETBACKS.
3. ONCE DISTURBANCE IS COMPLETE WITHIN CONSERVATION SETBACKS, THEY SHALL BE SEEDED AND MULCHED TO ESTABLISH VEGETATION.

- GENERAL NOTES:**
- ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL STATE OF NC, CITY OF WILMINGTON, AND NEW HANOVER COUNTY STANDARDS AND SPECIFICATIONS.
 - THE CONTRACTOR SHALL PLACE INLET PROTECTION AROUND ALL STORM DRAIN INLETS TO PROTECT THE SYSTEM FROM COLLECTING SEDIMENTATION DURING CONSTRUCTION. INLET PROTECTION SHALL REMAIN IN PLACE UNTIL THE ROADS ARE PAVED.
 - CONTRACTOR SHALL ADJUST ALL FRAMES OF EX. UTILITY INFRASTRUCTURE WITHIN ASPHALT OVERLAY AND NEW ASPHALT AREAS TO MATCH PROPOSED GRADES.
 - ALL PROPOSED SPOT ELEVATIONS SHOWN ARE PROPOSED EDGE OF PAVEMENT UNLESS NOTED OTHERWISE.
 - ALL ROOF DRAINS AND IMPERVIOUS SURFACES SHALL BE DIRECTED TOWARDS ON-SITE COLLECTION SYSTEM. NO ROOF DRAINS OR IMPERVIOUS AREA SHALL BE DIRECTED OFF-SITE WITHOUT ENTERING THE ON-SITE COLLECTION SYSTEM FIRST.
 - ALL SIDEWALK CROSS SLOPES HAVE BEEN GRADED TO MEET ADA REGULATIONS. CONTRACTOR SHALL CONFIRM GRADES BEFORE PLACING PAVEMENT OR SIDEWALKS AND REPORT ANY DISCREPANCIES TO OWNER AND/OR ENGINEER.
 - THE CONTRACTOR SHALL USE EITHER RCP (CL. III or CL. IV) OR ADS HP STORM PIPE FOR THE STORM DRAINAGE SYSTEM UNLESS NOTED OTHERWISE. IF THE CONTRACTOR CHOOSES TO USE ADS HP STORM PIPE, IT SHALL BE INSTALLED TO MANUFACTURER SPECIFICATIONS. IN ADDITION, THE CONTRACTOR SHALL BE SURE TO PROVIDE CONCRETE COLLARS AROUND EACH F.E.S. TO PREVENT FLOATATION IF PP PIPE IS CHOSEN.
 - CONTRACTOR SHALL COORDINATE WITH OWNER TO DETERMINE IF A GEOTECHNICAL ENGINEERING REPORT WAS COMPLETED FOR THE SITE.
 - CONTRACTOR SHALL STAKE SILT FENCE ALONG LIMITS OF DISTURBANCE LINE. THE SILT FENCE LINETYPE IS OFFSET ON THE DRAWING FOR CLARITY.



FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION

REVISIONS:

NO.	DESCRIPTION

CLIENT INFORMATION:
ECHO FARMS, LLC
c/o MATRIX DEVELOPMENT GROUP
CN 4000 FORSCATE DRIVE
CRANBURY, NJ 08512

PARAMOUNT ENGINEERING
122 Cinema Drive
Wilmington, North Carolina 28403
(910) 791-6707 (O) (910) 791-6760 (F)
NC License #: C-2846


PH. I EROSION CONTROL PLAN
TRACT 2
WOODLANDS @ ECHO FARMS
CITY OF WILMINGTON
NORTH CAROLINA

PROJECT STATUS:
CONCEPTUAL LAYOUT
PRELIMINARY LAYOUT
RELEASED FOR CONSTRUCTION

DRAWING INFORMATION:
DATE: 08/08/19
DRAWN: JPH
CHECKED: RPB

Professional Seal
redacted on electronic
copy per City of
Wilmington Policy

C-3.1
PEI JOB#: 17358.PE



CITY OF WILMINGTON
NORTH CAROLINA
Public Services • Engineering Division
APPROVED STORMWATER MANAGEMENT PLAN

Date: _____ Permit # _____
Signed: _____



NOTATION:
CI = CURB INLET
DI = DROP INLET
CO = CLEANOUT
DDI = DOUBLE DROP INLET
MH = STORM DRAIN MANHOLE
RD = ROOF DRAIN CLEANOUT
FFE = FINISHED FLOOR ELEVATION
BPE = BUILDING PAD ELEVATION

CONSTRUCTION NOTES FOR WORK IN ENVIRONMENTAL SETBACKS:
1. ANY CONSTRUCTION ACTIVITY AND DISTURBANCE WITHIN THE CONSERVATION SETBACKS SHALL BE KEPT TO AN ABSOLUTE MINIMUM.
2. THERE SHALL BE NO STOCKPILING OF MATERIAL WITHIN THE CONSERVATION SETBACKS.
3. ONCE DISTURBANCE IS COMPLETE WITHIN CONSERVATION SETBACKS, THEY SHALL BE SEEDED AND MULCHED TO ESTABLISH VEGETATION.

LEGEND:

- 16— EXISTING CONTOUR
- 29— PROPOSED CONTOUR
- EG=25.05 EXISTING GRADE SPOT ELEVATION
- EP=25.05 PROPOSED EDGE OF PAVEMENT
- TW=25.05 PROPOSED SIDEWALK ELEVATION
- GL=25.05 PROPOSED GUTTER FLOW LINE
- TC=25.05 PROPOSED TOP OF CURB ELEVATION
- INLET PROTECTION
- LIMITS OF DISTURBANCE
- SILT FENCE
- TREE PROTECTION FENCING
- DRAINAGE FLOW PATH
- DRAINAGE INLET LABEL
- GUTTER
- ROCK INLET PROTECTION
- GEOTECH BORING LOCATION
- DRAINAGE FLOW PATH & SLOPE

Approved Construction Plan


Name	Date
Planning _____	_____
Traffic _____	_____
Fire _____	_____

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

NCDENR PWSS WATER PERMIT #: _____
WATER CAPACITY: _____ GPD
DWQ SEWER PERMIT #: _____
SEWER CAPACITY: _____ GPD
SEWER SHED # AND PLANT: _____
SEWER TO FLOW THROUGH NEI: YES or NO (CIRCLE ONE)

- GENERAL NOTES:**
- ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL STATE OF NC, CITY OF WILMINGTON, AND NEW HANOVER COUNTY STANDARDS AND SPECIFICATIONS.
 - THE CONTRACTOR SHALL PLACE INLET PROTECTION AROUND ALL STORM DRAIN INLETS TO PROTECT THE SYSTEM FROM COLLECTING SEDIMENTATION DURING CONSTRUCTION. INLET PROTECTION SHALL REMAIN IN PLACE UNTIL THE ROADS ARE PAVED.
 - CONTRACTOR SHALL ADJUST ALL FRAMES OF EX. UTILITY INFRASTRUCTURE WITHIN ASPHALT OVERLAY AND NEW ASPHALT AREAS TO MATCH PROPOSED GRADES.
 - ALL PROPOSED SPOT ELEVATIONS SHOWN ARE PROPOSED EDGE OF PAVEMENT UNLESS NOTED OTHERWISE.
 - ALL ROOF DRAINS AND IMPERVIOUS SURFACES SHALL BE DIRECTED TOWARDS ON-SITE COLLECTION SYSTEM. NO ROOF DRAINS OR IMPERVIOUS AREA SHALL BE DIRECTED OFF-SITE WITHOUT ENTERING THE ON-SITE COLLECTION SYSTEM FIRST.
 - ALL SIDEWALK CROSS SLOPES HAVE BEEN GRADED TO MEET ADA REGULATIONS. CONTRACTOR SHALL CONFIRM GRADES BEFORE PLACING PAVEMENT OR SIDEWALKS AND REPORT ANY DISCREPANCIES TO OWNER AND/OR ENGINEER.
 - THE CONTRACTOR SHALL USE EITHER RCP (CL. III or CL. IV) OR ADS HP STORM PIPE FOR THE STORM DRAINAGE SYSTEM UNLESS NOTED OTHERWISE. IF THE CONTRACTOR CHOOSES TO USE ADS HP STORM PIPE, IT SHALL BE INSTALLED TO MANUFACTURER SPECIFICATIONS. IN ADDITION, THE CONTRACTOR SHALL BE SURE TO PROVIDE CONCRETE COLLARS AROUND EACH F.E.S. TO PREVENT FLOTTATION IF PP PIPE IS CHOSEN.
 - CONTRACTOR SHALL COORDINATE WITH OWNER TO DETERMINE IF A GEOTECHNICAL ENGINEERING REPORT WAS COMPLETED FOR THE SITE.
 - CONTRACTOR SHALL STAKE SILT FENCE ALONG LIMITS OF DISTURBANCE LINE. THE SILT FENCE LINETYPE IS OFFSET ON THE DRAWING FOR CLARITY.

- ASPHALT AREA NOTE:**
- SITE CONTRACTOR SHALL STRIP TOPSOIL AND ANY UNSUITABLE MATERIAL AND PROVIDE CUT/FILL OPERATIONS TO PROVIDE A COMPACTED CONTROLLED SUBGRADE, IN ACCORDANCE WITH THE SUBSURFACE GEOTECHNICAL EXPLORATION AND TECHNICAL SPECIFICATIONS.
- BUILDING PAD NOTE:**
- SITE CONTRACTOR SHALL STRIP TOPSOIL AND ANY UNSUITABLE MATERIAL AND PROVIDE CUT/FILL OPERATIONS TO PROVIDE A COMPACTED CONTROLLED BUILDING PAD, IN ACCORDANCE WITH STRUCTURAL DRAWINGS.
- STORMWATER NOTE:**
- THIS PROJECT DRAINS TO A PROPOSED ON-SITE STORM WATER WET DETENTION BASIN.
 - ONCE SITE IS STABILIZED AND SEDIMENT BASIN IS CONVERTED TO A WET DETENTION BASIN, CONTRACTOR SHALL REMOVE ALL SEDIMENT FROM BASIN AND RESTORE TO DESIGN ELEVATIONS.
- DUKE ENERGY NOTES:**
- NO STOCKPILING OF MATERIAL IS ALLOWED AT ANY TIME IN THE DUKE ENERGY TRANSMISSION EASEMENT ALONG INDEPENDENCE BLVD.
 - NO GRADING IS ALLOWED WITHIN 25 FEET OF ANY GUY ANCHOR OR TRANSMISSION POLE.
 - THERE IS NO GRADE CHANGES ALLOWED IN THE TRANSMISSION EASEMENT UNLESS SHOWN ON THE PLANS.
 - NO SUBDIVISION ENTRY SIGNAGE IS ALLOWED IN THE DUKE ENERGY TRANSMISSION EASEMENT.



REVISIONS:

NO.	DATE	DESCRIPTION

CLIENT INFORMATION:
ECHO FARMS, LLC
c/o MATRIX DEVELOPMENT GROUP
CN 4000 FORSCATE DRIVE
CRANBURY, NJ 08512

PARAMOUNT ENGINEERING
122 Cinema Drive
Wilmington, North Carolina 28403
(910) 791-6707 (O) (910) 791-6760 (F)
NC License #: C-2846

GRADING & DRAINAGE PLAN
TRACT 2
WOODLANDS @ ECHO FARMS
CITY OF WILMINGTON
NORTH CAROLINA


PROJECT STATUS:
CONCEPTUAL LAYOUT:
PRELIMINARY LAYOUT:
RELEASED FOR CONSTRUCTION


DRAWING INFORMATION:
DATE: 08/08/19
DRAWN: JRM
CHECKED: RJB

Professional Seal redacted on electronic copy per City of Wilmington Policy

C-3.2
PEI JOB#: 17358.PE

FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION





VICINITY MAP
SCALE: 1" = 2,000'

LEGEND:

- 16 EXISTING CONTOUR
- 29 PROPOSED CONTOUR
- EG+25.05 EXISTING GRADE SPOT ELEVATION
- EP+25.05 PROPOSED EDGE OF PAVEMENT
- TW+25.05 PROPOSED SIDEWALK ELEVATION
- GL+25.05 PROPOSED GUTTER FLOW LINE
- TC+25.05 PROPOSED TOP OF CURB ELEVATION
- INLET PROTECTION
- LIMITS OF DISTURBANCE
- SILT FENCE
- TREE PROTECTION FENCING
- DRAINAGE FLOW PATH
- DRAINAGE INLET LABEL
- SPILL GUTTER
- ROCK INLET PROTECTION
- GEOTECH BORING LOCATION
- DRAINAGE FLOW PATH & SLOPE
- PROTECTIVE TREE FENCING

CITY OF WILMINGTON
NORTH CAROLINA
Public Services • Engineering Division
APPROVED STORMWATER MANAGEMENT PLAN

Date: _____ Permit # _____
Signed: _____

Approved Construction Plan
Name _____ Date _____

Planning _____
Traffic _____
Fire _____

811
Know what's below.
Call before you dig.


For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

NCDENR PWSS WATER PERMIT #: _____
WATER CAPACITY: _____ GPD
DWQ SEWER PERMIT #: _____
SEWER CAPACITY: _____ GPD
SEWER SHED # AND PLANT: _____
SEWER TO FLOW THROUGH NEI: YES or NO (CIRCLE ONE)

STORM SEWER SCHEDULE:


Upstream Node	Downstream Node	Diameter (in)	Upstream Pipe Invert (ft)	Downstream Pipe Invert (ft)	Pipe Length (ft)	Slope (%)	Upstream Rim Elev (ft)	Downstream Rim Elev (ft)	Pipe Material
MH-1A	FES-1	36	-0.45	-1.00	118	0.46	8.00	N/A	RCP III
CI-2	MH-1A	36	-0.23	-0.45	50	0.45	9.44	8.00	RCP III
CI-3	CI-2	36	-0.01	-0.23	71	0.30	10.63	9.44	RCP III
MH-37	CI-2	15	0.07	-0.23	78	0.38	9.00	9.44	RCP III
MH-38	MH-37	15	0.65	0.07	116	0.50	9.00	9.00	RCP III
CI-7	CI-3	15	6.63	6.50	26	0.52	10.63	10.63	RCP III
MH-4	CI-3	18	1.34	1.24	33	0.32	11.18	10.63	RCP III
MH-8	CI-3	24	0.16	-0.01	58	0.30	11.13	10.63	RCP III
MH-40	MH-38	15	1.00	0.65	69	0.50	8.00	9.00	RCP III
CI-9	MH-8	24	0.61	0.16	143	0.32	10.23	11.13	RCP III
CI-5	MH-4	18	2.06	1.34	240	0.30	6.69	11.18	RCP III
CI-10	CI-9	15	6.37	6.29	26	0.30	10.23	10.23	RCP III
MH-11	CI-9	24	1.08	0.61	156	0.30	10.79	10.23	RCP III
CI-6	CI-5	18	2.14	2.06	26	0.30	6.69	6.69	RCP III
CI-12	MH-11	24	1.64	1.16	161	0.30	9.08	10.79	RCP III
CI-13	CI-12	18	5.01	4.93	26	0.31	9.08	9.08	RCP III
MH-15	FES-14	18	0.26	0.00	36	0.73	9.00	N/A	RCP III
MH-16	MH-15	18	0.78	0.26	173	0.30	9.48	9.00	RCP III
CI-17	MH-16	18	0.97	0.78	65	0.29	8.64	9.48	RCP III
CI-18	CI-17	15	1.16	0.97	26	0.73	8.64	8.64	RCP III
MH-20	FES-19	30	2.70	2.00	248	0.28	10.68	N/A	RCP III
CI-21	MH-20	15	3.38	3.20	60	0.30	9.88	10.68	RCP III
CI-23	MH-20	30	3.27	2.70	190	0.30	8.76	10.68	RCP III
CI-24	CI-23	15	3.35	3.27	26	0.30	8.77	8.76	RCP III
CI-25	CI-23	24	3.64	3.27	122	0.30	8.24	8.76	RCP III
CI-22	CI-21	15	3.46	3.38	26	0.30	9.88	9.88	RCP III
CI-26	CI-25	18	3.72	3.64	26	0.30	8.24	8.24	RCP III
CI-27	CI-25	18	4.02	3.64	127	0.30	8.78	8.24	RCP III
CI-28	CI-27	15	4.10	4.02	26	0.30	8.78	8.78	RCP III
CI-31	FES-30	18	2.23	1.00	54	2.27	9.29	N/A	RCP III
CI-32	CI-31	18	2.32	2.23	18	0.50	9.29	9.29	RCP III
CI-34	FES-33	15	2.18	1.50	59	1.15	11.07	N/A	RCP III
CI-35	CI-34	15	2.27	2.18	18	0.50	11.07	11.07	RCP III
MH-39	MH-41	15	-3.00	-3.00	84	0.00	8.00	8.00	RCP IV
DI-40	MH-39	15	2.23	1.41	164	0.50	7.95	8.00	RCP III
DI-42	DI-40	15	3.30	2.23	215	0.50	8.50	7.95	RCP III
DI-43	DI-42	15	4.00	3.30	139	0.50	8.50	8.50	RCP III

- NOTATION:
- CI = CURB INLET
 - DI = DROP INLET
 - CO = CLEANOUT
 - DDI = DOUBLE DROP INLET
 - MH = STORM DRAIN MANHOLE
 - RD = ROOF DRAIN CLEANOUT
 - FFE = FINISHED FLOOR ELEVATION
 - BPE = BUILDING PAD ELEVATION




SIDEWALK - TYPICAL CROSS SECTION
ALONG BACK OF CURB
NOT TO SCALE

- CONSTRUCTION NOTES FOR WORK IN ENVIRONMENTAL SETBACKS:
- ANY CONSTRUCTION ACTIVITY AND DISTURBANCE WITHIN THE CONSERVATION SETBACKS SHALL BE KEPT TO AN ABSOLUTE MINIMUM.
 - THERE SHALL BE NO STOCKPILING OF MATERIAL WITHIN THE CONSERVATION SETBACKS.
 - ONCE DISTURBANCE IS COMPLETE WITHIN CONSERVATION SETBACKS, THEY SHALL BE SEEDED AND MULCHED TO ESTABLISH VEGETATION.



- GENERAL NOTES:
- ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL STATE OF NC, CITY OF WILMINGTON, AND NEW HANOVER COUNTY STANDARDS AND SPECIFICATIONS.
 - THE CONTRACTOR SHALL PLACE INLET PROTECTION AROUND ALL STORM DRAIN INLETS TO PROTECT THE SYSTEM FROM COLLECTING SEDIMENTATION DURING CONSTRUCTION. INLET PROTECTION SHALL REMAIN IN PLACE UNTIL THE ROADS ARE PAVED.
 - CONTRACTOR SHALL ADJUST ALL FRAMES OF EX. UTILITY INFRASTRUCTURE WITHIN ASPHALT OVERLAY AND NEW ASPHALT AREAS TO MATCH PROPOSED GRADES.
 - ALL PROPOSED SPOT ELEVATIONS SHOWN ARE PROPOSED EDGE OF PAVEMENT UNLESS NOTED OTHERWISE.
 - ALL ROOF DRAINS AND IMPERVIOUS SURFACES SHALL BE DIRECTED TOWARDS ON-SITE COLLECTION SYSTEM. NO ROOF DRAINS OR IMPERVIOUS AREA SHALL BE DIRECTED OFF-SITE WITHOUT ENTERING THE ON-SITE COLLECTION SYSTEM FIRST.
 - ALL SIDEWALK CROSS SLOPES HAVE BEEN GRADED TO MEET ADA REGULATIONS. CONTRACTOR SHALL CONFIRM GRADES BEFORE PLACING PAVEMENT OR SIDEWALKS AND REPORT ANY DISCREPANCIES TO OWNER AND/OR ENGINEER.
 - THE CONTRACTOR SHALL USE EITHER RCP (CL. III or CL. IV) OR ADS HP STORM PIPE FOR THE STORM DRAINAGE SYSTEM UNLESS NOTED OTHERWISE. IF THE CONTRACTOR CHOOSES TO USE ADS HP STORM PIPE, IT SHALL BE INSTALLED TO MANUFACTURER SPECIFICATIONS. IN ADDITION, THE CONTRACTOR SHALL BE SURE TO PROVIDE CONCRETE COLLARS AROUND EACH F.E.S. TO PREVENT FLOATION IF PP PIPE IS CHOSEN.
 - CONTRACTOR SHALL COORDINATE WITH OWNER TO DETERMINE IF A GEOTECHNICAL ENGINEERING REPORT WAS COMPLETED FOR THE SITE.
 - CONTRACTOR SHALL STAKE SILT FENCE ALONG LIMITS OF DISTURBANCE LINE. THE SILT FENCE LINE TYPE IS OFFSET 1-FOOT FOR CLARITY.
- ASPHALT AREA NOTE:
- SITE CONTRACTOR SHALL STRIP TOPSOIL AND ANY UNSUITABLE MATERIAL AND PROVIDE CUT/FILL OPERATIONS TO PROVIDE A COMPACTED CONTROLLED SUBGRADE, IN ACCORDANCE WITH THE SUBSURFACE GEOTECHNICAL EXPLORATION AND TECHNICAL SPECIFICATIONS.
- BUILDING PAD NOTE:
- SITE CONTRACTOR SHALL STRIP TOPSOIL AND ANY UNSUITABLE MATERIAL AND PROVIDE CUT/FILL OPERATIONS TO PROVIDE A COMPACTED CONTROLLED BUILDING PAD, IN ACCORDANCE WITH STRUCTURAL DRAWINGS.
- STORMWATER NOTE:
- THIS PROJECT DRAINS TO A PROPOSED ON-SITE STORM WATER WET DETENTION BASIN.
 - ONCE SITE IS STABILIZED AND SEDIMENT BASIN IS CONVERTED TO A WET DETENTION BASIN, CONTRACTOR SHALL REMOVE ALL SEDIMENT FROM BASIN AND RESTORE TO DESIGN ELEVATIONS.
- DUKE ENERGY NOTES:
- NO STOCKPILING OF MATERIAL IS ALLOWED AT ANY TIME IN THE DUKE ENERGY TRANSMISSION EASEMENT ALONG INDEPENDENCE BLVD.
 - NO GRADING IS ALLOWED WITHIN 25 FEET OF ANY GUY ANCHOR OR TRANSMISSION POLE.
 - THERE IS NO GRADE CHANGES ALLOWED IN THE TRANSMISSION EASEMENT UNLESS SHOWN ON THE PLANS.
 - NO SUBDIVISION ENTRY SIGNAGE IS ALLOWED IN THE DUKE ENERGY TRANSMISSION EASEMENT.



FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION

REVISIONS:

CLIENT INFORMATION:
ECHO FARMS, LLC
c/o MATRIX DEVELOPMENT GROUP
CN 4000 FORSGATE DRIVE
CRANBURY, NJ 08512

PARAMOUNT ENGINEERING
122 Cinema Drive
Wilmington, North Carolina 28403
(910) 791-6707 (O) (910) 791-6760 (F)
NC License #: C-2846



GRADING-DRAINAGE-EC PLAN
TRACT 2
WOODLANDS @ ECHO FARMS
CITY OF WILMINGTON
NORTH CAROLINA

PROJECT STATUS:
CONCEPTUAL LAYOUT:
PRELIMINARY LAYOUT:
RELEASED FOR CONSTRUCTION






















DRAWING INFORMATION:
DATE: 08/08/19
DRAWN: RFB
CHECKED: RFB

Professional Seal
redacted on electronic
copy per City of
Wilmington Policy

C-3.3
PEI JOB#: 17358.PE



TYPICAL PAVEMENT SECTION
NOT TO SCALE



Approved Construction Plan

Name: _____ Date: _____

Public Services • Engineering Division

APPROVED STORMWATER MANAGEMENT PLAN

Date: _____ Permit #: _____

Signed: _____

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

Planning _____
Traffic _____
Fire _____

FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION

REVISIONS:

CLIENT INFORMATION: ECHO FARMS, LLC
c/o MATRIX DEVELOPMENT GROUP
CN-4000 FORSGATE DRIVE
CRANBURY, NJ 08512

ENGINEERING: PARAMOUNT ENGINEERING
122 Cinema Drive
Wilmington, North Carolina 28403
(910) 791-0707 (O) (910) 791-6766 (F)
NC License #: C-2846


PROJECT STATUS: CONCEPTUAL LAYOUT, PRELIMINARY LAYOUT, RELEASED FOR CONSTRUCTION

DRAWING INFORMATION: DATE: 08/09/19, DRAWN: RPB, CHECKED: AIC, DESIGNED: AIC, CHECKED: RPB


Professional Seal
redacted on electronic copy per City of Wilmington Policy

C-5.0


PEI JOB#: 17358.PE



INLET PROTECTION
NOT TO SCALE



STANDARD PIPE TRENCH DETAIL
NOT TO SCALE




STONE CHECK DAM DETAIL
NOT TO SCALE


**Woodlands Tract 2
Temporary Sediment Fence - Ph1 EC**

Requirement = 100 lb per 0.25 acres disturbed


EC DA #	Disturbed area (sq) (ft)	Total drainage area (sq) (ft)	Silt Fence Required (ft)	Silt Fence Provided (ft)
1	0.70 ac	0.70 ac	280	811
2	1.20 ac	1.20 ac	480	932
3	0.58 ac	0.58 ac	232	435
6	0.84 ac	0.84 ac	336	520
8	0.15 ac	0.15 ac	60	201




GUIDELINES FOR TEMPORARY SILT FENCE DETAIL
NOT TO SCALE




TEMPORARY SKIMMER SEDIMENT BASIN DETAIL
NOT TO SCALE



FAIRCLOTH SKIMMER DETAIL
NOT TO SCALE




GUIDELINES FOR TEMPORARY DIVERSION DITCH
NOT TO SCALE



RIP-RAP SCHEDULE

	PIPE DIA. (IN.)	LENGTH (FT.)	WIDTH (FT.)	UPSTREAM WIDTH (FT.)	DOWNSTREAM WIDTH (FT.)
FES-1	30	11	7.5	7.5	7.5
FES-14	18	7	4.5	4.5	4.5
FES-19	30	11	7.5	7.5	7.5
FES-30	18	7	4.5	4.5	4.5
FES-33	15	7	3.75	3.75	3.75
FES-36	15	7	3.75	3.75	3.75
FES-42	18	7	4.5	4.5	4.5
FES-43	15	6	3.75	3.75	3.75
FES-44	15	6	3.75	3.75	3.75



SILT FENCE WATTLE BREAK DETAIL

TYPICAL SWALE
NOT TO SCALE

SWALE #	A ₁	C	D	Length	Sw	St	S	d	A ₂	P	R	V _{max}	Q _{max}	Adequate Capacity?	Lining Required?
1	0.17	0.46	0.27	85	8.40	7.98	0.0003	0.20	0.72	4.26	0.17	0.83	0.60	Y	N
2	0.18	0.53	0.68	207	8.25	7.95	0.0015	0.17	1.22	4.86	0.25	0.58	0.69	Y	N
3	0.19	0.62	0.85	146	9.00	8.50	0.0034	0.28	1.08	4.77	0.23	0.81	0.87	Y	N
4	0.08	0.36	0.21	68	9.00	8.50	0.0074	0.18	0.92	3.95	0.13	0.82	0.43	Y	N
5	0.13	0.46	0.33	68	9.00	8.50	0.0074	0.18	0.92	3.95	0.13	0.82	0.43	Y	N
6	0.23	0.55	0.91	146	10.50	8.50	0.0137	0.20	0.72	4.26	0.17	1.33	0.96	Y	N
7	0.60	0.55	0.58	1275	8.50	3.00	0.0343	0.80	4.32	8.08	0.94	1.61	0.97	Y	N
8	0.52	0.55	0.52	925	13.75	8.50	0.0145	0.28	0.98	4.84	0.21	1.59	1.56	Y	N


- BAFFLES CONSTRUCTION SPECIFICATION**
- Grade the basin so that the bottom is level front to back and side to side.
 - Install posts or saw horses across the width of the sediment trap (Practice 6.62, Sediment Fence).
 - Steel posts should be driven to a depth of 24 inches, spaced a maximum of 4 feet apart, and installed on the side of the basin as well. The top of the fabric should be 6 inches higher than the invert of the spillway. Tops of baffles should be 2 inches lower than the top of the berms.
 - Install at least three rows of baffles between the inlet and outlet discharge point. Basins less than 20 feet in length may use 2 baffles.
 - When using posts, add a support wire or rope across the top of the measure to prevent sagging.
 - Wrap joints, backed by coil material, over a sawhorse or the top wire. Hammer rebar into the sawhorse legs for anchoring. The fabric should have five to ten percent openings in the weave. Attach fabric to a rope and a support structure with zip ties, wire or staples.
 - The bottom and sides of the fabric should be anchored in a trench or pinned with 8-inch erosion control matting staples.
 - Do not splice the fabric, but use a continuous piece across the basin.

MAINTENANCE
Inspect baffles at least once a week and after each rainfall. Make any required repairs immediately. Be sure to maintain access to the baffles. Should the fabric of a baffle collapse, tear, decompose, or become ineffective, replace it promptly.

Remove sediment deposits when it reaches half full to provide adequate storage volume for the next rain and to reduce pressure on the baffles. Take care to avoid damaging the baffles during cleanup. Sediment depth should never exceed half the designed storage depth.

After the contributing drainage area has been properly stabilized, remove all baffle materials and unstable sediment deposits, bring the area to grade, and stabilize it.

NOTE:
Porous baffles shall be installed inside all temporary sediment traps, rock dams, skimmer basin or sediment basins to reduce the velocity and turbulence of the water flowing through the measure, and facilitate the settling of sediment from the water before discharge.



BAFFLE DETAIL
NOT TO SCALE

Surface Area (sf)	Length (ft)	Inlet Area (sf)	Chamber 1 Area (sf)	Chamber 2 Area (sf)	Outlet Area (sf)	Baffle #1 (Distance from End) (ft)	Baffle #2 (Distance from End) (ft)	Baffle #3 (Distance from End) (ft)
1,500	68	375	375	375	375	17	34	51

Approved Construction Plan

Name: _____ Date: _____

Planning _____

Traffic _____

Fire _____

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

WILMINGTON NORTH CAROLINA

Public Services • Engineering Division

APPROVED STORMWATER MANAGEMENT PLAN

Date: _____ Permit # _____

Signed: _____

NCDNR PWSS WATER PERMIT #: _____


WATER CAPACITY: _____ GPD

DWQ SEWER PERMIT #: _____

SEWER CAPACITY: _____ GPD

SEWER SHED # AND PLANT: _____


SEWER TO FLOW THROUGH NEI: YES or NO (CIRCLE ONE)




NOTE:
THE CRITICAL ROOT ZONE (CRZ) OF A TREE IS WHERE THE MAJORITY OF A TREE'S ROOTS LAY. 85% OF MOST TREE ROOTS ARE FOUND IN THE TOP 24" OF THE SOIL AND SUPPLY THE MAJORITY OF NUTRIENTS AND WATER. GENERALLY, ROOTS SPREAD OUT 2.5X THE HEIGHT OF THE TREE.

NOTE:
CROWN OF THE TREE IS NEEDED FOR LEAF GROWTH TO PRODUCE OXYGEN, FILTER THE AIR, REDUCE WIND AND SOFTEN NOISE. DO NOT DISRUPT CROWN WITH INTENSIVE PRUNING.


NOTE:
1. PROTECT CRITICAL ROOT ZONE (CRZ) OF TREES PRIOR TO CONSTRUCTION. CLEARLY MARK THE TREES AND DIRECT A PROTECTIVE BARRIER AT THE CRZ. BARRIER SHALL BE MAINTAINED UNTIL CONSTRUCTION IS COMPLETE.
2. CRZ RADIUS IS 1 FT PER INCH OF TREE DIAMETER AT BREAST HEIGHT (DBH).
3. IF CONSTRUCTION OCCURS WITHIN THE CRZ, AT LEAST 12" OF MULCH AND/OR LOGGING MATS SHALL BE PLACED WHERE MACHINERY MANEUVERS TO REDUCE SOIL COMPACTION IN THIS ZONE.
4. WHERE SIDEWALKS AND PATHWAYS PASS WITHIN CRZ, EXTRA CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE ROOTS. ALTERNATE CONSTRUCTION METHODS, SUCH AS A REINFORCED SIDEWALK, SHALL BE IMPLEMENTED AS NECESSARY.
5. FOR ALL TREES, CUTTING OF LARGE STRUCTURAL ROOTS LOCATED NEAR THE BASE OF THE TRUNK IS PROHIBITED. DO NOT COMPACT SOIL BENEATH TREES. NO VEHICLE SHALL BE ALLOWED TO PARK UNDER TREES. NO MATERIALS OR EQUIPMENT SHALL BE STORED BENEATH TREES. DAMAGING THE BARK WITH LAWNMOWERS, CONSTRUCTION EQUIPMENT OR ANYTHING ELSE IS PROHIBITED. CONTRACTOR SHALL REPAIR DAMAGE TO TREES.
6. FAILING TO INSTALL OR MAINTAIN PROTECTION MEASURES SHALL RESULT IN A STOP WORK ORDER AND FINE OF \$500/DAY DISTURBANCE OTHER THAN THAT ALLOWED ON THE APPROVED PLAN WILL REQUIRE OWNER TO POST LETTER OF CREDIT FOR 3 YRS FOR TREE MITIGATION.



NOTE:
1. THE TREE PROTECTION FENCING SHALL NOT BE VIOLATED FOR THE ENTIRE DURATION OF THE PROJECT WITHOUT APPROVAL FROM URBAN FORESTRY STAFF.
2. WARNING SIGNS TO BE MADE OF DURABLE, WEATHERPROOF MATERIAL. LETTERS TO BE 3" HIGH, MINIMUM, CLEARLY LEGIBLE AND SPACED AS DETAILED.
3. SIGNS SHALL BE PLACED AT 50' MAXIMUM INTERVALS. PLACE A SIGN AT EACH END OF LINEAR TREE PROTECTION AND 50' ON CENTER THEREAFTER. FOR TREE PROTECTION AREAS LESS THAN 100' IN PERIMETER, PROVIDE NO LESS THAN TWO SIGNS PER PROTECTION AREA.
4. ATTACH SIGNS SECURELY TO FENCE POSTS AND FABRIC. MAINTAIN TREE PROTECTION AND SIGNS THROUGHOUT DURATION OF PROJECT.
5. TREE PROTECTION FENCING AND SIGNAGE SHALL BE REMOVED AFTER CONSTRUCTION.
6. ADDITIONAL SIGNS MAY BE REQUIRED BY CITY OF WILMINGTON, BASED ON ACTUAL FIELD CONDITIONS.



ROLLED EROSION CONTROL LINING
NOT TO SCALE



TEMPORARY CONSTRUCTION ENTRANCE
NOT TO SCALE

REVISIONS:

CLIENT INFORMATION: ECHO FARMS, LLC
c/o MATRIX DEVELOPMENT GROUP
CN 4000 FORSGATE DRIVE
CRANBURY, NJ 08512

PARAMOUNT ENGINEERING
122 Cinema Drive
Wilmington, North Carolina 28403
(910) 791-0707 (O) (910) 791-6766 (F)
NC License #: C-2846

DETAILS TRACT 2 WOODLANDS AT ECHO FARMS NEW HANOVER COUNTY NORTH CAROLINA

PROJECT STATUS: CONCEPTUAL LAYOUT, PRELIMINARY LAYOUT, RELEASED FOR CONSTRUCTION




DRAWING INFORMATION: 08/09/19, DRAWN: RJK, DESIGNED: RJK, CHECKED: RJK, AEC: RJK

Professional Seal redacted on electronic copy per City of Wilmington Policy

C-5.1

PEI JOB#: 17358.PE

FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION



***NOTE:**
 FOR ALL PONDS, THE CONTRACTOR SHALL ATTACH EACH SKIMMER TO A DRAW DOWN ORIFICE. IF A DRAW DOWN ORIFICE DOES NOT HAVE A SKIMMER ATTACHED TO IT, THEN THE CONTRACTOR SHALL EITHER PLUG OR CAP THE PVC PIPE FOR THAT DRAW DOWN ORIFICE. ONCE THE AREA DRAINING TO THE BASIN IS STABILIZED, THE CONTRACTOR CAN ESTABLISH THE FINAL WET POND, REMOVE THE SKIMMER, AND ANY CAPS OR PLUGS USED AND FILL IN / MORTOR THE ORIFICE.

Approved Construction Plan	
Name	Date
Planning	
Traffic	
Fire	
















NCDENR PWSS WATER PERMIT #: _____
 WATER CAPACITY: _____ GPD
 DWQ SEWER PERMIT #: _____
 SEWER CAPACITY: _____ GPD
 SEWER SHED # AND PLANT: _____
 SEWER TO FLOW THROUGH NEI: YES or NO (CIRCLE ONE)

CITY OF WILMINGTON
 NORTH CAROLINA
 Public Services • Engineering Division
 APPROVED STORMWATER MANAGEMENT PLAN
 Date: _____ Permit # _____
 Signed: _____

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

REVISIONS:
 CLIENT INFORMATION:
 ECHO FARMS, LLC
 c/o MATRIX DEVELOPMENT GROUP
 CN 4000 FORSGATE DRIVE
 CRANBURY, NJ 08512
 PARAMOUNT ENGINEERING
 122 Cinema Drive
 Wilmington, North Carolina 28403
 (910) 791-0707 (O) (910) 791-6766 (F)
 NC License #: C-2846
 PROJECT STATUS:
 CONCEPTUAL LAYOUT:
 PRELIMINARY LAYOUT:
 RELEASED FOR CONSTRUCTION:
 DRAWING INFORMATION:
 DATE: 08/09/19
 DESIGNED: RPB
 DRAWN: AEC
 CHECKED: RPB
 DETAILS TRACT 2 WOODLANDS @ ECHO FARMS NEW HANOVER COUNTY NORTH CAROLINA
 Professional Seal redacted on electronic copy per City of Wilmington Policy
 C-5.2
 PEI JOB#: 17358.PE

FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION



For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.


NODERN PWSS WATER PERMIT # _____
 WATER CAPACITY: _____ GPD
 DWQ SEWER PERMIT # _____
 SEWER CAPACITY: _____ GPD
 SEWER TO FLOW THROUGH NEI: YES or NO (CIRCLE ONE)

FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION

PROJECT STATUS: CONCEPTUAL LAYOUT, PRELIMINARY LAYOUT, RELEASED FOR CONSTRUCTION
 DRAWING INFORMATION: DATE: 08/09/19, DESIGNED BY: AEC, DRAWN BY: AEC, CHECKED BY: AEC
 Professional Seal redacted on electronic copy per City of Wilmington Policy
C-5.3
 PEI JOB#: 17358.PE

CLIENT INFORMATION: ECHO FARMS, LLC
 c/o MATRIX DEVELOPMENT GROUP
 CN-4000 FORSGATE DRIVE
 CRANBURY, NJ 08512


REVISIONS:



DETAIL: CITY OF WILMINGTON REPAIRS/UTILITY CUTS
SCALE: NOT TO SCALE
CFPIA DETAIL DATE: 01/01/19
CFPIA REV. NO.: 1

CAPE FEAR PUBLIC UTILITY AUTHORITY
235 GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403
OFFICE: (910)332-6560


DETAIL NO: WS-1
SHEET NO: -



DETAIL: PIPE EMBEDMENT TYPES
SCALE: NOT TO SCALE
CFPIA DETAIL DATE: 01/01/19
CFPIA REV. NO.: 1

CAPE FEAR PUBLIC UTILITY AUTHORITY
235 GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403
OFFICE: (910)332-6560


DETAIL NO: WS-4
SHEET NO: -



DETAIL: VALVE DETAIL
SCALE: NOT TO SCALE
CFPIA DETAIL DATE: 01/01/19
CFPIA REV. NO.: 1

CAPE FEAR PUBLIC UTILITY AUTHORITY
235 GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403
OFFICE: (910)332-6560


DETAIL NO: WS-6
SHEET NO: -



DETAIL: TRACER WIRE DETAIL
SCALE: NOT TO SCALE
CFPIA DETAIL DATE: 01/01/19
CFPIA REV. NO.: 1

CAPE FEAR PUBLIC UTILITY AUTHORITY
235 GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403
OFFICE: (910)332-6560


DETAIL NO: WS-7
SHEET NO: -



DETAIL: TYPICAL BORING & JACKING DETAIL
SCALE: NOT TO SCALE
CFPIA DETAIL DATE: 01/01/19
CFPIA REV. NO.: 1

CAPE FEAR PUBLIC UTILITY AUTHORITY
235 GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403
OFFICE: (910)332-6560


DETAIL NO: WS-8
SHEET NO: -



DETAIL: TAPPING SLEEVE AND VALVE ASSEMBLY (4" DIA.)
SCALE: NOT TO SCALE
CFPIA DETAIL DATE: 01/01/19
CFPIA REV. NO.: 1

CAPE FEAR PUBLIC UTILITY AUTHORITY
235 GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403
OFFICE: (910)332-6560


DETAIL NO: WS-9
SHEET NO: -



DETAIL: PRESSURE MAIN DITCH AND STORM DRAIN DITCH CROSSING-DIP
SCALE: NOT TO SCALE
CFPIA DETAIL DATE: 01/01/19
CFPIA REV. NO.: 1

CAPE FEAR PUBLIC UTILITY AUTHORITY
235 GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403
OFFICE: (910)332-6560

DETAIL NO: WS-10
SHEET NO: -



DETAIL: STRUCTURAL BORING OVER WATER/SEWER LINES
SCALE: NOT TO SCALE
CFPIA DETAIL DATE: 01/01/19
CFPIA REV. NO.: 1

CAPE FEAR PUBLIC UTILITY AUTHORITY
235 GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403
OFFICE: (910)332-6560

DETAIL NO: WS-11
SHEET NO: -

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

NCDENR PWSS WATER PERMIT #: _____


WATER CAPACITY: _____ GPD

DWQ SEWER PERMIT #: _____

SEWER CAPACITY: _____ GPD

SEWER SHED # AND PLANT: _____

SEWER TO FLOW THROUGH NEI: YES or NO (CIRCLE ONE)



DETAIL: THRUST BLOCK
SCALE: NOT TO SCALE
CFPIA DETAIL DATE: 01/01/19
CFPIA REV. NO.: 1

CAPE FEAR PUBLIC UTILITY AUTHORITY
235 GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403
OFFICE: (910)332-6560

DETAIL NO: WS-12
SHEET NO: -

ANCHOR STRAPS

45° VERTICAL BENDS

PLAN BENDS

PLAN TEES

SIZE	90 BENDS		45 BENDS		22-1/2 BENDS		TEES/PLUGS		45 VERT. BENDS	
	A	B	A	B	A	B	A	B	A	B
3"	8"	6"	5"	6"	3"	7"	6"	6"	27"	
4"	8"	6"	5"	6"	3"	7"	6"	6"	28"	
6"	14"	11"	9"	9"	8"	8"	12"	9"	36"	
8"	18"	16"	12"	12"	10"	13"	14"	13"	42"	
10"	18"	22"	10"	14"	14"	16"	18"	15"	50"	
12"	20"	26"	18"	17"	16"	16"	22"	18"	62"	
14"	26"	29"	21"	19"	18"	18"	26"	20"	72"	
16"	33"	29"	26"	21"	20"	21"	32"	21"	83"	
18"	40"	30"	28"	24"	22"	23"	36"	24"	88"	

DETAIL: STANDARD NOTES
SCALE: NOT TO SCALE
CFPIA DETAIL DATE: 01/01/19
CFPIA REV. NO.: 1

CAPE FEAR PUBLIC UTILITY AUTHORITY
235 GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403
OFFICE: (910)332-6560

DETAIL NO: WS-13
SHEET NO: -

CAPE FEAR PUBLIC UTILITY AUTHORITY STANDARD NOTES:

- SEWER GUARDS REQUIRED AT ALL MANHOLES. STAINLESS STEEL SEWER GUARDS REQUIRED AT MANHOLES LOCATED IN TRAFFIC AREAS.
- WATER AND SEWER SERVICES SHALL BE PERPENDICULAR TO MAIN AND TERMINATE 18" INSIDE RIGHT-OF-WAY LINE. SEWER SERVICES IN CUL-DE-SACS ARE REQUIRED TO BE PERPENDICULAR, OR MUST ORIGINATE IN END OF LINE MANHOLE AND TERMINATE 18" INSIDE RIGHT-OF-WAY LINE.
- ALL SEWER SERVICES CONNECTING INTO DUCTILE IRON MAINS SHALL ALSO BE CONSTRUCTED OF DIP.
- MINIMUM 10' UTILITIES EASEMENT PROVIDED ALONG THE FRONTAGE OF ALL LOTS AND AS SHOWN FOR NEW DEVELOPMENTS.
- NO FLEXIBLE COUPLINGS SHALL BE USED.
- ALL STAINLESS STEEL FASTENERS SHALL BE TYPE 316.
- CLEANOUTS SHALL BE LOCATED A MINIMUM OF 12 FEET FROM PROPERTY CORNERS.
- WATER METER BOXES ARE TO BE A MINIMUM OF 5 FEET FROM THE PROPERTY CORNER.
- UNUSED SERVICES SHALL BE ABANDONED. ABANDONED WATER SERVICES SHALL BE DISCONNECTED FROM MAIN.
- A MINIMUM OF 10' OF MAIN LINE SHALL BE REPLACED FOR NEW CONNECTIONS TO EXISTING CLAY GRAVITY SEWER MAINS.

DETAIL: STANDARD NOTES
SCALE: NOT TO SCALE
CFPIA DETAIL DATE: 01/01/19
CFPIA REV. NO.: 1

CAPE FEAR PUBLIC UTILITY AUTHORITY
235 GOVERNMENT CENTER DRIVE
WILMINGTON, NC 28403
OFFICE: (910)332-6560

DETAIL NO: WS-14
SHEET NO: -

FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION

REVISIONS:

CLIENT INFORMATION:

ECHO FARMS, LLC
c/o MATRIX DEVELOPMENT GROUP
CN-4000 FORSGATE DRIVE
CRANBURY, NJ 08512

PARAMOUNT ENGINEERING
122 Cinema Drive
Wilmington, North Carolina 28403
(910) 791-6707 (O) (910) 791-6766 (F)
NC License #: C-2846

















PROJECT STATUS:
CONCEPTUAL LAYOUT:
PRELIMINARY LAYOUT:
RELEASED FOR CONST.

DRAWING INFORMATION:
DATE: 08/09/19
DESIGNED: AEC
DRAWN: AEC
CHECKED: RPB

Professional Seal
redacted on electronic
copy per City of
Wilmington Policy

C-5.4

PEI JOB#: 17358.PE



GENERAL NOTES:

CHAMFER ALL CORNERS 1" OR HAVE A RADIUS OF 1".

PLACE 2 #6 "Y" BARS IN THE TOP OF ALL ENDWALL FOR PIPE CULVERTS 42" AND OVER WITH A MINIMUM OF 3" COVER AND A LENGTH OF 6" LESS THAN ENDWALL LENGTH.

CONSTRUCT BOTTOM SLAB WITH FORMS.

DO NOT INTERPRET WALL THICKNESS (T) SHOWN FOR THE THICKNESS ACCEPTABLE, BUT IS USED IN COMPUTING ENDWALL QUANTITIES.

WHEN THE CONTRACTOR ELECTS TO USE A CONSTRUCTION JOINT AT THE BOTTOM OF THE PIPE, PLACE BAR "X" DOWELS IN THE BASE AS SHOWN ON PLANS SPACE BARS APPROXIMATELY ON 12" CENTERS UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

WHEN THE CONTRACTOR ELECTS TO USE A CONSTRUCTION JOINT AT THE BOTTOM OF THE PIPE AND POUR THE BASE SEPARATELY LEAVE THE POUR ROUGH.

USE CLASS "B" CONCRETE.

REVISIONS:

CLIENT INFORMATION: ECHO FARMS, LLC
c/o MATRIX DEVELOPMENT GROUP
CN-4000 FORSGATE DRIVE
CRANBURY, NJ 08512

PARAMOUNT ENGINEERING
122 Cinema Drive
Wilmington, North Carolina 28403
(910) 791-6707 (O) (910) 791-6766 (F)
NC License #: C-2846

DETAILS TRACT 2 WOODLANDS @ ECHO FARMS NEW HANOVER COUNTY NORTH CAROLINA

PROJECT STATUS: CONCEPTUAL LAYOUT, PRELIMINARY LAYOUT, RELEASED FOR CONSTRUCTION

DRAWING INFORMATION: DATE: 08/09/19, DESIGNED: AEC, DRAWN: AEC, CHECKED: RPB

Professional Seal redacted on electronic copy per City of Wilmington Policy

C-5.5

PEI JOB#: 17358.PE

FINAL DESIGN - NOT RELEASED FOR CONSTRUCTION

For each open utility cut of City streets, a \$325 permit shall be required from the City prior to occupancy and/or project acceptance.

NCDENR PWSS WATER PERMIT #: _____
WATER CAPACITY: _____ GPD
DWQ SEWER PERMIT #: _____
SEWER CAPACITY: _____ GPD
SEWER SHED # AND PLANT: _____
SEWER TO FLOW THROUGH NEI: YES or NO (CIRCLE ONE)