



Engineering 212 Operations Center Drive Wilmington, NC 28412 910 341-7807 910 341-5881 fax wilmingtonnc.gov Dial 711 TTY/Voice

COMPREHENSIVE STORMWATER MANAGEMENT PERMIT

HIGH DENSITY DEVELOPMENT

SECTION 1 – APPROVAL

Having reviewed the application and all supporting materials, the City of Wilmington has determined that the application is complete and the proposed development meets the requirements of the City of Wilmington's Comprehensive Stormwater Ordinance.

PROJECT:

PERMIT HOLDER: GPT Investments, LLC

ADDRESS:

Bluewater Motorsports 6753 & 6757 Market Street

PERMIT #:

2018055

DATE:

January 9, 2019

Therefore, the above referenced site is hereby approved and subject to all conditions set forth in Section 2 of this approval and all applicable provisions of the City of Wilmington Comprehensive Stormwater Management Ordinance.

This permit shall be effective from the date of issuance until January 9, 2029 and shall be subject to the following specified conditions and limitations:

Section 2 - CONDITIONS

- This approval is valid only for the stormwater management system as proposed on 1. the approved stormwater management plans dated January 9, 2019.
- 2. The project will be limited to the amount and type of built-upon area indicated in Section IV of the Stormwater Management Application Form submitted as part of the approved stormwater permit application package, and per the approved plans.
- 3. This permit shall become void unless the facilities are constructed in accordance with the approved stormwater management plans, specifications and supporting documentation, including information provided in the application and supplements.
- The runoff from all built-upon area within any permitted drainage area must be 4. directed into the permitted stormwater control system for that drainage area.





Engineering
212 Operations Center Drive
Wilmington, NC 28412
910 341-7807
910 341-5881 fax
wilmingtonnc.gov
Dial 711 TTY/Voice

- 5. The permittee shall submit a revised stormwater management application packet to the City of Wilmington and shall have received approval prior to construction, for any modification to the approved plans, including, but not limited to, those listed below:
 - a. Any revision to any item shown on the approved plans, including the stormwater management measures, built-upon area, details, etc.
 - Redesign or addition to the approved amount of built-upon area or to the drainage area.
 - c. Further subdivision, acquisition, lease or sale of any part of the project area.
 - d. Filling in, altering, or piping of any vegetative conveyance shown on the approved plan.
 - e. Construction of any permitted future areas shown on the approved plans.
- 6. A copy of the approved plans and specifications shall be maintained on file by the Permittee.
- 7. During construction, erosion shall be kept to a minimum and any eroded areas of the system will be repaired immediately.
- 8. If the stormwater system was used as an Erosion Control device, it must be restored to design condition prior to operation as a stormwater treatment device, and prior to issuance of any certificate of occupancy for the project.
- 9. All areas must be maintained in a permanently stabilized condition. If vegetated, permanent seeding requirements must follow the guidelines established in the North Carolina Erosion and Sediment Control Planning and Design Manual unless an alternative is specified and approved by the City of Wilmington.
- 10. All applicable operation & maintenance agreements and easements pertaining to each stormwater treatment system shall be referenced on the final plat and recorded with the Register of Deeds upon final plat approval. If no plat is recorded for the site the operation and maintenance agreements and easements shall be recorded with the Register of Deeds so as to appear in the chain of title of all subsequent purchasers under generally accepted searching standards.
- 11. The stormwater management system shall be constructed in its entirety, vegetated and operational for its intended use prior to the construction of any built-upon surface unless prior approval is obtained. City Staff must be notified of any deviation prior to construction of the built-upon surface. Any deviation request shall include justification and must propose an alternative timeline or construction sequence. Notification shall not constitute approval. Any alternative timeline approved by City staff shall become an enforceable component of this permit.





Engineering
212 Operations Center Drive
Wilmington, NC 28412
910 341-7807
910 341-5881 fax
wilmingtonnc.gov
Dial 711 TTY/Voice

12. The permittee shall at all times provide the operation and maintenance necessary to assure the permitted stormwater system functions at optimum efficiency. The approved Operation and Maintenance Agreement must be followed in its entirety and maintenance must occur at the scheduled intervals including, but not limited to:

a. Scheduled inspections (interval noted on the agreement).

b. Sediment removal.

Mowing and revegetation of slopes and the vegetated areas.

d. Maintenance of landscape plants, including those within the landscape buffer and on the vegetated shelf.

e. Immediate repair of eroded areas, especially slopes.

- f. Debris removal and unclogging of outlet structure, orifice device, flow spreader, catch basins and/or piping.
- g. Access to the outlet structure must be available at all times.
- 13. Records of inspection, maintenance and repair for the permitted stormwater system must be kept by the permittee for at least 5 years from the date of record and made available upon request to authorized personnel of the City of Wilmington. The records will indicate the date, activity, name of person performing the work and what actions were taken.
- 14. Upon completion of construction, before a Certificate of Occupancy shall be granted, and prior to operation or intended use of this permitted facility, the applicant shall submit to the City of Wilmington as-built plans for all stormwater management facilities. The plans shall show the final design specifications and the field location, type, depth, invert and planted vegetation of all measures, controls and devices, as-installed. A certification shall be submitted, along with all supporting documentation that specifies, under seal that the as-built stormwater measures, controls and devices are in compliance with the approved stormwater management plans. A final inspection by City of Wilmington personnel will be required prior to issuance of a certificate of occupancy or operation of the permitted facility.
- 15. This permit is not transferable except after application and approval by the City of Wilmington. In the event of a change of ownership, name change or change of address the permittee must submit a completed Name/Ownership Change form to the City of Wilmington at least 30 days prior to the change. It shall be signed by all applicable parties, and be accompanied by all required supporting documentation. Submittal of a complete application shall not be construed as an approved application. The application will be reviewed on its own merits by the City of Wilmington and may or may not be approved. The project must be in compliance with the terms of this permit in order for the transfer request to be considered. The permittee is responsible for compliance with all permit conditions until such time as the City of Wilmington approves the transfer request. Neither the sale of the project nor the conveyance of common area to a third party should be considered as an approved transfer of the permit.
- 16. Failure to abide by the conditions and limitations contained in this permit may subject the Permittee to enforcement action by the City of Wilmington, in accordance with Sections 18-52 and 18-53 and any other applicable section of the Land Development Code.





Engineering 212 Operations Center Drive Wilmington, NC 28412 910 341-7807 910 341-5881 fax wilmingtonnc.gov Dial 711 TTY/Voice

- 17. The City of Wilmington may notify the permittee when the permitted site does not meet one or more of the minimum requirements of the permit. Within the time frame specified in the notice, the permittee shall submit a written time schedule to the City of Wilmington for modifying the site to meet minimum requirements. The permittee shall provide copies of revised plans and certification in writing to the City of Wilmington that the changes have been made.
- 18. The issuance of this permit does not preclude the Permittee from complying with any and all statutes, rules, regulations, or ordinances, which may be imposed by other government agencies (local, state, and federal) having jurisdiction.
- 19. In the event that the facilities fail to perform satisfactorily, including the creation of nuisance conditions, the Permittee shall take immediate corrective action, including those as may be required by the City of Wilmington, such as the construction of additional or replacement stormwater management systems.
- 20. The permittee grants City of Wilmington Staff permission to enter the property during normal business hours for the purpose of inspecting all components of the permitted stormwater management facility.
- 21. The permit issued shall continue in force and effect until revoked or terminated by the City of Wilmington. The permit may be modified, revoked and reissued or terminated for cause. The filing of a request for a permit modification, revocation and re-issuance or termination does not stay any permit condition.
- 22. The approved stormwater management plans and all documentation submitted as part of the approved stormwater management permit application package for this project are incorporated by reference and are enforceable parts of the permit.
- 23. The permittee shall submit a renewal request with all required forms and documentation at least 180 days prior to the expiration date of this permit.
- 24. If any one or more of the conditions of this permit is found to be unenforceable or otherwise invalidated, all remaining conditions shall remain in full effect.

Stormwater Management Permit issued this the 9th day of January, 2019

for Sterling Cheatham, City Manager

City of Wilmington

SWP2018055





Public Services
Engineering
212 Operations Center Dr
Wilmington, NC 28412
910 341-7807
910 341-5881 fax
wilmingtonnc.gov
Dial 711 TTY/Voice

STORMWATER MANAGEMENT PERMIT APPLICATION FORM (Form SWP 2.2)

l.	GENERAL INFORMATION
1.	Project Name (subdivision, facility, or establishment name - should be consistent with project name on plans, specifications, letters, operation and maintenance agreements, etc.):
	Bluewater Motorsports
2.	Location of Project (street address): 6753 & 6757 Market Street
	City: Wilmington County: New Hanover Zip: 28405
3.	Directions to project (from nearest major intersection):
	From the intersection of US 17 (Market Street) and SR 2048 (Gordon Road), travel approx. 0.4 miles
	southwest on Market Street. Site is on the right.
II.	PERMIT INFORMATION
1.	Specify the type of project (check one): Low Density x High Density Drains to an Offsite Stormwater System Drainage Plan Other If the project drains to an Offsite System, list the Stormwater Permit Number(s):
	City of Wilmington: State – NCDENR/DWQ:
2.	Is the project currently covered (whole or in part) by an existing City or State (NCDENR/DWQ) Stormwater Permit? Yes x No If yes, list all applicable Stormwater Permit Numbers:
	City of Wilmington: State – NCDENR/DWQ:
3.	Additional Project Permit Requirements (check all applicable): CAMA Major X Sedimentation/Erosion Control NPDES Industrial Stormwater 404/401 Permit: Proposed Impacts: If any of these permits have already been acquired please provide the Project Name, Project/Permit Number, issue date and the type of each permit:



III. CONTACT INFORMATION

1.	designated government official, individual, etc. who owns the project):					
	Applicant / Organization: GPT Investments, LLC					
	Signing Official & Title:Gregory P. Tarlton, Member Manager					
	a. Contact information for Applicant / Signing Official:					
	Street Address: 140 King Arthur Drive					
	City: Wilmington State: NC Zip: 28403					
	Phone: 910-584-1008 Fax:Email: gtarlton333@gmail.com					
	Mailing Address (if different than physical address):					
	City:State:Zip:					
	b. Please check the appropriate box. The applicant listed above is:					
	 The property owner (Skip to item 3) Lessee* (Attach a copy of the lease agreement and complete items 2 and 2a below) Purchaser* (Attach a copy of the pending sales agreement and complete items 2 and 2a below) Developer* (Complete items 2 and 2a below.) 					
2.	Print Property Owner's name and title below, if you are the lessee, purchaser, or developer. (This is the person who owns the property that the project is on.)					
	Property Owner / Organization:					
	Signing Official & Title:					
	a. Contact information for Property Owner:					
	Street Address:					
	City:State:Zip:					
	Phone:Fax:Email:					
	Mailing Address (if different than physical address):					
	City:State:Zip:					
3.	(Optional) Print the name and title of another contact such as the project's construction supervisor or another person who can answer questions about the project:					
	Other Contact Person / Organization:					
	Signing Official & Title:					

 \checkmark



IV.	Street Address: City: Phone: Fax: Mailing Address (if different than physical address)	_State:				
IV.	Phone:Fax:					
IV.		_Email:				
IV.	waning Address (ii dinerent than physical addre					
IV.	City:					
	PROJECT INFORMATION					
1.	In the space provided below, briefly summarize how	the store	mwater runoff will be treated			
	Underground infiltration rain tanks					
	Ondorground Infinacion full tuling					
2.	Total Property Area: 111,580 square feet					
3.	Total Coastal Wetlands Area: 0 square	feet				
	Total Surface Water Area:square feet					
5.	Total Property Area (2) – Total Coastal Wetlands Area (3) – Total Surface Water Area (4) = Total Project Area:111,580 square feet.					
	Existing Impervious Surface within Property Area: 17,472 square feet					
	Existing Impervious Surface to be Removed/Demoli					
	Existing Impervious Surface to Remain:15,420		•			
		'				
9.	Total Onsite (within property boundary) Newly Cons	tructed in	mpervious Surface (in square feet):			
	Buildings/Lots		0			
1	Impervious Pavement		56,428			
	Pervious Pavement (adj. total, with % credit appli	ied)	0			
	Impervious Sidewalks		132			
Pervious Sidewalks (adj. total, with % credit applied) ()						
(Other (describe)		0			
<u> </u>	Future Development		1,020			
L	Total Onsite Newly Constructed Impervious Surface		57,580			
(Total Onsite Impervious Surface (Existing Impervious Surface to remain + Onsite Newly Construct Project percent of impervious area: (Total Onsite Imperv		vious Surface) = <u>73,000</u> square fe			



12. Total Offsite Newly Constructed Impervious Area (improvements made outside of property boundary, in square feet):

Impervious Pavement		782
Pervious Pavement (adj. total, with	% credit applied)	0
Impervious Sidewalks		0
Pervious Sidewalks (adj. total, with	% credit applied)	0
Other (describe)		0
Total Offsite Newly Constructed Imper	vious Surface	782

13. Total Newly Constructed Impervious Surface		
(Total Onsite + Offsite Newly Constructed Impervious Surface) =	58,362	square feet

14. Complete the following information for each Stormwater BMP drainage area. If there are more than three drainage areas in the project, attach an additional sheet with the information for each area provided in the same format as below. Low Density projects may omit this section and skip to Section V.

Basin Information	BMP#	BMP#	BMP#
Receiving Stream Name	UT to Smith Cre	ek	
Receiving Stream Index Number	C;Sw		
Stream Classification	18-74-63		***************************************
Total Drainage Area (sf)	111,580		
On-Site Drainage Area (sf)	111,580		
Off-Site Drainage Area (sf)	0		
Total Impervious Area (sf)	73,000		
Buildings/Lots (sf)	0		
Impervious Pavement (sf)	56,428	7,1	
Pervious Pavement (sf)	0	***************************************	
Impervious Sidewalks (sf)	132	<u> </u>	·
Pervious Sidewalks (sf)	0	***	
Other (sf)	0		
Future Development (sf)	1,020		· · · · · · · · · · · · · · · · · · ·
Existing Impervious to remain (sf)	15,420		
Offsite (sf)	0	-	
Percent Impervious Area (%)	65.4		

15. How was the off-site impervious area listed above determined? Provide documentation:



V. SUBMITTAL REQUIREMENTS

- Supplemental and Operation & Maintenance Forms One applicable City of Wilmington Stormwater BMP supplement form and checklist must be submitted for each BMP specified for this project. One applicable proposed operation and maintenance (O&M) form must be submitted for each type of stormwater BMP. Once approved, the operation and maintenance forms must be referenced on the final plat and recorded with the register of deeds office.
- 2. Deed Restrictions and Restrictive Covenants For all subdivisions, outparcels, and future development, the appropriate property restrictions and protective covenants are required to be recorded prior to the sale of any lot. Due to variability in lot sizes or the proposed BUA allocations, a table listing each lot number, lot size, and the allowable built-upon area must be provided as an attachment to the completed and notarized deed restriction form. The appropriate deed restrictions and protective covenants forms can be downloaded at the link listed in section V (3). Download the latest versions for each submittal.

In instances where the applicant is different than the property owner, it is the responsibility of the property owner to sign the deed restrictions and protective covenants form while the applicant is responsible for ensuring that the deed restrictions are recorded.

By the notarized signature(s) below, the permit holder(s) certify that the recorded property restrictions and protective covenants for this project, if required, shall include all the items required in the permit and listed on the forms available on the website, that the covenants will be binding on all parties and persons claiming under them, that they will run with the land, that the required covenants cannot be changed or deleted without concurrence from the City of Wilmington, and that they will be recorded prior to the sale of any lot.

3. Only complete application packages will be accepted and reviewed by the City. A complete package includes all of the items listed on the City Engineering Plan Review Checklist, including the fee. Copies of the Engineering Plan Review Checklist, all Forms, Deed Restrictions as well as detailed instructions on how to complete this application form may be downloaded from:

http://www.wilmingtonnc.gov/PublicServices/Engineering/PlanReview/StormwaterPermits.aspx

The complete application package should be submitted to the following address:

City of Wilmington – Engineering Plan Review Section 212 Operations Center Dr Wilmington, NC 28412



VI. CONSULTANT INFORMATION AND AUTHORIZATION

1.	. Applicant: Complete this section if you wish to designate authority to another individual and (such as a consulting engineer and /or firm) so that they may provide information on your be this project (such as addressing requests for additional information).	
	Consulting Engineer: Phillip G. Tripp, P.E.	
	Consulting Firm:Tripp Engineering	
	a. Contact information for consultant listed above:	
	Mailing Address: 419 Chestnut Street	
	City: Wilmington State: NC Zip: 28401	
	Phone: 910-763-5100 Fax: 910-763-5631 Email: office@trippengineering.com	
VII	/II. PROPERTY OWNER AUTHORIZATION (If Section III(2) has been filled out, complete this section	n)
pers liste pro the sto As des	with (print or type name of organ with (print or type name of organ sted in Contact Information, item 1) with (print or type name of organ to develop the project as custoposed. A copy of the lease agreement or pending property sales contract has been provided ne submittal, which indicates the party responsible for the operation and maintenance of the tormwater system. As the legal property owner I acknowledge, understand, and agree by my signature below, that designated agent (entity listed in Contact Information, item 1) dissolves their company and/or cancelefaults on their lease agreement, or pending sale, responsibility for compliance with the City of Vilmington Stormwater Permit reverts back to me, the property owner. As the property owner, in the company owner, in the property owner, in the property owner.	ization irrently d with if my els or f
res Ch val	esponsibility to notify the City of Wilmington immediately and submit a completed Name/Owne change Form within 30 days; otherwise I will be operating a stormwater treatment facility withoualid permit. I understand that the operation of a stormwater treatment facility without a valid perion iolation of the City of Wilmington Municipal Code of Ordinances and may result in appropriate	rship ut a
s	SEAL enforcement including the assessment of civil penalties.	
	Signature:	
	Date:	
	l,, a Notary Public f	or the
	State of, County of,	
	hereby certify that	
	personally appeared before me this day of,	



and acknowledge the due execution	n of the application for a stormwater permit. Witness my hand and officia	al seal,
My commission expires:		
VIII. APPLICANT'S CERTIFIC	CATION	
that the information included on that the project will be constructed restrictions and protective coven SEAL C. BA	Contact Information, item 1) , Gregory P. Tarlton Cothis permit application form is, to the best of my knowledge, corrected in conformance with the approved plans, that the required dead ants will be recorded, and that the proposed project complies with requirements of the applicable stormwater rules under. Signature: Date: 7/9/8	ł
PUBLIC COUNTY	I, Della C. Baid, a Notary Public for to State of North Carolina, County of, do hereby certify that Gregory P. Torloton personally appeared before me this day of, 20 and acknowledge the due execution of the application for a stormwater	<u>18</u> ,
permit. Witness my hand and official way. My commission expires:		i.



Please indicate the types, quantities and locations of SCMs that will be used on this project

		Treatment Swale
		Disconnected Impervious Surface
		Level Spreader-Filter Strip
		Green Roof
		Rainwater Harvesting
		Sand Filter
		Permeable Pavement
		Stormwater Wetland
		Wet Pond
		Bioretention Cell
under parking lot		Infiltration System
Location(s)	Cuality	

Project Name:

Bluewater Motorsports

Address

6753 Market Street

City / Town

Wilmington

Applicant:

Designer information for this project:

Email:	Phone number(s): 910-584-1008	City, State, Zip:	Mailing Address:	Contact:	Company:
gtarlton333@gmail.com	910-584-1008	Wilmington, NC 28403	140 King Arthur Drive	Greg Tarlton, member manager	GPT Investments, LLC


Designer

Email:

Phone number(s): City, State, Zip: Street address: Organization: Name and Title

910-763-5100 trippeng@ec.rr.com

Wilmington, NC 28401 419 Chestnut Street Tripp Engineering, P.C. Phillip G. Tripp, P.E.



Date



Certification Statement:

- I certify, under penalty of law: that this Supplement-EZ form and all supporting information were prepared under my direction or supervision;
 that the information provided in the form is, to the best of my knowledge and belief, true, accurate, and complete; and
- that the engineering plans, specifications, operation and maintenance agreements and other supporting information are consistent with the information provided here.

I am aware that there are significant penalties for submitting false information including the possibility of fines and imprisonment for knowing violations as well as a report being made to my professional board



INFILTRATION SYSTEMS

Bluewater Motorsports

	PROPERTY CONTRACTOR SANCE SANC		Wanter Toolsand Michael Charles of Charles and Charles
Diamage area number	_	Break down of BUA in the drainage area (both new and existing):	
Total coastal wetlands area (sq ft)	sf	- Parking / driveway (sq ft)	64816 sf
Total surface water area (sq ft)	sf		2340 sf
Total drainage area (sq ft)	111580 sf	- Roof (sq ft)	4824 sf
BUA associated with existing development (sq ft)	0.00	- Roadway (sq ft)	sf
Proposed new BUA (sq ft)	73000 sf	- Other, please specify in the comment box below (sq ft)	1020 sf
Percent BUA of drainage area	65.4	Total BUA (sq ft)	73000 sf
COMPLIANCE WITH THE APPLICABLE STORMWATER PROGRAM			, 0000 0
Stormwater program(s) that apply (please specify):		Design rainfall depth (in)	1.5 in
O assizi	A CONTRACTOR OF THE CONTRACTOR	Minimum volume required (cu ft)	8910 cf
GENERAL MDC FROM 02H .1050			12 C7 97 th
#1 Is the SCM sized to treat the SW from all surfaces at build-out?	Yes	#7 If applicable, with the SCM he cleaned out after construction?	PROBREMON AND AND AND AND AND AND AND AND AND AN
#2 Is the SCM located on or near contaminated soils?	No	Does the maineter	Ype
#3 What are the side slopes of the SCM (H:V)?		#9 Does the drainage easement comply with General MDC (9)?	No S
#3 Does the SCM have retaining walls, gabion walls or other engineered side slopes?	No	#10 If the SCM is on a single family lot, does the plat comply with General MDC (10)?	
#4 Are the inlets, outlets, and receiving stream protected from erosion (10-year storm)?	Yes	#11 Is there an O&M Agreement that complies with General MDC (11)?	Yes
#5 Is there a a bypass for flows in excess of the design flow?	Yes	Is there an O&M	Yes
#6 What is the method for dewatering the SCM for maintenance?		#13 Was the SCM designed by an NC licensed professional?	Yes
INFILTRATION SYSTEM MDC FROM 02H .1051			CATALOGUE SAN
#1 SHWT elevation (fmsl)	36.75	#5 Length (ft)	206 (varies)
#1 Was the soil investigated in the footprint and at the elevation of the infiltration system?	Yes	#5 Width (ft)	100 (varies)
#1 Soil infiltration rate (in/hr)	1.5 in/hr	#5 Depth/Height (ft)	2.16
#1 Briefly describe the hydraulic properties and characteristics of the soil profile:		#5 Surface area of the bottom of the infiltration system (sq feet)	20682 sf
clean tine sands to depth of 84 inches below the ground surface. No distinct zones of soil cementation were encountered	ion were	#5 Ponding depth of the design volume (in)	2.16
		#5 Estimated dewatering time (hours)	17.28
	Management of the control of the con	#5 For trenches only: Perforated pipe diameter, if applicable (inches)	see plan
#2 SHWT elevation (fmsl)	36.75	#5 For trenches only: Number of laterals	see plan
	38.75	#5 For trenches only: Stone type, if applicable	N/A
#2 Is a detailed hydrogeologic study attached if the separation is between 1 and 2 feet?	Trees for all forms of green representations of the second of the company of the		Sand 40% N/A
#3 Proposed slope of the subgrade surface (%)	0%	#5 For trenches only: Is stone free of fines?	
#3 Are terraces or baffles provided?	No	#5 For trenches only: Is the stone wrapped in geotextile fabric?	Yes
#4 Describe the pretreatment that will be provided:		#6 Is the infiltration system located underground?	Yes
		#6 If so, has at least one infiltration port been provided?	Yes

Please use this space to provide any information about this infiltration system that you think is relevant to the review: Future is impervious available for minor changes to layout.



Operat	ion & Maint	enance Agree	ment
Project Name: Blue	water Motors	ports	
Project Location: 6753	& 6757 Marke	et Street	
	Cove	r Page	
Maintenance records shall be kept on the followant deficient BMP elements noted in the inspection.	owing BMP(s). This ection will be correc	maintenance record shated, repaired, or replaced	d immediately. These deficiencies can
affect the integrity of structures, safety of the	oublic, and the pollu	tant removal efficiency o	f the BMP(s).
The BMP(s) on this project include (check all the	hat apply & corrosp	anding OOM tables will be	and and another afficult As
Bioretention Cell	Quantity:	Location(s):	be added automatically).
Dry Detention Basin	Quantity:	Location(s):	
Grassed Swale	Quantity:	Location(s):	
Green Roof	Quantity:	Location(s):	
Infiltration Basin	Quantity:	Location(s):	
Infiltration Trench	Quantity: 1		under parking lot
Level Spreader/VFS	Quantity:	Location(s):	
Permeable Pavement	Quantity:	Location(s):	
Proprietary System	Quantity:	Location(s):	
Rainwater Harvesting Sand Filter	Quantity:	Location(s):	
Stormwater Wetland	Quantity:	Location(s):	
Wet Detention Basin	Quantity: 0	Location(s):	
Disconnected Impervious Area	Present: No		
User Defined BMP	Present: No		
Street address: 140 in City, state, zip: Wilmin Phone number(s): 910-58	ber Manager, GPT (ing Arthur Drive gton, NC 28403	Investments, LLC	
Linaii. gtarito			
	0/1		, ,
Signature:	1. J.M.		Date: 7/19/18
Della Parid		otary Public for the State	
County of Londer	, do h	The state of the s	Gregory 1. Tarleton
personally appeared before me this	<u>19</u> day		and
acknowledge the due execution of the Operation		e Agreement .	
Witness my hand and official seal,	acrail	900	
Witness my hand and official seal, OTAR OUBLIC OUBLIC			DEGETVED AUG - 7 2018 ENGINEERING
Seal My commission e	expires	10-15-21	

Infiltration System Maintenance Requirements

Important maintenance procedures:

- The drainage area will be carefully managed to reduce The sediment load to The infiltration basin.
- Immediately after the infiltration basin is established, the vegetation will be watered twice weekly if needed until the plants become established (commonly six weeks).
- No portion of the infiltration basin will be fertilized after the initial fertilization that is required to establish the vegetation.
- The vegetation in and around the basin will be maintained at a height of approximately six inches.

After the infiltration basin is established, it shall be inspected once a quarter and within 24 hours after every storm event greater than 1.0 inches (or 1.5 inches if in a Coastal County). Records of operation and maintenance shall be kept in a known set location and shall be available upon request.

Inspection activities shall be performed as follows. Any problems that are found shall be repaired immediately.

BMP element:	Potential problem:	How to remediate the problem:
The entire BMP	Trash/debris is present.	Remove the trash/debris.
The perimeter of the infiltration basin	Areas of bare soil and/or erosive gullies have formed.	Regrade the soil if necessary to remove the gully, and then plant a ground cover and water until it is established. Provide lime and a one time fertilizer application.
The inlet device: pipe or swale	The pipe is clogged (if applicable).	Unclog the pipe. Dispose of the sediment off-site.
	The pipe is cracked or otherwise damaged (if applicable).	Replace the pipe.
	Erosion is occurring in the swale (if applicable).	Regrade the swale if necessary to smooth it over and provide erosion control devices such as reinforced turf matting or riprap to avoid future problems with erosion.
The forebay	Sediment has accumulated and reduced the depth to 75% of the original design depth.	Search for the source of the sediment and remedy the problem if possible. Remove the sediment and dispose of it in a location where i will not cause impacts to streams or the BMP.
	Erosion has occurred or riprap is displaced.	Provide additional erosion protection such as reinforced turf matting or riprap if needed to prevent future erosion problems.
	Weeds are present.	Remove the weeds, preferably by hand. If pesticides are used, wipe them on the plants rather than spraying.
The main treatment area	A visible layer of sediment has accumulated.	Search for the source of the sediment and remedy the problem if possible. Remove the sediment and dispose of it in a location where it will not cause impacts to streams or the BMP. Replace any media that was removed in the process. Revegetate disturbed areas immediately.
	Water is standing more than 5 days after a storm event.	Replace the top few inches of filter media and see if this corrects the standing water problem. If so, revegetate immediately. If not, consult an appropriate professional for a more extensive repair.
	Weeds and noxious plants are growing in the main treatment area.	Remove the plants by hand or by wiping them with pesticide (do not spray).
The embankment	Shrubs or trees have started to grow on the embankment.	Remove shrubs or trees immediately.
	An annual inspection by an appropriate professional shows that the embankment needs repair.	Make all needed repairs.
The outlet device	Clogging has occurred.	Clean out the outlet device. Dispose of the sediment off-site.
	The outlet device is damaged	Repair or replace the outlet device.
The receiving water	Erosion or other signs of damage have occurred at the outlet.	Contact the local NC Department of Environment and Natural Resources Regional Office.

STORM-EZ /ersion 1.4