



## **COMPREHENSIVE STORMWATER MANAGEMENT PERMIT**

## HIGH DENSITY DEVELOPMENT

## **SECTION 1 – APPROVAL**

Having reviewed the application and all supporting materials, the City of Wilmington has determined that the application is complete and the proposed development meets the requirements of the City of Wilmington's Comprehensive Stormwater Ordinance.

PERMIT HOLDER:	Phillip R. Barker
PROJECT:	Legacy Pointe
ADDRESS:	2509 Shandy Lane
PERMIT #:	2021011
DATE:	April 30, 2021

Therefore, the above referenced site is hereby approved and subject to all conditions set forth in Section 2 of this approval and all applicable provisions of the City of Wilmington Comprehensive Stormwater Management Ordinance.

This permit shall be effective from the date of issuance until April 30, 2031 and shall be subject to the following specified conditions and limitations:

## Section 2 - CONDITIONS

- 1. This approval is valid only for the stormwater management system as proposed on the approved stormwater management plans dated March 15, 2021.
- 2. The project will be limited to the amount and type of built-upon area indicated in Section IV of the Stormwater Management Application Form submitted as part of the approved stormwater permit application package, and per the approved plans.
- 3. This permit shall become void unless the facilities are constructed in accordance with the approved stormwater management plans, specifications and supporting documentation, including information provided in the application and supplements.
- 4. The runoff from all built-upon area within any permitted drainage area must be directed into the permitted stormwater control system for that drainage area.
- 5. The permittee shall submit a revised stormwater management application packet to the City of Wilmington and shall have received approval prior to construction, for any modification to the approved plans, including, but not limited to, those listed below:
  - a. Any revision to any item shown on the approved plans, including the stormwater management measures, built-upon area, details, etc.
  - b. Redesign or addition to the approved amount of built-upon area or to the drainage area.
  - c. Further subdivision, acquisition, lease or sale of any part of the project area.
  - d. Filling in, altering, or piping of any vegetative conveyance shown on the approved plan.
  - e. Construction of any permitted future areas shown on the approved plans.





- 6. A copy of the approved plans and specifications shall be maintained on file by the Permittee.
- 7. During construction, erosion shall be kept to a minimum and any eroded areas of the system will be repaired immediately.
- 8. If the stormwater system was used as an Erosion Control device, it must be restored to design condition prior to operation as a stormwater treatment device, and prior to issuance of any certificate of occupancy for the project.
- 9. All areas must be maintained in a permanently stabilized condition. If vegetated, permanent seeding requirements must follow the guidelines established in the North Carolina Erosion and Sediment Control Planning and Design Manual unless an alternative is specified and approved by the City of Wilmington.
- 10. All stormwater treatment systems as well as access to nearest right-of-way must be located in recorded easements.
- 11. All applicable operation & maintenance agreements and easements pertaining to each stormwater treatment system shall be referenced on the final plat and recorded with the Register of Deeds upon final plat approval. If no plat is recorded for the site the operation and maintenance agreements and easements shall be recorded with the Register of Deeds so as to appear in the chain of title of all subsequent purchasers under generally accepted searching standards.
- 12. The stormwater management system shall be constructed in its entirety, vegetated and operational for its intended use prior to the construction of any built-upon surface unless prior approval is obtained. City Staff must be notified of any deviation prior to construction of the built-upon surface. Any deviation request shall include justification and must propose an alternative timeline or construction sequence. Notification shall not constitute approval. Any alternative timeline approved by City staff shall become an enforceable component of this permit.
- 13. The permittee shall at all times provide the operation and maintenance necessary to assure the permitted stormwater system functions at optimum efficiency. The approved Operation and Maintenance Agreement must be followed in its entirety and maintenance must occur at the scheduled intervals including, but not limited to:
  - a. Scheduled inspections (interval noted on the agreement).
  - b. Sediment removal.
  - c. Mowing and revegetation of slopes and the vegetated areas.
  - d. Maintenance of landscape plants, including those within the landscape buffer and on the vegetated shelf.
  - e. Immediate repair of eroded areas, especially slopes.
  - f. Debris removal and unclogging of outlet structure, orifice device, flow spreader, catch basins and/or piping.
  - g. Access to the outlet structure must be available at all times.
- 14. Records of inspection, maintenance and repair for the permitted stormwater system must be kept by the permittee for at least 5 years from the date of record and made available upon request to authorized personnel of the City of Wilmington. The records will indicate the date, activity, name of person performing the work and what actions were taken.





- 15. Upon completion of construction, before a Certificate of Occupancy shall be granted, and prior to operation or intended use of this permitted facility, the applicant shall submit to the City of Wilmington as-built plans for all stormwater management facilities. The plans shall show the final design specifications and the field location, type, depth, invert and planted vegetation of all measures, controls and devices, as-installed. A certification shall be submitted, along with all supporting documentation that specifies, under seal that the as-built stormwater measures, controls and devices are in compliance with the approved stormwater management plans. A final inspection by City of Wilmington personnel will be required prior to issuance of a certificate of occupancy or operation of the permitted facility.
- 16. This permit is not transferable except after application and approval by the City of Wilmington. In the event of a change of ownership, name change or change of address the permittee must submit a completed Name/Ownership Change form to the City of Wilmington at least 30 days prior to the change. It shall be signed by all applicable parties and be accompanied by all required supporting documentation. Submittal of a complete application shall not be construed as an approved application. The application will be reviewed on its own merits by the City of Wilmington and may or may not be approved. The project must be in compliance with the terms of this permit in order for the transfer request to be considered. The permittee is responsible for compliance with all permit conditions until such time as the City of Wilmington approves the transfer request. Neither the sale of the project nor the conveyance of common area to a third party should be considered as an approved transfer of the permit.
- 17. Failure to abide by the conditions and limitations contained in this permit may subject the Permittee to enforcement action by the City of Wilmington, in accordance with Sections 18-52 and 18-53 and any other applicable section of the Land Development Code.
- 18. The City of Wilmington may notify the permittee when the permitted site does not meet one or more of the minimum requirements of the permit. Within the time frame specified in the notice, the permittee shall submit a written time schedule to the City of Wilmington for modifying the site to meet minimum requirements. The permittee shall provide copies of revised plans and certification in writing to the City of Wilmington that the changes have been made.
- 19. The issuance of this permit does not preclude the Permittee from complying with any and all statutes, rules, regulations, or ordinances, which may be imposed by other government agencies (local, state, and federal) having jurisdiction.
- 20. In the event that the facilities fail to perform satisfactorily, including the creation of nuisance conditions, the Permittee shall take immediate corrective action, including those as may be required by the City of Wilmington, such as the construction of additional or replacement stormwater management systems.
- 21. The permittee grants City of Wilmington Staff permission to enter the property during normal business hours for the purpose of inspecting all components of the permitted stormwater management facility.





- 22. The permit issued shall continue in force and effect until revoked or terminated by the City of Wilmington. The permit may be modified, revoked and reissued or terminated for cause. The filing of a request for a permit modification, revocation and re-issuance or termination does not stay any permit condition.
- 23. The approved stormwater management plans and all documentation submitted as part of the approved stormwater management permit application package for this project are incorporated by reference and are enforceable parts of the permit.
- 24. The permittee shall submit a renewal request with all required forms and documentation at least 180 days prior to the expiration date of this permit.
- 25. If any one or more of the conditions of this permit is found to be unenforceable or otherwise invalidated, all remaining conditions shall remain in full effect.

Stormwater Management Permit issued this the 30th day of April, 2021.

Richard Christensen

*for* Sterling Cheatham, City Manager City of Wilmington





#### STORMWATER MANAGEMENT PERMIT APPLICATION FORM (Form SWP 2.3)

#### I. GENERAL INFORMATION

 Project Name (subdivision, facility, or establishment name - should be consistent with project name on plans, specifications, letters, operation and maintenance agreements, etc.): Legacy Pointe

2.	Location of Project (street address): 2509 Shandy Lane
	City: <u>Wilmington</u> County: <u>New Hanover</u> Zip: 28409
11.	PERMIT INFORMATION
1.	Specify the type of project (check one): Low Density High Density Offsite Stormwater System Drainage Plan Redevelopment Other If the project drains to an Offsite System, list the Stormwater Permit Number(s): City of Wilmington: State – NCDEQ/DEMLR:
2.	Is the project currently covered (whole or in part) by an existing City or State (NCDEQ/DEMLR) Stormwater Permit? Yes No If yes, list all applicable Stormwater Permit Numbers: City of Wilmington: State – NCDEQ/DEMLR:
3.	Additional Project Permit Requirements (check all applicable):
III.	CONTACT INFORMATION
1.	Print Applicant / Signing Official's name and title (the developer, property owner, lessee, designated government official, individual, etc. who owns the project):
	Applicant / Organization: Phillip R. Barker & D. Christopher Boggs
	Signing Official & Title: Phillip R. Barker





a. Contact information for Applicant / Signing Official:

	Address: 2005 Eastwood Rd., Suite 20	
	City: Wilmington	State: NCZip: _28403
	Phone: 910-231-2020	Email: pbarker@bellsouth.net
	b. Please check the appropriate box. The a	oplicant listed above is:
	The property owner/Purchaser (Skip to item Lessee (Attach a copy of the lease agreement as Developer (Complete items 2 and 2a below.)	
2.	Print Property Owner's name and title (if different	from the applicant).
	Property Owner / Organization:	
	Signing Official & Title:	
	a. Contact information for Property Owner:	
	Street Address:	
	City:	State:Zip:
	Phone:	Email:
3.	(Optional) Other Contact name and title (such as on all correspondence:	a construction supervisor) who would like to be copied
	Other Contact Person / Organization:	
	Signing Official & Title:	

a. Contact information for person listed in item 3 above:

Street Address:		
City:	Zip:	
Phone:	Email:	

4. Agent Authorization: Complete this section if you wish to designate authority to another individual and/or firm (such as a consulting engineer and /or firm) so that they may provide information on your behalf for this project (such as addressing requests for additional information).

Consulting Engineer: Adam Grady, PE

Consulting Firm: Hanover Design Services, PA

a. Contact information for consultant listed above:

Mailing Address: 1123 Floral Parkway

City: Wilmington	_State: NCZip: 28403
Phone: 910-343-8002	Email: agrady@hdsilm.com





## **IV. PROJECT INFORMATION**

- 1. Total Property Area: \_\_\_\_\_\_square feet
- 2. Total Coastal Wetlands Area: \_\_\_\_\_\_square feet
- 3. Total Surface Water Area: \_\_\_\_\_\_square feet
- Total Property Area (1) Total Coastal Wetlands Area (2) Total Surface Water Area (3) = Total Project Area: \_\_\_\_\_\_\_ square feet.
- 5. Existing Impervious Surface within Project Area: \_\_\_\_\_\_square feet
- 6. Existing Impervious Surface to be Removed/Demolished: \_\_\_\_\_\_square feet
- 7. Existing Impervious Surface to Remain: \_\_\_\_\_\_\_square feet
- 8. Total Onsite (within property boundary) Newly Constructed Impervious Surface (in square feet):

Buildings/Lots	
Impervious Pavement	
Pervious Pavement (total area / adjusted area w credit applied)	/
Impervious Sidewalks	
Pervious Sidewalks (total area / adjusted area w credit applied)	/
Other	
Future Development	
Total Onsite Newly Constructed Impervious Surface	

- 9. Total Onsite Impervious Surface
  - (Existing Impervious Surface to remain + Onsite Newly Constructed Impervious Surface) \_\_\_\_\_\_\_\_square feet
- 10. Net Change in Onsite Impervious Surface (+ for net increase, for net decrease)\_\_\_\_\_\_square feet
- 11. Project percent of impervious area: (Total Onsite Impervious Surface / Total Project Area) x100 = \_\_\_\_%
- 12. Total Offsite Newly Constructed Impervious Area (in square feet):

Impervious Pavement	
Pervious Pavement (total area / adjusted area w credit applied)	/
Impervious Sidewalks	
Pervious Sidewalks (total area / adjusted area w credit applied)	/
Other	
Total Offsite Newly Constructed Impervious Surface	



13. Complete the following information for each Stormwater SCM drainage area. Low Density and Drainage Plan projects (with no permeable pavements) may omit this section and skip to Section V.

Basin Information			
Receiving Stream Name			
Receiving Stream Index Number			
Stream Classification			
Total Drainage Area (sf)			
On-Site Drainage Area (sf)			
Off-Site Drainage Area (sf)			
Buildings/Lots (sf)			
Impervious Pavement (sf)			
Pervious Pavement (total / adjusted) (sf)	/	/	/
Impervious Sidewalks (sf)			
Pervious Sidewalks (total / adjusted) (sf)	/	/	/
Other (sf)			
Future Development (sf)			
Existing Impervious to remain (sf)			
Offsite (sf)			
Total Impervious Area (sf)			
Percent Impervious Area (%)			

Basin Information			
Receiving Stream Name			
Receiving Stream Index Number			
Stream Classification			
Total Drainage Area (sf)			
On-Site Drainage Area (sf)			
Off-Site Drainage Area (sf)			
Buildings/Lots (sf)			
Impervious Pavement (sf)			
Pervious Pavement (total / adjusted) (sf)	/	/	/
Impervious Sidewalks (sf)			
Pervious Sidewalks (total / adjusted) (sf)	/	/	/
Other (sf)			
Future Development (sf)			
Existing Impervious to remain (sf)			
Offsite (sf)			
Total Impervious Area (sf)			
Percent Impervious Area (%)			





#### V. SUBMITTAL REQUIREMENTS

Only complete application packages will be accepted and reviewed by the City. A complete package includes all of the items listed below. Copies of forms, deed restrictions, checklists as well as detailed instructions on how to complete this application form may be downloaded from the City of Wilmington Plan Review website below:

https://www.wilmingtonnc.gov/departments/engineering/plan-review/stormwater-permits

The complete application package should be submitted to the following address:

City of Wilmington – Engineering Plan Review Section 212 Operations Center Dr. Wilmington, NC 28412

Please indicate that the following required information have been provided by initialing in the space provided for each item.

		Initials
1.	One completed Stormwater Management Permit Application Form.	AG
2.	One completed Supplement Form for each SCM proposed (signed, sealed and dated).	AG
3.	One completed Operation & Maintenance agreement for each type of SCM.	AG
4.	Proposed Deed Restrictions and Restrictive Covenants (for all subdivisions)	AG
5.	Appropriate stormwater permit review fee.	AG
6.	Minimum requirements identified on the Engineering Plan Review Checklist have been addressed.	AG
7.	One set of calculations (sealed. signed and dated).	AG
8.	A detailed narrative (one to two pages) describing the stormwater treatment/management system for the project.	AG
9.	A USGS map identifying the site location. If the receiving stream is reported as class SA or the receiving stream drains to class SA waters within $\frac{1}{2}$ mile of the site boundary, include the $\frac{1}{2}$ mile radius on the map.	AG
10.	A copy of the soils report, if applicable. Must meet NCDEQ SCM Manual and MDC requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations.	AG
11.	One full set of plans folded to 8.5" x 14".	AG
12.	A map delineating and labeling the drainage area for each SCM proposed.	AG
13.	A map delineating and labeling the drainage area for each inlet and conveyance proposed.	AG
14.	A digital copy of the entire submittal package (can be submitted via flash drive, CD, email, dropbox or other file sharing system).	AG



#### VI. PROPERTY OWNER AUTHORIZATION (If Section III(2) has been filled out, complete this section)

I, \_\_\_\_\_\_, certify that I own the property identified in this permit application, and thus give permission to \_\_\_\_\_\_\_ with \_\_\_\_\_\_ to develop the project as currently proposed. A copy of the lease agreement or pending property sales contract has been provided with the submittal, which indicates the party responsible for the operation and maintenance of the stormwater system.

As the legal property owner I acknowledge, understand, and agree by my signature below, that if my designated agent \_\_\_\_\_\_\_dissolves their company and/or cancels or defaults on their lease agreement, or pending sale, responsibility for compliance with the City of Wilmington Stormwater Permit reverts back to me, the property owner. As the property owner, it is my responsibility to notify the City of Wilmington immediately and submit a completed Name/Ownership Change Form within 30 days; otherwise I will be operating a stormwater treatment facility without a valid permit. I understand that the operation of a stormwater treatment facility without a valid permit of the City of Wilmington Municipal Code of Ordinances and may result in appropriate enforcement including the assessment of civil penalties.

Signature:		
SEAL	I,, a State of, County of hereby certify that personally appeared before me this day of and acknowledge the due execution of the application permit. Witness my hand and official seal,  My commission expires:	, do ,,

## VII. APPLICANT'S CERTIFICATION

I, <u>Phillip R. Barker</u> certify that the information included on this permit application form is, to the best of my knowledge, correct and that the project will be constructed in conformance with the approved plans, that the required deed restrictions and protective covenants will be recorded, and that the proposed project complies with the requirements of the applicable rules under the City's Comprehensive Stormwater Ordinance.

Signature: hillips R. Bonker Date: (2/30/20	
	_
SEAL I, Budget V. Onhuse, a Notary Public for the	r the
State of <u>NC</u> , County of <u>New Hano ver</u> , do hereby certify that <u>Phillip R. Barker</u>	
personally appeared before me this day of <u>30<sup>th</sup> Dec</u> , <u>30<sup>th</sup></u>	020,
and acknowledge the due execution of the application for a stormwater	iter
permit Witness my hand and official seal,	
Bridget V Sishing	
My  commission expires:  4-12-21	

#### SUPPLEMENT-EZ COVER PAGE

FORMS LOADED

PRO.	PROJECT INFORMATION			
1	Project Name	Legacy Pointe		
2	Project Area (ac)	5.78		
3	Coastal Wetland Area (ac)	0		
4	Surface Water Area (ac)	0		
5	Is this project High or Low Density?	High		
6	Does this project use an off-site SCM?	No		

COMPLIANCE WITH 02H .1003(4)				
7	Width of vegetated setbacks provided (feet)	na		
8	Will the vegetated setback remain vegetated?	N/A		
9	If BUA is proposed in the setback, does it meet NCAC 02H.1003(4)(c-d)?	N/A		
10	Is streambank stabilization proposed on this project?	No		

11	Infiltration System	5
12	Bioretention Cell	
13	Wet Pond	
14	Stormwater Wetland	
15	Permeable Pavement	1
16	Sand Filter	
17	Rainwater Harvesting (RWH)	
18	Green Roof	
19	Level Spreader-Filter Strip (LS-FS)	
20	Disconnected Impervious Surface (DIS)	
21	Treatment Swale	
22	Dry Pond	
23	StormFilter	
24	Silva Cell	
25	Bayfilter	
26	Filterra	

#### FORMS LOADED

27	Name and Title:	Adam Grady
28	Organization:	Hanover Design Services, PA
29	Street address:	1123 Floral Parkway
30	City, State, Zip:	Wilmington, NC 28403
31	Phone number(s):	910-343-8002
32	Email:	agrady@hdsilm.com

#### Certification Statement:

I certify, under penalty of law that this Supplement-EZ form and all supporting information were prepared under my direction or supervision; that the information provided in the form is, to the best of my knowledge and belief, true, accurate, and complete, and that the engineering plans, specifications, operation and maintenance agreements and other supporting information are consistent with the information provided here.

<u>Designer</u>



Signature of Designer

3/2/21 Date

## UKAINAGE AKEAS

1	Is this a high density project?	Yes
2	If so, number of drainage areas/SCMs	6
3	Does this project have low density areas?	No
4	If so, number of low density drainage areas	0
5	Is all/part of this project subject to previous rule versions?	No

FORMS LOADED

DRAINAG	E AREA INFORMATION	Entire Site	1	2	3	4
			INFILTRATION	INFILTRATION	INFILTRATION	INFILTRATION
	e of SCM		BASIN	BASIN	BASIN	BASIN
5 Tota	al drainage area (sq ft)	210066	20478	40000	20000	40000
6 Ons	site drainage area (sq ft)	210066	20478	40000	20000	40000
7 Offs	site drainage area (sq ft)					
8 Tota	al BUA in project (sq ft)	56000 sf	7000 sf	14000 sf	7000 sf	14000 sf
9 (sq	v BUA on subdivided lots (subject to permitting) ft)	56000 sf	7000 sf	14000 sf	7000 sf	14000 sf
	v BUA not on subdivided lots (subject to mitting) (sf)					
11 Offs	site BUA (sq ft)	343 sf				
	akdown of new BUA not on subdivided lots:					
- F	Parking (sq ft)	sf				
	Sidewalk (sq ft)	sf				
- F	Roof (sq ft)	sf				
- F	Roadway (sq ft)	sf		and the second second second		
- F	Future (sq ft)	56000 sf	7000 sf	14000 sf	7000 sf	14000 sf
	Other, please specify in the comment box w (sq ft)					
New	<ul> <li>infiltrating permeable pavement on divided lots (sq ft)</li> </ul>	3423 sf				
	infiltrating permeable pavement not on divided lots (sq ft)					
Exis	ting BUA that will remain (not subject to nitting) (sq ft)					
	ting BUA that is already permitted (sq ft)	Frank Installer States		and the second s		1/2010-1022-1-
	ting BUA that will be removed (sq ft)	7545 sf	The second state of the se			2544 sf
	cent BUA	22%	34%	35%	35%	35%
19 Desi	ign storm (inches)	1-Year 24hr storm	1-Year 24hr storm	1-Year 24hr storm	1-Year 24hr storm	1-Year 24hr storm
	gn volume of SCM (cu ft)	17938 cf	2290 cf	4575 cf	2414 cf	4017 cf
21 Calc	ulation method for design volume	24 hr storm	24 hr storm	24 hr storm	24 hr storm	24 hr storm
CONTRACTOR OF THE OWNER		FierPost amerence	Pre/Post difference	Pre/Post amerence	Pre/Post difference	Pre/Post difference

ADDITIONAL INFORMATION Please use this space to provide any additional information about the 22 drainage area(s): Pervious Concrete is located in an access easment.

#### URAINAGE AREAS

1	Is this a high density project?	Yes
2	If so, number of drainage areas/SCMs	6
3	Does this project have low density areas?	No
4	If so, number of low density drainage areas	0
	Is all/part of this project subject to previous rule	
5	versions?	No

FORMS LOADED

DRA	INAGE AREA INFORMATION	Entire Site	5	6
			INFILTRATION	Permeable
4	Type of SCM		BASIN	Pavement
5	Total drainage area (sq ft)	210066	89588	3838
6	Onsite drainage area (sq ft)	210066	89588	3838
7	Offsite drainage area (sq ft)			
8	Total BUA in project (sq ft)	56000 sf	14000 sf	
9	New BUA on subdivided lots (subject to permitting) (sq ft)	56000 sf	14000 sf	
10	New BUA not on subdivided lots (subject to permitting) (sf)			
11	Offsite BUA (sq ft)	343 sf		
12	Breakdown of new BUA not on subdivided lots:			
	- Parking (sq ft)	sf		
	- Sidewalk (sq ft)	sf		and the second second
	- Roof (sq ft)	sf	Physical Street and	
	- Roadway (sq ft)	sf		and a second second
	- Future (sq ft)	56000 sf	14000 sf	
	- Other, please specify in the comment box below (sq ft)			
	New infiltrating permeable pavement on			
13	subdivided lots (sq ft)	3423 sf		3838 sf
14	New infiltrating permeable pavement not on subdivided lots (sq ft)			
15	Existing BUA that will remain (not subject to permitting) (sq ft)			
16	Existing BUA that is already permitted (sq ft)			
17	Existing BUA that will be removed (sq ft)	7545 sf	2931 sf	2070 sf
18	Percent BUA	22%	16%	0%
19	Design storm (inches)	1-Year 24hr storm	1-Year 24hr storm	1.5 in
20	Design volume of SCM (cu ft)	17938 cf	4162 cf	480 cf
21	Calculation method for design volume	24 hr storm Pre/Post difference	24 hr storm Pre/Post difference	1.5"

ADDITIONAL INFORMATION Please use this space to provide any additional information about the drainage area(s): Pervious Concrete is located in an access easment.

#### INFILIRATION STOLEN

Drainage area number	1	2	3	4
Minimum required treatment volume (cu ft)	1975 cf	3950 cf	1975 cf	3950 cf
RAL MDC FROM 02H .1050				
Is the SCM sized to treat the SW from all surfaces at build-out?	Yes	Yes	Yes	Yes
	Yes	Yes	the second s	the second s
Is the SCM located away from contaminated soils?	Tes	Tes	Yes	Yes
What are the side slopes of the SCM (H:V or enter "Vertical" for	0.4			
trenches)?	3:1	3:1	3:1	3:1
Does the SCM have retaining walls, gabion walls or other engineered				
side slopes?	No	No	No	No
Are the inlets, outlets, and receiving stream protected from erosion	and the second	104		
(10-year storm)?	Yes	Yes	Yes	Yes
Is there an overflow or bypass for inflow volume in excess of the				1.2. 1. 14.4
design volume?	Yes	Yes	Yes	Yes
What is the method for dewatering the SCM for maintenance?	Pump (preferred)	Pump (preferred)	Pump (preferred)	Pump (preferred
If applicable, will the SCM be cleaned out after construction?	Yes	Yes	Yes	Yes
Does the maintenance access comply with General MDC (8)?	Yes	Yes	Yes	Yes
Does the drainage easement comply with General MDC (9)?	Yes	Yes	Yes	Yes
	103	105	Tes	165
If the SCM is on a single family lot, does (will?) the plat comply with	Vee	Vee	New	Maria
General MDC (10)?	Yes	Yes	Yes	Yes
Is there an O&M Agreement that complies with General MDC (11)?				
	Yes	Yes	Yes	Yes
Is there an O&M Plan that complies with General MDC (12)?	Yes	Yes	Yes	Yes
Does the SCM follow the device specific MDC?	Yes	Yes	Yes	Yes
Was the SCM designed by an NC licensed professional?	Yes	Yes	Yes	Yes
TRATION SYSTEM MDC FROM 02H .1051				COLUMN TWO IS NOT
Proposed slope of the subgrade surface (%)	0.10/	0.49/	0.40/	0.40/
	0-1%	0-1%	0-1%	0-1%
Are terraces or baffles provided?	No	No	No	No
Type of pretreatment:	Other	Other	Other	Other
Data				
Was the soil investigated in the footprint and at the elevation of the				
infiltration system?	No	No	No	Yes
SHWT elevation (fmsl)	6.63	6.63	7.16	6.09
Depth to SHWT per soils report (in)	30.00	30.00	62.04	24.00
Ground elevation at boring in soils report (fmsl)	9.13	9.13	12.33	8.09
	9.10	9.15	12.33	0.09
Is a detailed hydrogeologic study attached if the separation is	21/4	A11A		
between 1 and 2 feet?	N/A	N/A	N/A	N/A
Soil infiltration rate (in/hr)	8.94	8.94	15.17	6.35
Factor of safety (FS) (2 is recommended):	2.00	2.00	2.00	2.00
ations				
Bottom elevation (fmsl)	8.7 ft	9.0 ft	10.0 ft	8.1 ft
Storage elevation (fmsl)	10.5 ft	10.5 ft	12.5 ft	9.5 ft
Bypass elevation (fmsl)	10.5 ft	10.5 ft	12.5 ft	9.5 ft
Basins Only	TOTOTIC	10.0 1	12.0 1	0.0 11
	074.0	055.0		4 4 10 10
Bottom surface area (ft <sup>2</sup> )	671 ft	855 ft	238 ft	1476 ft
Storage elevation surface area (ft <sup>2</sup> )	2094. ft	5061. ft	2050. ft	4472. ft
Frenches Only				
Length (ft)				
Width (ft)				Part of the second second
Perforated pipe diameter, if applicable (inches)		TRANSPORT OF TAXABLE		
Number of laterals				
Total length of perforated piping				A ALAN ALAN AND
Stone type, if applicable				and states and
Stone porosity (%)				
Is stone free of fines?			THE REPORT OF THE PARTY OF	
Is the stone wrapped in geotextile fabric?				
Has at least one inspection port been provided?			Constant of the local data	and the second se
mes/Drawdown	and the second se			
	2200 cf	AETE of	0444 ct	4047 -4
Design volume of SCM (cu ft)	2290 cf	4575 cf	2414 cf	4017 cf
Time to draw down (hours)	9 hrs	11 hrs	24 hrs	6 hrs
TIONAL INFORMATION				
Please use this space to provide any additional information about the				
infiltration system(s):				

#### INFILIRATION STOLEN

Minimum required treatment volume (cu ft) MDC FROM 02H .1050 a the SCM sized to treat the SW from all surfaces at build-out? a the SCM located away from contaminated soils? Vhat are the side slopes of the SCM (H:V or enter "Vertical" for enches)? to be the SCM have retaining walls, gabion walls or other engineered de slopes? re the inlets, outlets, and receiving stream protected from erosion 10-year storm)? a there an overflow or bypass for inflow volume in excess of the esign volume? Vhat is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? Vas the SCM designed by an NC licensed professional? TON SYSTEM MDC FROM 02H .1051 roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: Vas the soil investigated in the footprint and at the elevation of the filtration system?	3950 cf Yes Yes 3:1 No Yes Yes Yes Yes Yes Yes Yes Yes Yes Yes
a the SCM sized to treat the SW from all surfaces at build-out? a the SCM located away from contaminated soils? What are the side slopes of the SCM (H:V or enter "Vertical" for enches)? toes the SCM have retaining walls, gabion walls or other engineered ide slopes? re the inlets, outlets, and receiving stream protected from erosion 10-year storm)? a there an overflow or bypass for inflow volume in excess of the esign volume? What is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? //as the SCM designed by an NC licensed professional? <b>TON SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: //as the soil investigated in the footprint and at the elevation of the	Yes 3:1 No Yes Yes Yes Yes Yes Yes Yes Yes
a the SCM located away from contaminated soils? Vhat are the side slopes of the SCM (H:V or enter "Vertical" for enches)? toes the SCM have retaining walls, gabion walls or other engineered ide slopes? re the inlets, outlets, and receiving stream protected from erosion 10-year storm)? a there an overflow or bypass for inflow volume in excess of the esign volume? /hat is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>TON SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes 3:1 No Yes Yes Yes Yes Yes Yes Yes Yes
Vhat are the side slopes of the SCM (H:V or enter "Vertical" for enches)? toes the SCM have retaining walls, gabion walls or other engineered ide slopes? the inlets, outlets, and receiving stream protected from erosion 10-year storm)? there an overflow or bypass for inflow volume in excess of the esign volume? //hat is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? //as the SCM designed by an NC licensed professional? <b>TON SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: //as the soil investigated in the footprint and at the elevation of the	3:1 No Yes Yes Pump (preferred) Yes Yes Yes Yes Yes Yes Yes Yes Yes Yes
enches)? tooes the SCM have retaining walls, gabion walls or other engineered ide slopes? re the inlets, outlets, and receiving stream protected from erosion 10-year storm)? a there an overflow or bypass for inflow volume in excess of the esign volume? /hat is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>TON SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	No Yes Yes Pump (preferred) Yes Yes Yes Yes Yes Yes Yes Yes Yes Yes
oes the SCM have retaining walls, gabion walls or other engineered ide slopes? re the inlets, outlets, and receiving stream protected from erosion 10-year storm)? a there an overflow or bypass for inflow volume in excess of the esign volume? /hat is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>TON SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	No Yes Yes Pump (preferred) Yes Yes Yes Yes Yes Yes Yes Yes Yes Yes
ide slopes? re the inlets, outlets, and receiving stream protected from erosion 10-year storm)? a there an overflow or bypass for inflow volume in excess of the esign volume? /hat is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>TON SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes Yes Pump (preferred) Yes Yes Yes Yes Yes Yes Yes Yes Yes Yes
ide slopes? re the inlets, outlets, and receiving stream protected from erosion 10-year storm)? a there an overflow or bypass for inflow volume in excess of the esign volume? /hat is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>TON SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes Yes Pump (preferred) Yes Yes Yes Yes Yes Yes Yes Yes Yes Yes
10-year storm)? a there an overflow or bypass for inflow volume in excess of the esign volume? /hat is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? //as the SCM designed by an NC licensed professional? TON SYSTEM MDC FROM 02H .1051 roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: //as the soil investigated in the footprint and at the elevation of the	Yes Pump (preferred Yes Yes Yes Yes Yes Yes Yes Yes Yes No
10-year storm)? a there an overflow or bypass for inflow volume in excess of the esign volume? /hat is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? //as the SCM designed by an NC licensed professional? TON SYSTEM MDC FROM 02H .1051 roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: //as the soil investigated in the footprint and at the elevation of the	Yes Pump (preferred Yes Yes Yes Yes Yes Yes Yes Yes Yes No
there an overflow or bypass for inflow volume in excess of the esign volume? /hat is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>TON SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes Pump (preferred Yes Yes Yes Yes Yes Yes Yes Yes Yes No
esign volume? /hat is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? TON SYSTEM MDC FROM 02H .1051 roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Pump (preferred Yes Yes Yes Yes Yes Yes Yes Yes O-1% No
What is the method for dewatering the SCM for maintenance? applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>TON SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment:	Pump (preferred Yes Yes Yes Yes Yes Yes Yes Yes O-1% No
applicable, will the SCM be cleaned out after construction? oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? TON SYSTEM MDC FROM 02H .1051 roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment:	Yes Yes Yes Yes Yes Yes Yes Yes O-1% No
oes the maintenance access comply with General MDC (8)? oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? TON SYSTEM MDC FROM 02H .1051 roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment:	Yes Yes Yes Yes Yes Yes Yes O-1% No
oes the drainage easement comply with General MDC (9)? the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? TON SYSTEM MDC FROM 02H .1051 roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment:	Yes Yes Yes Yes Yes Yes O-1% No
the SCM is on a single family lot, does (will?) the plat comply with eneral MDC (10)? there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? TON SYSTEM MDC FROM 02H .1051 roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes Yes Yes Yes Yes O-1% No
there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>TON SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes Yes Yes Yes O-1% No
there an O&M Agreement that complies with General MDC (11)? there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>TON SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes Yes Yes Yes O-1% No
there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>ION SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes Yes Yes O-1% No
there an O&M Plan that complies with General MDC (12)? oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>ION SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes Yes Yes O-1% No
oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>ION SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes Yes Yes O-1% No
oes the SCM follow the device specific MDC? /as the SCM designed by an NC licensed professional? <b>ION SYSTEM MDC FROM 02H .1051</b> roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes Yes 0-1% No
/as the SCM designed by an NC licensed professional? TON SYSTEM MDC FROM 02H .1051 roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	Yes 0-1% No
TON SYSTEM MDC FROM 02H .1051 roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	0-1% No
roposed slope of the subgrade surface (%) re terraces or baffles provided? ype of pretreatment: //as the soil investigated in the footprint and at the elevation of the	No
re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	No
re terraces or baffles provided? ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	the second s
ype of pretreatment: /as the soil investigated in the footprint and at the elevation of the	the second s
as the soil investigated in the footprint and at the elevation of the	Other
	and a second second
tilitration system?	
	No
HWT elevation (fmsl)	4.86
epth to SHWT per soils report (in)	54.00
round elevation at boring in soils report (fmsl)	9.36
a detailed hydrogeologic study attached if the separation is	
etween 1 and 2 feet?	N/A
bil infiltration rate (in/hr)	13.89
	the second s
actor of safety (FS) (2 is recommended):	2.00
ottom elevation (fmsl)	8.0 ft
orage elevation (fmsl)	9.5 ft
(pass elevation (fmsl)	9.5 ft
ns Only	100 100 mm 200 mm 200 mm
	1240 8
	1240 ft
	4450. ft
ength (ft)	
idth (ft)	
	the second second
stone free of fines?	and some provide the second
the stone wrapped in geotextile fabric?	
	4160 -
	4162 cf
And the second	6 hrs
NAL INFORMATION	
ease use this space to provide any additional information about the	
	s         Attom elevation (fmsl)         borage elevation (fmsl)         pass elevation fifth         pass elevation surface area (ft <sup>2</sup> )         pass elevation for perforated piping         pone prosity (%)         stone wrapped in geotextile fabric?

# PERMEABLE PAVEMENT

PE		
1	Drainage area number	6
2	Minimum required treatment volume (cu ft)	480 cf
3	Area of permeable pavement to be installed (square feet)	3838 sf
	Area of screened roof runoff that is directed to pavement (square feet)	sf
5	Area of additional built-upon area runoff that is directed to pavement (square feet)	sf
6	Area of incidental, unavoidable runoff from adjacent stable pervious areas (square feet)	sf
<b>GENER</b>	AL MDC FROM 02H .1050	
7	Is the SCM sized to treat the SW from all surfaces at build-out?	No
	Is the SCM located away from contaminated soils?	Yes
	What are the side slopes of the SCM (H:V)?	N/A
10	Are the inlets, outlets, and receiving stream protected from erosion (10-year storm)?	No
11	Is there an overflow or bypass for inflow volume in excess of the design volume?	Yes
12	What is the method for dewatering the SCM for maintenance?	Other
	If applicable, will the SCM be cleaned out after construction?	Yes
	Does the maintenance access comply with General MDC (8)?	Yes
15	Does the drainage easement comply with General MDC (9)?	N/A
16	If the SCM is on a single family lot, does (will?) the plat comply with General MDC (10)?	Yes
	Is there an O&M Agreement that complies with General MDC (11)?	No
	Is there an O&M Plan that complies with General MDC (12)?	No
	Does the SCM follow the device specific MDC?	Yes
	Was the SCM designed by an NC licensed professional?	Yes
	ABLE PAVEMENT MDC FROM 02H .1055	Infilmetics
	Is this a detention or infiltration permeable pavement system?	Infiltration
	Design volume of SCM (cu ft)	Infiltration
	Proposed slope of the subgrade surface (%)	
	Are terraces or baffles provided?	No
	SHWT elevation (fmsl)	5.82
26	Storage elevation of the design rainfall depth (fmsl)	
27	Will toxic pollutants be stored or handled on or near the permeable pavement?	No
28	Does the proposed pavement surface comply with .1055(6)?	Yes
29	Will runoff from pervious surfaces be directed away from the pavement?	Yes
30	Maximum adjacent area directed to a single point onto the permeable pavement (sq ft)	sf
31	Has at least one observation well per terrace been provided at the low point(s)?	Yes
	Have edge restraints been provided?	No
33	Will the subgrade be graded when dry?	Yes
34	Will the permeable pavement be protected from sediment during construction?	Yes
35	Will an in-situ permeability test be conducted after site stabilization?	Yes
For Inf	iltrating Pavement Systems	
36	Was the soil investigated in the footprint and at the elevation of the subgrade?	Yes
37	Soil infiltration rate (in/hr)	7.25 in/hr
38	Is a detailed hydrogeologic study attached if the separation is between 1 and 2 feet?	No
39	Is additional media being added to the soil profile?	No
	Proposed slope of the subgrade surface (%)	<2%
	Top of the subgrade (bottom of the aggregate) (fmsl)	10.6 TO 14
	Drawdown time (hours)	1 hrs
For De	tention Pavement Systems	
43	Drawdown time (hours)	
Aggree	gate	
44	Aggregate depth (in)	6 in
	Aggregate porosity (%)	30
	Size of aggregate to be used in the subbase	3/4''
	Will the aggregate be washed?	Yes
	ONAL INFORMATION	
48	Please use this space to provide any additional information about the permeable pavement system(s):	
	test were taken in the direct vicinity of the system and both had	
similar found.	attributes. 37. 7.25 in/hr is shown here which is half the lowest rate	

## Infiltration Basin Operation and Maintenance Agreement

I will keep a maintenance record on this SCM. This maintenance record will be kept in a log in a known set location. Any deficient SCM elements noted in the inspection will be corrected, repaired or replaced **immediately**. These deficiencies can affect the integrity of structures, safety of the public, and the pollutant removal efficiency of the SCM.

Important maintenance procedures:

- The drainage area will be carefully managed to reduce the sediment load to the infiltration basin.
- Immediately after the infiltration basin is established, the vegetation will be watered twice weekly if needed until the plants become established (commonly six weeks).
- No portion of the infiltration basin will be fertilized after the initial fertilization that is required to establish the vegetation.
- The vegetation in and around the basin will be maintained at a height of approximately six inches.

After the infiltration basin is established, it will be inspected **once a quarter and within 24 hours after every storm event greater than 1.5 inches**. Records of operation and maintenance will be kept in a known set location and will be available upon request.

Inspection activities shall be performed as follows. Any problems that are found shall be repaired immediately.

SCM element:	Potential problem:	How to remediate the problem:
The entire SCM	Trash/debris is present.	Remove the trash/debris.
The perimeter of the infiltration basin	Areas of bare soil and/or erosive gullies have formed.	Regrade the soil if necessary, to remove the gully, and then plant a ground cover and water until it is established. Provide lime and a one-time fertilizer application.
The inlet device: pipe or swale	The pipe is clogged (if applicable). The pipe is cracked or otherwise damaged (if applicable).	Unclog the pipe. Dispose of the sediment off-site. Replace the pipe.
	Erosion is occurring in the swale (if applicable).	Regrade the swale if necessary, to smooth it over and provide erosion control devices such as reinforced turf matting or riprap to avoid future problems with erosion.

SCM element:	Potential problem:	How to remediate the problem:
The forebay	Sediment has accumulated	Search for the source of the
	and reduced the depth to 75%	sediment and remedy the problem if
	of the original design depth.	possible. Remove the sediment and
		dispose of it in a location where it
		will not cause impacts to streams or
		the SCM. Replace any media that
		was removed in the process.
		Revegetate disturbed areas
		immediately.
	Erosion has occurred or	Provide additional erosion
	riprap is displaced.	protection such as reinforced turf
		matting or riprap if needed to
		prevent future erosion problems.
	Weeds are present.	Remove the weeds, preferably by
	-	hand. If pesticides are used, wipe
		them on the plants rather than
		spraying.
The main treatment area	A visible layer of sediment	Search for the source of the
	has accumulated.	sediment and remedy the problem if
		possible. Remove the sediment and
		dispose of it in a location where it
		will not cause impacts to streams or
		the SCM. Replace any media that
		was removed in the process.
		Revegetate disturbed areas
		immediately.
	Water is standing more than	Replace the top few inches of filter
	5 days after a storm event.	media and see if this corrects the
		standing water problem. If so,
		revegetate immediately. If not,
		consult an appropriate professional
		for a more extensive repair.
	Weeds and noxious plants are	Remove the plants by hand or by
	growing in the main	wiping them with pesticide (do not
	treatment area.	spray).
The embankment	Shrubs or trees have started	Remove shrubs or trees
	to grow on the embankment.	immediately.
	An annual inspection by an	Make all needed repairs.
	appropriate professional	
	shows that the embankment	
	needs repair.	
The outlet device	Clogging has occurred.	Clean out the outlet device. Dispose
		of the sediment off-site.
	The outlet device is damaged	Repair or replace the outlet device.
The receiving water	Erosion or other signs of	Contact the local NC Department of
	damage have occurred at the	Environment and Natural Resources
	outlet.	Regional Office.


I acknowledge and agree by my signature below that I am responsible for the performance of the maintenance procedures listed above. I agree to notify the City of Wilmington of any problems with the system or prior to any changes to the system or responsible party.

Project name: Legacy Pointe	
SCM drainage basin number: 1	
Print name: Phillip R. Barker	
Title: Owner	
Address: 2005 Eastwood Rd Suite 201; Wilmington, NC 28403	
Phone: 910-231-2020	
$\mathcal{D}(\mathcal{A}) = \langle \mathcal{D} \rangle$	
Signature: Thillip K. Barbon Date: 12/30/20	

Note: The legally responsible party should not be a homeowners' association unless more than 50% of the lots have been sold and a resident of the subdivision has been named the president.

a Notary Public for the State of , do hereby certify that County of New anover personally appeared before me this \_\_\_\_ 2030, and acknowledge the due execution of the day of

forgoing infiltration basin maintenance requirements. Witness my hand and official seal,



SEAL

12-21 My commission expires

Project name: Legacy Pointe
SCM drainage basin number: 2
Print name: Phillip R. Barker
Title: Owner
Address: 2005 Eastwood Rd Suite 201; Wilmington, NC 28403
Phone: 910-231-2020
Signature: Thelip R. Barper
Date: 2 30 20
Note: The legally responsible party should not be a homeowners' association unless more than 50% of the lots have been sold and a resident of the subdivision has been named the president.
I, Budger V. Oghese, a Notary Public for the State of NC, County of <u>New Hanour</u> , do hereby certify that <u>Phillip R. Barker</u> personally appeared before me this
day of $30^{\frac{11}{10}}$ Dec , $2020$ , and acknowledge the due execution of the
forgoing infiltration basin maintenance requirements. Witness my hand and official seal,
NOTARL NUTARL NOTARL NOTARL NOTARL NOTARL NOTARL NOTARL NOTARL NOTARL NOTARL NOTARL NOTARL NOTARL NOTARL NOTARL
SEAL

-12-21 My commission expires\_


Project name: Legacy Pointe		
SCM drainage basin number: 3	1 2	
<u> </u>		

Print name: Phillip R. Barker
Title: Owner
Address: 2005 Eastwood Rd Suite 201; Wilmington, NC 28403
Phone: 910-231-2020
Signature: Phillips R. Barpen
Date: 12/30/20

Note: The legally responsible party should not be a homeowners' association unless more than 50% of the lots have been sold and a resident of the subdivision has been named the president.

\_\_\_\_, a Notary Public for the State of County of <u>New Hanover</u>, do hereby certify that Barker \_\_\_\_\_ personally appeared before me this \_\_\_\_\_ 2020 and acknowledge the due execution of the day of

forgoing infiltration basin maintenance requirements. Witness my hand and official seal,



SEAL


21 My commission expires

Project name: Legacy Pointe	
SCM drainage basin number: 4	
Print name: Phillip R. Barker	2
Title: Owner	
Address: 2005 Eastwood Rd Suite 201; Wilmington, NC 28403	
Phone: 910-231-2020	
Signature: Thilps K. Barber Date: 12-30/20	

Note: The legally responsible party should not be a homeowners' association unless more than 50% of the lots have been sold and a resident of the subdivision has been named the president.

\_, a Notary Public for the State of County of New Nanover , do hereby certify that personally appeared before me this \_\_\_\_\_ 2020, and acknowledge the due execution of the day of

forgoing infiltration basin maintenance requirements. Witness my hand and official seal,



SEAL

12-21 My commission expires

Project name: Legacy Pointe
SCM drainage basin number: 5
Print name: Phillip R. Barker
Title: Owner
Address: 2005 Eastwood Rd Suite 201; Wilmington, NC 28403
Phone: 910-231-2020
Signature: Phillips R. Barber
Date: 12/30/20
Note: The legally responsible party should not be a homeowners' association unless more than 50% of the lots have been sold and a resident of the subdivision has been named the president.
I, Budget V. Oethese, a Notary Public for the State of
NC, County of New Hanover, do hereby certify that
Phillip R. Barky personally appeared before me this
day of <u><math>30^{\pm}</math> Dec.</u> , <u><math>2020</math></u> , and acknowledge the due execution of the
forgoing infiltration basin maintenance requirements. Witness my hand and official seal,
HUNDGET V DELA



SEAL

12-21 My commission expires

# Permeable Pavement Operation and Maintenance Agreement

I will keep a maintenance record on this SCM. This maintenance record will be kept in a log in a known set location. Any deficient SCM elements noted in the inspection will be corrected, repaired or replaced **immediately**. These deficiencies can affect the integrity of structures, safety of the public, and the pollutant removal efficiency of the SCM(s).

Important maintenance procedures:

At all times, the permeable pavement shall be kept free of:

- Debris and particulate matter through frequent blowing that removes such debris, particularly during the fall and spring.
- Piles of soil, sand, mulch, building materials or other materials that could deposit particulates on the permeable pavement.
- Piles of snow and ice.
- Chemicals of all kinds, including deicers.

The permeable pavement will be inspected **once a quarter**. Records of operation and maintenance will be kept in a known set location and will be available upon request.

Inspection activities shall be performed as follows. Any problems that are found shall be repaired immediately.

SCM element:	Potential problem:	How to remediate the problem:
The entire SCM	Trash/debris is present.	Remove the trash/debris.
The perimeter of the permeable pavement	Areas of bare soil and/or erosive gullies have formed.	Regrade the soil if necessary, to remove the gully, then plant ground cover and water until established.
	A vegetated area drains toward the pavement.	Regrade the area so that it drains away from the pavement, then plant ground cover and water until established.
The inlet device	The pipe is clogged.	Unclog the pipe. Dispose of the sediment off-site.
	The pipe is cracked or otherwise damaged.	Replace the pipe.
	Erosion is occurring in the swale.	Regrade the swale if necessary, to smooth it over and provide erosion control devices such as reinforced turf matting or riprap to avoid future problems with erosion.
	Stone verge is clogged or covered in sediment (if applicable).	Remove sediment and replace with clean stone.

SCM element:	Potential problem:	How to remediate the problem:
The surface of the permeable pavement	Trash/debris present.	Remove the trash/debris.
	Weeds.	Do not pull the weeds (may pull out media as well). Spray them with a systemic herbicide such as glyphosate and then return within the week to remove them by hand. (Another option is to pour boiling water on them or steam them.)
	Sediment.	Vacuum sweep the pavement.
	Rutting, cracking or slumping or damaged structure.	Consult an appropriate professional.
Observation well	Water present more than five	Clean out clogged underdrain
	days after a storm event.	pipes. Consult an appropriate
		professional for clogged soil subgrade.
Educational sign	Missing or is damaged.	Replace the sign.
The outlet device	Clogging has occurred.	Clean out the outlet device. Dispose of the sediment off-site.
	The outlet device is damaged.	Repair or replace the outlet device.
The receiving water	Erosion or other signs of	Contact the NC Department of
-	damage have occurred at the outlet.	Environment and Natural Resources Regional Office.

I acknowledge and agree by my signature below that I am responsible for the performance of the maintenance procedures listed above. I agree to notify the City of Wilmington of any problems with the system or prior to any changes to the system or responsible party.

Project name: Legacy Pointe
SCM drainage basin number: <u>6</u>
Print name: Phillip R. Barker
Title: Owner
Address: 2005 Eastwood Rd Suite 201; Wilmington, NC 28403
Phone: 910-231-2020
Signature: P. hellys R. Barton
Date: 2/19/2/
Note: The legally responsible party should not be a homeowners' association unless more than 50% of the lots have been sold and a resident of the subdivision has been named the president.
I, Bridget V, Oghuse, a Notary Public for the State of
North Cardinic. County of New Vanover, do hereby certify that
Phillip R. Barker personally appeared before me this
day of February 19, 2021, and acknowledge the due execution of the
forgoing filter strip, riparian buffer, and/or level spreader maintenance requirements.
Witness my hand and official seal,
NOTARL NOTARL PUBLIC PUBLIC PUBLIC CDIAL
SEAL
My commission expires $4-12-21$