



Public Services

Engineering 212 Operations Center Drive Wilmington, NC 28412 910 341-7807 910 341-5881 fax wilmingtonnc.gov Dial 711 TTY/Voice

May 11, 2022

Mr. Charles Hale - Vice President of Operations & Programs Food Bank of Central & Eastern NC 1924 Capital Blvd Raleigh, NC, 27604

Subject:

Stormwater Management Permit No. 2022015R1

Wilmington Food Bank

High Density

Dear Mr. Hale:

The City of Wilmington Engineering Division has received a request for a revision to the Stormwater Management Permit for the Wilmington Food Bank. Having reviewed the application and all supporting materials, the City of Wilmington has determined that the proposed revision meets the requirements of the City of Wilmington's Comprehensive Stormwater Ordinance.

The revisions include:

- Replace RCP IV (shallow cover) pipe with RCP III

- Add an open grate structure for the infiltration basin inlet

Please be aware all terms and conditions of the permit 03/28/2022 remain in full force and effect. Any additional changes to the approved plans must be approved by this office prior to construction. The issuance of the plan revision does not preclude the permittee from complying with all other applicable statutes, rules, regulations or ordinances which may have jurisdiction over the proposed activity, and obtaining a permit or approval prior to construction.

The revised stamped, approved stormwater management drawings will be released for construction by the Wilmington Planning Division under separate cover. Please replace any old plan sheets from the approved set with the new, revised sheet. An electronic copy of the approved drawing set, permit, application and supplementary documents will be maintained by the Wilmington Engineering Division. If you have any questions, or need additional information, please contact Trent Butler at (910) 341-0094 or trent.butler@wilmingtonnc.gov

Sincerely,

for Anthony Caudle, City Manager

City of Wilmington

cc: Jerry Burks, P.E., Paramounte Engineering, Inc.

Jeff Walton, Wilmington Development Services/Planning







Public Services
Engineering
212 Operations Center Dr
Wilmington, NC 28412
910 341-7807
91 341-5881 fax
wilmingtonnc.gov
Dial 711 TTY/Voice

STORMWATER MANAGEMENT PERMIT APPLICATION FORM (Form SWP 2.3)

GENERAL INFORMATION 1. Project Name (subdivision, facility, or establishment name - should be consistent with project name on plans, specifications, letters, operation and maintenance agreements, etc.): 2. Location of Project (street address): County: New Hanover City: Wilmington Zip: II. PERMIT INFORMATION 1. Specify the type of project (check one): Low Density **High Density** Offsite Stormwater System Drainage Plan Redevelopment Other If the project drains to an Offsite System, list the Stormwater Permit Number(s): City of Wilmington: State – NCDEQ/DEMLR: _ 2. Is the project currently covered (whole or in part) by an existing City or State (NCDEQ/DEMLR) Stormwater Permit? Yes If yes, list all applicable Stormwater Permit Numbers: City of Wilmington: State – NCDEQ/DEMLR: 3. Additional Project Permit Requirements (check all applicable): **CAMA Major** Sedimentation/Erosion Control 404/401 Permit III. CONTACT INFORMATION 1. Print Applicant / Signing Official's name and title (the developer, property owner, lessee, designated government official, individual, etc. who owns the project): Applicant / Organization:

Signing Official & Title:



	 a. Contact information for Applic 	cant / Signing Official:	
	Address:		
	City:	State:	Zip:
	Phone:	Email:	
	b. Please check the appropriate	box. The applicant listed abo	ove is:
	The property owner/Purchase Lessee (Attach a copy of the lease Developer (Complete items 2 and	e agreement and complete items 2	and 2a below)
2.	Print Property Owner's name and title	e (if different from the applicant)	
	Property Owner / Organization:		
	Signing Official & Title:		
	a. Contact information for Prope	erty Owner:	
	Street Address:		
	City:	State:	Zip:
	Phone:	Email:	
3.	(Optional) Other Contact name and to all correspondence:	itle (such as a construction sup	ervisor) who would like to be copied
	Other Contact Person / Organization	:	
	Signing Official & Title:		
	a. Contact information for perso	n listed in item 3 above:	
	Street Address:		
	City:	State:	Zip:
	Phone:	Email:	
4.	Agent Authorization: Complete this see firm (such as a consulting engineer and project (such as addressing requests for	or firm) so that they may provid	
	Consulting Engineer:		
	Consulting Firm:		
	a. Contact information for consu		
	Mailing Address:		
	City:		
	Phone:	Email:	



IV. PROJECT INFORMATION

1.	Total Property Area: <u>223,942</u> square feet
2.	Total Coastal Wetlands Area: 0square feet
3.	Total Surface Water Area: 0square feet
4.	Total Property Area (1) – Total Coastal Wetlands Area (2) – Total Surface Water Area (3) = Total Project Area: 223,942 square feet.
5.	Existing Impervious Surface within Project Area: 45,787 square feet
6.	Existing Impervious Surface to be Removed/Demolished: 45,787 square feet
7.	Existing Impervious Surface to Remain: 0 square feet

8. Total Onsite (within property boundary) Newly Constructed Impervious Surface (in square feet):

Buildings/Lots	31,915
Impervious Pavement	53,295
Pervious Pavement (total area / adjusted area w credit applied)	0 /
Impervious Sidewalks	5,240
Pervious Sidewalks (total area / adjusted area w credit applied)	0 /
Other (Describe)	0
Future Development	0
Total Onsite Newly Constructed Impervious Surface	90,450

9. Total Onsite Impervious Surface (Existing Impervious Surface to remain + Onsite Newly Constructed Impervious Surface) 90,450 square feet

10. Net Change in Onsite Impervious Surface (+ for net increase, - for net decrease) +44,663 square feet

11. Project percent of impervious area: (Total Onsite Impervious Surface / Total Project Area) x100 = 40.4 %

12. Total Offsite Newly Constructed Impervious Area (in square feet):

Impervious Pavement	1,157
Pervious Pavement (total area / adjusted area w credit applied)	1
Impervious Sidewalks	2,115
Pervious Sidewalks (total area / adjusted area w credit applied)	1
Other (Describe)	
Total Offsite Newly Constructed Impervious Surface	3,272



13. Complete the following information for each Stormwater SCM drainage area. Low Density and Drainage Plan projects (with no permeable pavements) may omit this section and skip to Section V.

Basin Information	Infiltration Basin SCM # 1	Type of SCM SCM#	Type of SCM SCM#
Receiving Stream Name	Greenfield Creek		
Receiving Stream Index Number	18-76-1.4		
Stream Classification	C,SW		
Total Drainage Area (sf)	142,589		
On-Site Drainage Area (sf)	142,589		
Off-Site Drainage Area (sf)	0		
Buildings/Lots (sf)	31,915		
Impervious Pavement (sf)	53,295		
Pervious Pavement (total / adjusted) (sf)	0 /	1	/
Impervious Sidewalks (sf)	5,240		
Pervious Sidewalks (total / adjusted) (sf)	0 /	1	/
Other (sf)	0		
Future Development (sf)	0		
Existing Impervious to remain (sf)	0		
Offsite (sf)	3,272		
Total Impervious Area (sf)	90,450		
Percent Impervious Area (%)	63.43		

Basin Information	Type of SCM	Type of SCM	Type of SCM
Basiii iiiloiiilatioii	SCM#	SCM#	SCM#
Receiving Stream Name			
Receiving Stream Index Number			
Stream Classification			
Total Drainage Area (sf)			
On-Site Drainage Area (sf)			
Off-Site Drainage Area (sf)			
Buildings/Lots (sf)			
Impervious Pavement (sf)			
Pervious Pavement (total / adjusted) (sf)	1	1	/
Impervious Sidewalks (sf)			
Pervious Sidewalks (total / adjusted) (sf)	1	1	/
Other (sf)			
Future Development (sf)			
Existing Impervious to remain (sf)			
Offsite (sf)			
Total Impervious Area (sf)			
Percent Impervious Area (%)			



V. SUBMITTAL REQUIREMENTS

Only complete application packages will be accepted and reviewed by the City. A complete package includes all of the items listed below. Copies of forms, deed restrictions, checklists as well as detailed instructions on how to complete this application form may be downloaded from the City of Wilmington Plan Review website below:

https://www.wilmingtonnc.gov/departments/engineering/plan-review/stormwater-permits

The complete application package should be submitted to the following address:

City of Wilmington – Engineering Plan Review Section 212 Operations Center Dr. Wilmington, NC 28412

Please indicate that the following required information have been provided by initialing in the space provided for each item.

	Initials
1. One completed Stormwater Management Permit Application Form.	GJB
2. One completed Supplement Form for each SCM proposed (signed, sealed and dated).	GJB
3. One completed Operation & Maintenance agreement for each type of SCM.	GJB
4. Proposed Deed Restrictions and Restrictive Covenants (for all subdivisions)	N/A
5. Appropriate stormwater permit review fee.	GJB
 Minimum requirements identified on the Engineering Plan Review Checklist have been addressed. 	GJB —
7. One set of calculations (sealed. signed and dated).	GJB
8. A detailed narrative (one to two pages) describing the stormwater treatment/management system for the project.	ent _{GJB}
9. A USGS map identifying the site location. If the receiving stream is reported as class S or the receiving stream drains to class SA waters within ½ mile of the site boundary, include the ½ mile radius on the map.	GJB
10. A copy of the soils report, if applicable. Must meet NCDEQ SCM Manual and MDC requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations.	GJB
11. One full set of plans folded to 8.5" x 14".	GJB
12. A map delineating and labeling the drainage area for each SCM proposed.	GJB
13. A map delineating and labeling the drainage area for each inlet and conveyance propos	sed.
 A digital copy of the entire submittal package (can be submitted via flash drive, CD, em dropbox or other file sharing system). 	ail, _{GJB}



VI. PROPERTY OWNER AUTHO	DRIZATION (If Section III(2) has been filled out, complete this section)
1, Charlie Hale / Food Bank	CENC, certify that I own the property identified in this permit application, and
thus give permission to	with
	oposed. A copy of the lease agreement or pending property sales contract, which indicates the party responsible for the operation and maintenance of
the stormwater system.	, which indicates the party responsible for the operation and maintenance of
	vledge, understand, and agree by my signature below, that if my designateddissolves their company and/or cancels or defaults on their lease
agentagreement, or pending sale, respons	ibility for compliance with the City of Wilmington Stormwater Permit reverts
back to me, the property owner. As t	he property owner, it is my responsibility to notify the City of Wilmington
	Name/Ownership Change Form within 30 days; otherwise I will be operating
facility without a valid permit is a viol	ut a valid permit. I understand that the operation of a stormwater treatment ation of the City of Wilmington Municipal Code of Ordinances and may result
in appropriate enforcement including	
Signature:	Date: 10/12/21
	0 1 1 01
SEAL	I, Standa & Stallell , a Notary Public for the
	State of, County of, do
	hereby certify that Charles Hale
	personally appeared before me this day of,,,,
	and acknowledge the due execution of the application for a stormwater
	permit. Witness my hand and official seal,
	Notary Public Vol
	My commission expires: 6/5/2025 Wake
	County My Comm. Exp.
VII. APPLICANT'S CERTIFIC	00 15-2023 57 5
7 7 2.07 6 02	MILLIATA CAROLINIA
l,	certify that the information included on this permit application
	, correct and that the project will be constructed in conformance with the ed restrictions and protective covenants will be recorded, and that the
proposed project complies with the r	equirements of the applicable rules under the City's Comprehensive
Stormwater Ordinance.	
Simulatura () Att	Data: 10/12/21
Signature:	Date:
SEAL	I, Brenda K Naturen , a Notary Public for the
	State of, County of, do
	hereby certify that Charles Harle
	personally appeared before me this day of
	and acknowledge the due execution of the application for a stormwater
	and acknowledge the due execution of the application for a stormwall fring permit. Witness my hand and official seal,
	Notary Public 75
	My commission expired:
	My Comm. Exp.
	My commission expires: My commission expires:
	My Comm. Exp. My Comm. Exp. 06-15-2023 MY CAROLLINI MY
	"Mummulli

SUPPLEMENT-EZ COVER PAGE

RECEIVED

By Jeff Walton at 8:38 am, Mar 09, 2022

1	Project Name	The Wilmington Food Bank
2	Project Area (ac)	3.27
3	Coastal Wetland Area (ac)	0
4	Surface Water Area (ac)	0
5	Is this project High or Low Density?	High
6	Does this project use an off-site SCM?	no

СОМ	PLIANCE WITH 02H .1003(4)	
7	Width of vegetated setbacks provided (feet)	na na
8	Will the vegetated setback remain vegetated?	
9	If BUA is proposed in the setback, does it meet NCAC 02H.1003(4)(c-d)?	
10	Is streambank stabilization proposed on this project?	

11	Infiltration System	1
12	Bioretention Cell	
13	Wet Pond	
14	Stormwater Wetland	
15	Permeable Pavement	
16	Sand Filter	
17	Rainwater Harvesting (RWH)	
18	Green Roof	
19	Level Spreader-Filter Strip (LS-FS)	
20	Disconnected Impervious Surface (DIS)	
21	Treatment Swale	
22	Dry Pond	
23	StormFilter	
24	Silva Cell	
25	Bayfilter	
26	Filterra	

FORMS LOADED

DESIGNER CERTIFICATION		
27	Name and Title:	Gerald J. Burks, PE
28	Organization:	Paramounte Engineering, Inc.
29	Street address:	122 Cinema Drive
30	City, State, Zip:	Wilmington, NC 28409
31	Phone number(s):	910-791-6707
32	Email:	jburks@paramounte-eng.com

Certification Statement:

Designer

I certify, under penalty of law that this Supplement-EZ form and all supporting information were prepared under my direction or supervision; that the information provided in the form is, to the best of my knowledge and belief, true, accurate, and complete; and that the engineering plans, specifications, operation and maintenance agreements and other supporting information are consistent with the information provided here.

SEAL 050783

DRAINAGE AREAS

1	Is this a high density project?	Yes
2	If so, number of drainage areas/SCMs	1
3	Does this project have low density areas?	No
4	If so, number of low density drainage areas	0
	Is all/part of this project subject to previous rule	
5	versions?	No

FORMS LOADED

DRAIN	NAGE AREA INFORMATION	Entire Site	1
4	Type of SCM		Infiltration Basin
5	Total drainage area (sq ft)		142,589
6	Onsite drainage area (sq ft)		142,589
7	Offsite drainage area (sq ft)		
8	Total BUA in project (sq ft)	90450 sf	90450 sf
	New BUA on subdivided lots (subject to permitting)		
9	(sq ft)		
	New BUA not on subdivided lots (subject to		
10	permitting) (sf)	44663 sf	44663 sf
11	Offsite BUA (sq ft)	3272 sf	3272 sf
12	Breakdown of new BUA not on subdivided lots:		
12	- Parking (sq ft)	53295 sf	53295 sf
	- Sidewalk (sq ft)	5240 sf	5240 sf
	- Roof (sq ft)	31915 sf	31915 sf
	- Roadway (sq ft)	0101031	0101031
	- Future (sq ft)	sf	sf
	- Other, please specify in the comment box below	OI	- Oi
	(sq ft)		
	New infiltrating permeable pavement on subdivided		
13	lots (sq ft)		
	New infiltrating permeable pavement not on		
14	subdivided lots (sq ft)	sf	sf
	Existing BUA that will remain (not subject to		
15	permitting) (sq ft)		
16	Existing BUA that is already permitted (sq ft)		
17	Existing BUA that will be removed (sq ft)		
18	Percent BUA		63.43%
19	Design storm (inches)		1.50 in
	Design volume of SCM (cu ft)		15002 cf
21	Calculation method for design volume		simple

ADDITIONAL INFORMATION

Please use this space to provide any additional information about the drainage area(s):

INFILTRATION SYSTEM

3 4	Drainage area number	1
3 4	Minimum required treatment volume (cu ft)	11107 cf
3 4	AL MDC FROM 02H .1050	
4	Is the SCM sized to treat the SW from all surfaces at build-out?	Yes
	Is the SCM located away from contaminated soils?	Yes
	What are the side slopes of the SCM (H:V or enter "Vertical" for	100
5	trenches)?	3:1
	Does the SCM have retaining walls, gabion walls or other	
6	engineered side slopes?	No
	Are the inlets, outlets, and receiving stream protected from erosion	
7	(10-year storm)?	Yes
	Is there an overflow or bypass for inflow volume in excess of the	
8	design volume?	Yes
9	What is the method for dewatering the SCM for maintenance?	Pump (preferred
10	If applicable, will the SCM be cleaned out after construction?	Yes
11	Does the maintenance access comply with General MDC (8)?	Yes
12	Does the drainage easement comply with General MDC (9)?	Yes
4.0	If the SCM is on a single family lot, does (will?) the plat comply with	
13	General MDC (10)?	N/A
14	Is there an O&M Agreement that complies with General MDC (11)?	Yes
15	Is there an O&M Plan that complies with General MDC (12)?	Yes
16	Does the SCM follow the device specific MDC?	Yes
17	Was the SCM designed by an NC licensed professional?	Yes
NEII TE	RATION SYSTEM MDC FROM 02H .1051	
18	Proposed slope of the subgrade surface (%)	0%
19	Are terraces or baffles provided?	No.
20	· ·	Other
oils D	Type of pretreatment:	Other
olis D		
21	Was the soil investigated in the footprint and at the elevation of the	Yes
22	infiltration system?	12.50
22	SHWT elevation (fmsl)	
23	Depth to SHWT per soils report (in)	66.00
24	Ground elevation at boring in soils report (fmsl)	18.00
25	Is a detailed hydrogeologic study attached if the separation is	N/A
	between 1 and 2 feet?	
26	Soil infiltration rate (in/hr)	13.95
27	Factor of safety (FS) (2 is recommended):	2.00
Elevat		44.50.5
29	Bottom elevation (fmsl)	14.50 ft
30	Storage elevation (fmsl)	17. ft
31	Bypass elevation (fmsl)	17.25 ft
	asins Only	I
32	Bottom surface area (ft²)	4467 ft
33	Storage elevation surface area (ft²)	7583. ft
-	renches Only	
	Length (ft)	
or Tr	Width (ft)	
For Tr 34		
For Tr 34 35	Width (ft)	
For Tr 34 35 36	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals	
34 35 36 37 38	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping	
34 35 36 37 38 39	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable	
34 35 36 37 38 39 40	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%)	
34 35 36 37 38 39 40 41	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines?	
34 35 36 37 38 39 40 41 42	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric?	
34 35 36 37 38 39 40 41 42 43	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric? Has at least one inspection port been provided?	
34 35 36 37 38 39 40 41 42 43	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric? Has at least one inspection port been provided? nes/Drawdown	15002 cf
34 35 36 37 38 39 40 41 42 43 Volum	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric? Has at least one inspection port been provided? nes/Drawdown Design volume of SCM (cu ft)	15002 cf 6 hrs
34 35 36 37 38 39 40 41 42 43 Volum 44	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric? Has at least one inspection port been provided? nes/Drawdown Design volume of SCM (cu ft) Time to draw down (hours)	15002 cf 6 hrs
34 35 36 37 38 39 40 41 42 43 Volum 44	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric? Has at least one inspection port been provided? nes/Drawdown Design volume of SCM (cu ft) Time to draw down (hours)	
34 35 36 37 38 39 40 41 42 43 Volum 44	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric? Has at least one inspection port been provided? nes/Drawdown Design volume of SCM (cu ft) Time to draw down (hours) FIONAL INFORMATION Please use this space to provide any additional information about	
34 35 36 37 38 39 40 41 42 43 Volum 44 45 ADDIT	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric? Has at least one inspection port been provided? nes/Drawdown Design volume of SCM (cu ft) Time to draw down (hours) FIONAL INFORMATION Please use this space to provide any additional information about the infiltration system(s):	
34 35 36 37 38 39 40 41 42 43 Volum 44 45 ADDIT	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric? Has at least one inspection port been provided? nes/Drawdown Design volume of SCM (cu ft) Time to draw down (hours) FIONAL INFORMATION Please use this space to provide any additional information about	
34 35 36 37 38 39 40 41 42 43 Volum 44 45 ADDIT	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric? Has at least one inspection port been provided? nes/Drawdown Design volume of SCM (cu ft) Time to draw down (hours) FIONAL INFORMATION Please use this space to provide any additional information about the infiltration system(s):	
34 35 36 37 38 39 40 41 42 43 Volum 44 45 ADDIT	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric? Has at least one inspection port been provided? nes/Drawdown Design volume of SCM (cu ft) Time to draw down (hours) FIONAL INFORMATION Please use this space to provide any additional information about the infiltration system(s):	
34 35 36 37 38 39 40 41 42 43 Volum 44 45 ADDIT	Width (ft) Perforated pipe diameter, if applicable (inches) Number of laterals Total length of perforated piping Stone type, if applicable Stone porosity (%) Is stone free of fines? Is the stone wrapped in geotextile fabric? Has at least one inspection port been provided? nes/Drawdown Design volume of SCM (cu ft) Time to draw down (hours) FIONAL INFORMATION Please use this space to provide any additional information about the infiltration system(s):	



Permit Number:	
(to be provided by	City of Wilmington)
SCM Drainage B	asin #:

Infiltration Basin Operation and Maintenance Agreement

I will keep a maintenance record on this SCM. This maintenance record will be kept in a log in a known set location. Any deficient SCM elements noted in the inspection will be corrected, repaired or replaced **immediately**. These deficiencies can affect the integrity of structures, safety of the public, and the pollutant removal efficiency of the SCM.

Important maintenance procedures:

- The drainage area will be carefully managed to reduce the sediment load to the infiltration basin.
- Immediately after the infiltration basin is established, the vegetation will be watered twice weekly if needed until the plants become established (commonly six weeks).
- No portion of the infiltration basin will be fertilized after the initial fertilization that is required to establish the vegetation.
- The vegetation in and around the basin will be maintained at a height of approximately six inches.

After the infiltration basin is established, it will be inspected **once a quarter and within 24 hours after every storm event greater than 1.5 inches**. Records of operation and maintenance will be kept in a known set location and will be available upon request.

Inspection activities shall be performed as follows. Any problems that are found shall be repaired immediately.

SCM element:	Potential problem:	How to remediate the problem:
The entire SCM	Trash/debris is present.	Remove the trash/debris.
The perimeter of the	Areas of bare soil and/or	Regrade the soil if necessary, to
infiltration basin	erosive gullies have formed.	remove the gully, and then plant a
	9-30	ground cover and water until it is
		established. Provide lime and a
		one-time fertilizer application.
The inlet device: pipe or	The pipe is clogged (if	Unclog the pipe. Dispose of the
swale	applicable).	sediment off-site.
	The pipe is cracked or	Replace the pipe.
	otherwise damaged (if	
	applicable).	
	Erosion is occurring in the	Regrade the swale if necessary, to
	swale (if applicable).	smooth it over and provide erosion
	and seculation SSE	control devices such as reinforced
		turf matting or riprap to avoid
		future problems with erosion.

SCM element:	Potential problem:	How to remediate the problem:
The forebay	Sediment has accumulated	Search for the source of the
	and reduced the depth to 75%	sediment and remedy the problem if
	of the original design depth.	possible. Remove the sediment and
		dispose of it in a location where it
		will not cause impacts to streams or
		the SCM. Replace any media that
		was removed in the process.
		Revegetate disturbed areas
		immediately.
	Erosion has occurred or	Provide additional erosion
	riprap is displaced.	protection such as reinforced turf
		matting or riprap if needed to
	70	prevent future erosion problems.
	Weeds are present.	Remove the weeds, preferably by
	1	hand. If pesticides are used, wipe
		them on the plants rather than
		spraying.
The main treatment area	A visible layer of sediment	Search for the source of the
	has accumulated.	sediment and remedy the problem if
		possible. Remove the sediment and
		dispose of it in a location where it
		will not cause impacts to streams or
2.5		the SCM. Replace any media that
		was removed in the process.
		Revegetate disturbed areas
		immediately.
	Water is standing more than	Replace the top few inches of filter
	5 days after a storm event.	media and see if this corrects the
		standing water problem. If so,
		revegetate immediately. If not,
		consult an appropriate professional
		for a more extensive repair.
	Weeds and noxious plants are	Remove the plants by hand or by
	growing in the main	wiping them with pesticide (do not
	treatment area.	spray).
The embankment	Shrubs or trees have started	Remove shrubs or trees
	to grow on the embankment.	immediately.
	An annual inspection by an	Make all needed repairs.
	appropriate professional	Š.
	shows that the embankment	
*	needs repair.	¥
The outlet device	Clogging has occurred.	Clean out the outlet device. Dispose
		of the sediment off-site.
	The outlet device is damaged	Repair or replace the outlet device.
The receiving water	Erosion or other signs of	Contact the local NC Department of
	damage have occurred at the	Environment and Natural Resources
	outlet.	Regional Office.

Permit Number:	
(to be provid	led by City of Wilmington)

I acknowledge and agree by my signature below that I am responsible for the performance of the maintenance procedures listed above. I agree to notify the City of Wilmington of any problems with the system or prior to any changes to the system or responsible party.

Project name: The Wilmington Food Bank
SCM drainage basin number: 1
Print name: Charlie Hale
Title: Senior Vice President of Operations
Address: 1924 Capital Blvd Raleigh, NC 27604
Phone: 919-865-3057
Signature:
Date: 1/27/22
Note: The legally responsible party should not be a homeowners' association unless more than 50% of the lots have been sold and a resident of the subdivision has been named the president. I, Bread A Notary Public for the State of A One of th
forgoing infiltration basin maintenance requirements. Witness my hand and official seal,
SEAL

My commission expires 6-15-2023