



Engineering
212 Operations Center Drive
Wilmington, NC 28412
910 341-7807
910 341-5881 fax
wilmingtonnc.gov
Dial 711 TTY/Voice

COMPREHENSIVE STORMWATER MANAGEMENT PERMIT

HIGH DENSITY DEVELOPMENT

SECTION 1 – APPROVAL

Having reviewed the application and all supporting materials, the City of Wilmington has determined that the application is complete and the proposed development meets the requirements of the City of Wilmington's Comprehensive Stormwater Ordinance.

PERMIT HOLDER: Seahawk Cove SH, LLC

PROJECT: Seahawk Cove

ADDRESS: 615, 617, 619, 621 & 623 S. Kerr Avenue

PERMIT #: 2016019R2

DATE: **January 25, 2023**

Therefore, the above referenced site is hereby approved and subject to all conditions set forth in Section 2 of this approval and all applicable provisions of the City of Wilmington Comprehensive Stormwater Management Ordinance.

This permit shall be effective from the date of issuance until January 25, 2031 and shall be subject to the following specified conditions and limitations:

Section 2 - CONDITIONS

- 1. This approval is valid only for the stormwater management system as proposed on the approved stormwater management plans dated January 24, 2023.
- 2. The project will be limited to the amount and type of built-upon area indicated in Section IV of the Stormwater Management Application Form submitted as part of the approved stormwater permit application package, and per the approved plans.
- 3. This permit shall become void unless the facilities are constructed in accordance with the approved stormwater management plans, specifications and supporting documentation, including information provided in the application and supplements.
- 4. The runoff from all built-upon area within any permitted drainage area must be directed into the permitted stormwater control system for that drainage area.
- 5. The permittee shall submit a revised stormwater management application packet to the City of Wilmington and shall have received approval prior to construction, for any modification to the approved plans, including, but not limited to, those listed below:
 - a. Any revision to any item shown on the approved plans, including the stormwater management measures, built-upon area, details, etc.
 - b. Redesign or addition to the approved amount of built-upon area or to the drainage area.
 - c. Further subdivision, acquisition, lease or sale of any part of the project area.
 - d. Filling in, altering, or piping of any vegetative conveyance shown on the approved plan.
 - e. Construction of any permitted future areas shown on the approved plans.





Engineering 212 Operations Center Drive Wilmington, NC 28412 910 341-7807 910 341-5881 fax wilmingtonnc.gov Dial 711 TTY/Voice

- 6. A copy of the approved plans and specifications shall be maintained on file by the Permittee.
- 7. During construction, erosion shall be kept to a minimum and any eroded areas of the system will be repaired immediately.
- 8. If the stormwater system was used as an Erosion Control device, it must be restored to design condition prior to operation as a stormwater treatment device, and prior to issuance of any certificate of occupancy for the project.
- 9. All areas must be maintained in a permanently stabilized condition. If vegetated, permanent seeding requirements must follow the guidelines established in the North Carolina Erosion and Sediment Control Planning and Design Manual unless an alternative is specified and approved by the City of Wilmington.
- 10. All applicable operation & maintenance agreements and easements pertaining to each stormwater treatment system shall be referenced on the final plat and recorded with the Register of Deeds upon final plat approval. If no plat is recorded for the site the operation and maintenance agreements and easements shall be recorded with the Register of Deeds so as to appear in the chain of title of all subsequent purchasers under generally accepted searching standards.
- 11. The stormwater management system shall be constructed in its entirety, vegetated and operational for its intended use prior to the construction of any built-upon surface unless prior approval is obtained. City Staff must be notified of any deviation prior to construction of the built-upon surface. Any deviation request shall include justification and must propose an alternative timeline or construction sequence. Notification shall not constitute approval. Any alternative timeline approved by City staff shall become an enforceable component of this permit.
- 12. The permittee shall at all times provide the operation and maintenance necessary to assure the permitted stormwater system functions at optimum efficiency. The approved Operation and Maintenance Agreement must be followed in its entirety and maintenance must occur at the scheduled intervals including, but not limited to:
 - a. Scheduled inspections (interval noted on the agreement).
 - b. Sediment removal.
 - c. Mowing and revegetation of slopes and the vegetated areas.
 - d. Maintenance of landscape plants, including those within the landscape buffer and on the vegetated shelf.
 - e. Immediate repair of eroded areas, especially slopes.
 - f. Debris removal and unclogging of outlet structure, orifice device, flow spreader, catch basins and/or piping.
 - g. Access to the outlet structure must be available at all times.
- 13. Records of inspection, maintenance and repair for the permitted stormwater system must be kept by the permittee for at least 5 years from the date of record and made available upon request to authorized personnel of the City of Wilmington. The records will indicate the date, activity, name of person performing the work and what actions were taken.





Engineering
212 Operations Center Drive
Wilmington, NC 28412
910 341-7807
910 341-5881 fax
wilmingtonnc.gov
Dial 711 TTY/Voice

- 14. Upon completion of construction, before a Certificate of Occupancy shall be granted, and prior to operation or intended use of this permitted facility, the applicant shall submit to the City of Wilmington as-built plans for all stormwater management facilities. The plans shall show the final design specifications and the field location, type, depth, invert and planted vegetation of all measures, controls and devices, as installed. A certification shall be submitted, along with all supporting documentation that specifies, under seal that the as-built stormwater measures, controls and devices are in compliance with the approved stormwater management plans. A final inspection by City of Wilmington personnel will be required prior to issuance of a certificate of occupancy or operation of the permitted facility.
- 15. This permit is not transferable except after application and approval by the City of Wilmington. In the event of a change of ownership, name change or change of address the permittee must submit a completed Name/Ownership Change form to the City of Wilmington at least 30 days prior to the change. It shall be signed by all applicable parties and be accompanied by all required supporting documentation. Submittal of a complete application shall not be construed as an approved application. The application will be reviewed on its own merits by the City of Wilmington and may or may not be approved. The project must be in compliance with the terms of this permit in order for the transfer request to be considered. The permittee is responsible for compliance with all permit conditions until such time as the City of Wilmington approves the transfer request. Neither the sale of the project nor the conveyance of common area to a third party should be considered as an approved transfer of the permit.
- 16. Failure to abide by the conditions and limitations contained in this permit may subject the Permittee to enforcement action by the City of Wilmington, in accordance with Sections 18-52 and 18-53 and any other applicable section of the Land Development Code.
- 17. The City of Wilmington may notify the permittee when the permitted site does not meet one or more of the minimum requirements of the permit. Within the time frame specified in the notice, the permittee shall submit a written time schedule to the City of Wilmington for modifying the site to meet minimum requirements. The permittee shall provide copies of revised plans and certification in writing to the City of Wilmington that the changes have been made.
- 18. The issuance of this permit does not preclude the Permittee from complying with any and all statutes, rules, regulations, or ordinances, which may be imposed by other government agencies (local, state, and federal) having jurisdiction.
- 19. In the event that the facilities fail to perform satisfactorily, including the creation of nuisance conditions, the Permittee shall take immediate corrective action, including those as may be required by the City of Wilmington, such as the construction of additional or replacement stormwater management systems.
- 20. The permittee grants City of Wilmington Staff permission to enter the property during normal business hours for the purpose of inspecting all components of the permitted stormwater management facility.





Engineering 212 Operations Center Drive Wilmington, NC 28412 910 341-7807 910 341-5881 fax wilmingtonnc.gov Dial 711 TTY/Voice

- 21. The permit issued shall continue in force and effect until revoked or terminated by the City of Wilmington. The permit may be modified, revoked and reissued or terminated for cause. The filing of a request for a permit modification, revocation and re-issuance or termination does not stay any permit condition.
- 22. The approved stormwater management plans and all documentation submitted as part of the approved stormwater management permit application package for this project are incorporated by reference and are enforceable parts of the permit.
- 23. The permittee shall submit a renewal request with all required forms and documentation at least 180 days prior to the expiration date of this permit.
- 24. If any one or more of the conditions of this permit is found to be unenforceable or otherwise invalidated, all remaining conditions shall remain in full effect.

Stormwater Management Permit issued this the 25th day of January, 2023.

for Anthony Caudle, City Manager

City of Wilmington







Public Services
Engineering
212 Operations Center Dr
Wilmington, NC 28412
910 341-7807
91 341-5881 fax
wilmingtonnc.gov
Dial 711 TTY/Voice

STORMWATER MANAGEMENT PERMIT APPLICATION FORM (Form SWP 2.3)

I.	GENERAL INFORMATION
1.	Project Name (subdivision, facility, or establishment name - should be consistent with project name on plans, specifications, letters, operation and maintenance agreements, etc.): SEAHAWK COVE
2.	Location of Project (street address): 615, 617, 619, 621, AND 623 SOUTH KERR AVENUE
	City: Wilmington County: New Hanover Zip: 28403
II.	PERMIT INFORMATION
1.	Specify the type of project (check one): Low Density High Density Offsite Stormwater System Drainage Plan Redevelopment Other If the project drains to an Offsite System, list the Stormwater Permit Number(s): City of Wilmington: State – NCDEQ/DEMLR:
2.	Is the project currently covered (whole or in part) by an existing City or State (NCDEQ/DEMLR) Stormwater Permit? (a) Yes (No
	If yes, list all applicable Stormwater Permit Numbers:
	City of Wilmington: SWP2016019R1 State – NCDEQ/DEMLR:
3.	Additional Project Permit Requirements (check all applicable): CAMA Major Sedimentation/Erosion Control 404/401 Permit
Ш.	CONTACT INFORMATION
1.	Print Applicant / Signing Official's name and title (the developer, property owner, lessee, designated government official, individual, etc. who owns the project):
	Applicant / Organization: SEAHAWK COVE SH, LLC
	Signing Official & Title: BARRY COPPEDGE, MANAGER



	 a. Contact information for Applicant / Signing Offi Address: 305 PETTGREW DRIVE 	cial:				
	City: WILMINGTON St	ate.		ИС		_
	Phone: 910-367-9782 Er					- 3
	b. Please check the appropriate box. The applica The property owner/Purchaser (Skip to item 3) Lessee (Attach a copy of the lease agreement and composed (Complete items 2 and 2a below.)					
2.		ne a	nn	olicant).		
	Property Owner / Organization:			,		
	Signing Official & Title:					_
	a. Contact information for Property Owner:					_
	Street Address:					_
	City:St					_
	Phone:Er	nail:				_
3.	 (Optional) Other Contact name and title (such as a cons on all correspondence: 	truc	tio	n superviso	r) who would like to be copied	
	Other Contact Person / Organization:					_
	Signing Official & Title:					_
	a. Contact information for person listed in item 3 a	bov	/e:			
	Street Address:					
	City:St:					
	Phone:En	nail:				_
4.	firm (such as a consulting engineer and /or firm) so that they project (such as addressing requests for additional information	ma	ıy μ			
	Consulting Engineer: DAVID L. MENIUS, P.E.					
	Consulting Firm: STROUD ENGINEERING, P.A.					_
	a. Contact information for consultant listed above:					
	Mailing Address: 102-D CINEMA DRIVE					_
	City: WILMINGTON Sta	ıte:	N	IC	z _{ip: 28403}	_
	Phone: 910-815-0775 En	ail:		LMENIUS(@STROUDENGINEER.COM	l



IV. PROJECT INFORMATION

1.	Total Property Area: 149,986 square feet
2.	Total Coastal Wetlands Area: 0square feet
3.	Total Surface Water Area: 0square feet
4.	Total Property Area (1) – Total Coastal Wetlands Area (2) – Total Surface Water Area (3) = Total Project Area: $\frac{149,986}{}$ square feet.
5.	Existing Impervious Surface within Project Area: 53,085 square feet
6.	Existing Impervious Surface to be Removed/Demolished: 4,428 square feet
7.	Existing Impervious Surface to Remain: 48,657square feet

8.	Total Onsite (within property boundary) Newly Constru	cted Impervious Surface	(in square feet):
Г	D. O. H. C.		1

Buildings/Lots	9,320		
Impervious Pavement	19,876		
Pervious Pavement (total area / adjusted area w credit applied)	0	1	0
Impervious Sidewalks		2,243	
Pervious Sidewalks (total area / adjusted area w credit applied)	0	1	0
Other (Describe)		0	
Future Development		500	
Total Onsite Newly Constructed Impervious Surface		31,939	

^	T-4-1	O:4-	Lancia a se si a cola	0
9.	rotai	Onsite	Impervious	бипасе

(Existing Impervious Surface to remain + Onsite Newly Constructed Impervious Surface) 80,596 square feet

- 10. Net Change in Onsite Impervious Surface (+ for net increase, for net decrease) +27,511 square feet
- 11. Project percent of impervious area: (Total Onsite Impervious Surface / Total Project Area) x100 = 53.7 %
- 12. Total Offsite Newly Constructed Impervious Area (in square feet):

Impervious Pavement	()		
Pervious Pavement (total area / adjusted area w credit applied)			1	0
Impervious Sidewalks			0	
Pervious Sidewalks (total area / adjusted area w credit appl	ied)	0	1	0
Other 100 LF FUTURE 10' WIDE MULTI USE PATH			1000	
Total Offsite Newly Constructed Impervious Surface			1000	



13. Complete the following information for each Stormwater SCM drainage area. Low Density and Drainage Plan projects (with no permeable pavements) may omit this section and skip to Section V.

Basin Information	Type of SCM SCM 1	Type of SCM SCM#	Type of SCM SCM#
Receiving Stream Name	BURNT MILL CREEK		
Receiving Stream Index Number	18-74-63-2		
Stream Classification	C;SW		
Total Drainage Area (sf)	33,864		
On-Site Drainage Area (sf)	33,864		
Off-Site Drainage Area (sf)	0		
Buildings/Lots (sf)	9,320		and the same of the same of the same
Impervious Pavement (sf)	19,876		
Pervious Pavement (total / adjusted) (sf)	0 /0	1	1
Impervious Sidewalks (sf)	2,243		
Pervious Sidewalks (total / adjusted) (sf)	0 /0	1	/
Other (sf)	0		
Future Development (sf)	500		
Existing Impervious to remain (sf)	0		
Offsite (sf)	0	71,000	100011
Total Impervious Area (sf)	31,939	1955	PHOS
Percent Impervious Area (%)	94.3		

Basin Information	Type of SCM SCM#	Type of SCM SCM#	Type of SCM SCM#
Receiving Stream Name			
Receiving Stream Index Number			
Stream Classification			
Total Drainage Area (sf)			
On-Site Drainage Area (sf)			
Off-Site Drainage Area (sf)			
Buildings/Lots (sf)			
Impervious Pavement (sf)			
Pervious Pavement (total / adjusted) (sf)	1	1	/
Impervious Sidewalks (sf)			
Pervious Sidewalks (total / adjusted) (sf)	1	/	1
Other (sf)			
Future Development (sf)			
Existing Impervious to remain (sf)			
Offsite (sf)			
Total Impervious Area (sf)			
Percent Impervious Area (%)			



V. SUBMITTAL REQUIREMENTS

Only complete application packages will be accepted and reviewed by the City. A complete package includes all of the items listed below. Copies of forms, deed restrictions, checklists as well as detailed instructions on how to complete this application form may be downloaded from the City of Wilmington Plan Review website below:

https://www.wilmingtonnc.gov/departments/engineering/plan-review/stormwater-permits

The complete application package should be submitted to the following address:

City of Wilmington – Engineering Plan Review Section 212 Operations Center Dr. Wilmington, NC 28412

Please indicate that the following required information have been provided by initialing in the space provided for each item.

1. One completed Stormwater Management Permit Application Form. 2. One completed Supplement Form for each SCM proposed (signed, sealed and dated). 3. One completed Operation & Maintenance agreement for each type of SCM. 4. Proposed Deed Restrictions and Restrictive Covenants (for all subdivisions) 5. Appropriate stormwater permit review fee. 6. Minimum requirements identified on the Engineering Plan Review Checklist have been addressed. 7. One set of calculations (sealed. signed and dated). 8. A detailed narrative (one to two pages) describing the stormwater treatment/management system for the project. 9. A USGS map identifying the site location. If the receiving stream is reported as class SA or the receiving stream drains to class SA waters within ½ mile of the site boundary, include the ½ mile radius on the map. 10. A copy of the soils report, if applicable. Must meet NCDEQ SCM Manual and MDC requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations. 11. One full set of plans folded to 8.5" x 14". 12. A map delineating and labeling the drainage area for each SCM proposed. 13. A map delineating and labeling the drainage area for each inlet and conveyance proposed. 14. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email, dropbox or other file sharing system).	•		Initials
3. One completed Operation & Maintenance agreement for each type of SCM. 4. Proposed Deed Restrictions and Restrictive Covenants (for all subdivisions) 5. Appropriate stormwater permit review fee. 6. Minimum requirements identified on the Engineering Plan Review Checklist have been addressed. 7. One set of calculations (sealed. signed and dated). 8. A detailed narrative (one to two pages) describing the stormwater treatment/management system for the project. 9. A USGS map identifying the site location. If the receiving stream is reported as class SA or the receiving stream drains to class SA waters within ½ mile of the site boundary, include the ½ mile radius on the map. 10. A copy of the soils report, if applicable. Must meet NCDEQ SCM Manual and MDC requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations. 11. One full set of plans folded to 8.5" x 14". 12. A map delineating and labeling the drainage area for each SCM proposed. 13. A map delineating and labeling the drainage area for each inlet and conveyance proposed. 14. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email,	1.	One completed Stormwater Management Permit Application Form.	h
 4. Proposed Deed Restrictions and Restrictive Covenants (for all subdivisions) 5. Appropriate stormwater permit review fee. 6. Minimum requirements identified on the Engineering Plan Review Checklist have been addressed. 7. One set of calculations (sealed. signed and dated). 8. A detailed narrative (one to two pages) describing the stormwater treatment/management system for the project. 9. A USGS map identifying the site location. If the receiving stream is reported as class SA or the receiving stream drains to class SA waters within ½ mile of the site boundary, include the ½ mile radius on the map. 10. A copy of the soils report, if applicable. Must meet NCDEQ SCM Manual and MDC requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations. 11. One full set of plans folded to 8.5" x 14". 12. A map delineating and labeling the drainage area for each SCM proposed. 13. A map delineating and labeling the drainage area for each inlet and conveyance proposed. 14. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email, 	2.	One completed Supplement Form for each SCM proposed (signed, sealed and dated).	h
5. Appropriate stormwater permit review fee. 6. Minimum requirements identified on the Engineering Plan Review Checklist have been addressed. 7. One set of calculations (sealed. signed and dated). 8. A detailed narrative (one to two pages) describing the stormwater treatment/management system for the project. 9. A USGS map identifying the site location. If the receiving stream is reported as class SA or the receiving stream drains to class SA waters within ½ mile of the site boundary, include the ½ mile radius on the map. 10. A copy of the soils report, if applicable. Must meet NCDEQ SCM Manual and MDC requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations. 11. One full set of plans folded to 8.5" x 14". 12. A map delineating and labeling the drainage area for each SCM proposed. 13. A map delineating and labeling the drainage area for each inlet and conveyance proposed. 14. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email,	3.	One completed Operation & Maintenance agreement for each type of SCM.	<u>_</u>
6. Minimum requirements identified on the Engineering Plan Review Checklist have been addressed. 7. One set of calculations (sealed. signed and dated). 8. A detailed narrative (one to two pages) describing the stormwater treatment/management system for the project. 9. A USGS map identifying the site location. If the receiving stream is reported as class SA or the receiving stream drains to class SA waters within ½ mile of the site boundary, include the ½ mile radius on the map. 10. A copy of the soils report, if applicable. Must meet NCDEQ SCM Manual and MDC requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations. 11. One full set of plans folded to 8.5" x 14". 12. A map delineating and labeling the drainage area for each SCM proposed. 13. A map delineating and labeling the drainage area for each inlet and conveyance proposed. 14. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email,	4.	Proposed Deed Restrictions and Restrictive Covenants (for all subdivisions)	NA
 Done set of calculations (sealed. signed and dated). A detailed narrative (one to two pages) describing the stormwater treatment/management system for the project. A USGS map identifying the site location. If the receiving stream is reported as class SA or the receiving stream drains to class SA waters within ½ mile of the site boundary, include the ½ mile radius on the map. A copy of the soils report, if applicable. Must meet NCDEQ SCM Manual and MDC requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations. One full set of plans folded to 8.5" x 14". A map delineating and labeling the drainage area for each SCM proposed. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email, 	5.	Appropriate stormwater permit review fee.	<u></u>
 A detailed narrative (one to two pages) describing the stormwater treatment/management system for the project. A USGS map identifying the site location. If the receiving stream is reported as class SA or the receiving stream drains to class SA waters within ½ mile of the site boundary, include the ½ mile radius on the map. A copy of the soils report, if applicable. Must meet NCDEQ SCM Manual and MDC requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations. One full set of plans folded to 8.5" x 14". A map delineating and labeling the drainage area for each SCM proposed. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email, 	6.		h
 9. A USGS map identifying the site location. If the receiving stream is reported as class SA or the receiving stream drains to class SA waters within ½ mile of the site boundary, include the ½ mile radius on the map. 10. A copy of the soils report, if applicable. Must meet NCDEQ SCM Manual and MDC requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations. 11. One full set of plans folded to 8.5" x 14". 12. A map delineating and labeling the drainage area for each SCM proposed. 13. A map delineating and labeling the drainage area for each inlet and conveyance proposed. 14. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email, 	7.	One set of calculations (sealed. signed and dated).	4
or the receiving stream drains to class SA waters within ½ mile of the site boundary, include the ½ mile radius on the map. 10. A copy of the soils report, if applicable. Must meet NCDEQ SCM Manual and MDC requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations. 11. One full set of plans folded to 8.5" x 14". 12. A map delineating and labeling the drainage area for each SCM proposed. 13. A map delineating and labeling the drainage area for each inlet and conveyance proposed. 14. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email,	8.		4
requirements for the type of SCM proposed. The report must include boring logs and a map of boring locations. 11. One full set of plans folded to 8.5" x 14". 12. A map delineating and labeling the drainage area for each SCM proposed. 13. A map delineating and labeling the drainage area for each inlet and conveyance proposed. 14. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email,	9.	or the receiving stream drains to class SA waters within ½ mile of the site boundary,	h
 12. A map delineating and labeling the drainage area for each SCM proposed. 13. A map delineating and labeling the drainage area for each inlet and conveyance proposed. 14. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email, 	10.	requirements for the type of SCM proposed. The report must include boring logs	4
13. A map delineating and labeling the drainage area for each inlet and conveyance proposed.14. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email,	11.	One full set of plans folded to 8.5" x 14".	ln
14. A digital copy of the entire submittal package (can be submitted via flash drive, CD, email,	12.	A map delineating and labeling the drainage area for each SCM proposed.	ln
	13.	A map delineating and labeling the drainage area for each inlet and conveyance proposed.	4
	14.		4



PROPERTY OWNER AUTH	ORIZATION (If Section III(2) has been filled out, complete this section)
I.	certify that I own the property identified in this permit application, and
to develop the project as currently phas been provided with the submitted the stormwater system.	proposed. A copy of the lease agreement or pending property sales contract al, which indicates the party responsible for the operation and maintenance of
As the legal property owner I acknowledge, understand, and agree by my agnature below, that if my designated agent	
Signature:	Date:
SEAL	State of, County of, do hereby certify that personally appeared before me this day of,, and acknowledge the due execution of the application for a stormwater
VII APPLICANT'S CEPTIFIC	
I, BARRY COPPEDGE form is, to the best of my knowledge approved plans, that the required de proposed project complies with the Stormwater Ordinance.	certify that the information included on this permit application e, correct and that the project will be constructed in conformance with the sed restrictions and protective covenants will be recorded, and that the requirements of the applicable rules under the City's Comprehensive
SEAL OTAP OTAP MININGS ONE OTAP OTAP	

SUPPLEMENT-EZ COVER PAGE

FORMS LOADED

1	Project Name	SEAHAWK COVE	
2	Project Area (ac)	3.44	
3	Coastal Wetland Area (ac)	0	
4	Surface Water Area (ac)	0	
5	Is this project High or Low Density?	High	
6	Does this project use an off-site SCM?	No	

7	Width of vegetated setbacks provided (feet)	NA	
8	Will the vegetated setback remain vegetated?	N/A	
9	If BUA is proposed in the setback, does it meet NCAC 02H.1003(4)(c-d)?	N/A	
10	Is streambank stabilization proposed on this project?	No	

NUME	BER AND TYPE OF SCMs:	
11	Infiltration System	1
12	Bioretention Cell	
13	Wet Pond	
14	Stormwater Wetland	
15	Permeable Pavement	
16	Sand Filter	
1.7	Rainwater Harvesting (RWH)	
18	Green Roof	
19	Level Spreader-Filter Strip (LS-FS)	
20	Disconnected Impervious Surface (DIS)	
21	Treatment Swale	
22	Dry Pond	
23	StormFilter	
24	Silva Cell	
25	Bayfilter	
26	Filterra	

FORMS LOADED

DESIGNER CERTIFICATION		
27	Name and Title:	DAVID L. MENIUS, P.E.
28	Organization:	STROUD ENGINEERING, P.A.
29	Street address:	102-D CINEMA DRIVE
30	City, State, Zip:	WILMINGTON, NC 28403
31	Phone number(s):	910-815-0775
32	Email:	LMENIUS@STROUDENGINEER.COM

Certification Statement:

I certify, under penalty of law that this Supplement-EZ form and all supporting information were prepared under my direction or supervision; that the information provided in the form is, to the best of my knowledge and belief, true, accurate, and complete; and that the engineering plans, specifications, operation and maintenance agreements and other supporting information are consistent with the information provided here.

Designer CARO FESSION SEAL SEAL	Signature of Designer
35677 35677 MENINITION Seal	Date Designed

DRAINAGE AREAS

1	Is this a high density project?	Yes
2	If so, number of drainage areas/SCMs	1
3	Does this project have low density areas?	No
4	If so, number of low density drainage areas	0
	Is all/part of this project subject to previous rule	
5	versions?	No

FORMS LOADED

DRA	NAGE AREA INFORMATION	Entire Site	1
4	Type of SCM		Infiltration Trench
5	Total drainage area (sq ft)	149,986	33,864
6	Onsite drainage area (sq ft)	149986	33,864
7	Offsite drainage area (sq ft)	0	0
8	Total BUA in project (sq ft)	80596 sf	
	New BUA on subdivided lots (subject to		
9	permitting) (sq ft)	0	0
	New BUA not on subdivided lots (subject to		
10	permitting) (sf)	80596 sf	31939 sf
11	Offsite BUA (sq ft)	sf	sf
12	Breakdown of new BUA not on subdivided lots:		
	- Parking (sq ft)	19876 sf	19876 sf
	- Sidewalk (sq ft)	2243 sf	2243 sf
	- Roof (sq ft)	9320 sf	9320 sf
	- Roadway (sq ft)	0	0
	- Future (sq ft)	500	500
	Other, please specify in the comment box below (sq ft)		
	New infiltrating permeable pavement on		
13	subdivided lots (sq ft)	0	0
	New infiltrating permeable pavement not on		
14	subdivided lots (sq ft)	0	0
	Existing BUA that will remain (not subject to		A NAME OF THE OWN
15	permitting) (sq ft)	0	0
16	Existing BUA that is already permitted (sq ft)	48657 sf	sf
17	Existing BUA that will be removed (sq ft)	4428 sf	4428 sf
18	Percent BUA	54%	94%
19	Design storm (inches)	1.5 in	1.5 in
20	Design volume of SCM (cu ft)		3805 cf
21	Calculation method for design volume		SCHULER

ADDITIONAL INFORMATION

Please use this space to provide any additional information about the drainage area(s):

INFILTRATION SYSTEM

1	Drainage area number	1
2	Minimum required treatment volume (cu ft)	3805 cf
ENER	<u>AL MDC FROM 02H .1050</u>	
3	Is the SCM sized to treat the SW from all surfaces at build-out?	Yes
4	Is the SCM located away from contaminated soils?	Yes
-	What are the side slopes of the SCM (H:V or enter "Vertical" for	
5	trenches)?	vertical
^	Does the SCM have retaining walls, gabion walls or other	
6	engineered side slopes?	No
7	Are the inlets, outlets, and receiving stream protected from erosion	
/	(10-year storm)?	Yes
8	Is there an overflow or bypass for inflow volume in excess of the	
	design volume?	Yes
9	What is the method for dewatering the SCM for maintenance?	Pump (preferred
10	If applicable, will the SCM be cleaned out after construction?	Yes
11	Does the maintenance access comply with General MDC (8)?	Yes
12	Does the drainage easement comply with General MDC (9)?	N/A
13	If the SCM is on a single family lot, does (will?) the plat comply with	
10	General MDC (10)?	N/A
14	Is there an O&M Agreement that complies with General MDC (11)?	
		Yes
15	Is there an O&M Plan that complies with General MDC (12)?	Yes
16	Does the SCM follow the device specific MDC?	Yes
17	Was the SCM designed by an NC licensed professional?	Yes
VFILTE	ATION SYSTEM MDC FROM 02H .1051	
18	Proposed slope of the subgrade surface (%)	0%
19	Are terraces or baffles provided?	Yes
20	Type of pretreatment:	Other
oils Do	danida	
~ .	Was the soil investigated in the footprint and at the elevation of the	***************************************
21	infiltration system?	Yes
22	SHWT elevation (fmsl)	33.10
23	Depth to SHWT per soils report (in)	46.00
24	Ground elevation at boring in soils report (fmsl)	36.90
	Is a detailed hydrogeologic study attached if the separation is	00.00
25	between 1 and 2 feet?	N/A
26	Soil infiltration rate (in/hr)	7.83
27	Factor of safety (FS) (2 is recommended):	1.00
levat		
29	Bottom elevation (fmsl)	35.10
30	Storage elevation (fmsl)	37.10
31	Bypass elevation (fmsl)	37.15
	ssins Only	07,10
32	Bottom surface area (ft²)	***************************************

	Storage elevation surface area (ft²)	***************************************
***************************************	enches Only	
	Length (ft)	145 ft
35	Width (ft)	41 ft
36	Perforated pipe diameter, if applicable (inches)	18 in
37	Number of laterals	14
38	Total length of perforated piping	1960 ft
39	Stone type, if applicable	WASHED #57
40	Stone porosity (%)	40%
41	Is stone free of fines?	Yes
42	Is the stone wrapped in geotextile fabric?	Yes
	Has at least one inspection port been provided?	Yes
	es/Drawdown	
44	Design volume of SCM (cu ft)	3805 cf
45	Time to draw down (hours)	2 hrs
DDIT	IONAL INFORMATION	
	Please use this space to provide any additional information about	
46	the infiltration system(s):	
#1 N ·		
нтЭ:	The offset inverts in junction boxes functions	
	as a terrace.	
	The collection system is designed as a sure	
#20:	The conection system is designed as a sumn.	
‡ 20:	The collection system is designed as a sump. Additionally, sumps are provided in structures.	

Permit Number:	
(to be provided by	City of Wilmington)
SCM Drainage B	asin #:

Infiltration Trench Operation and Maintenance Agreement

I will keep a maintenance record on this SCM. This maintenance record will be kept in a log in a known set location. Any deficient SCM elements noted in the inspection will be corrected, repaired or replaced **immediately**. These deficiencies can affect the integrity of structures, safety of the public, and the pollutant removal efficiency of the SCM.

Important maintenance procedures:

- The drainage area of the infiltration trench will be carefully managed to reduce the sediment load to the sand filter.
- The water level in the monitoring wells will be recorded once a month and after every storm event greater than 1.5 inches.

The infiltration trench will be inspected **once a quarter and within 24 hours after every storm event greater than 1.5 inches.** Records of operation and maintenance will be kept in a known set location and will be available upon request.

Inspection activities shall be performed as follows. Any problems that are found shall be repaired immediately.

SCM element:	Potential problem:	How to remediate the problem:	
The entire SCM	Trash/debris is present.	Remove the trash/debris.	
The grass filter strip or	Areas of bare soil and/or	Regrade the soil if necessary, to	
other pretreatment area	erosive gullies have formed.	remove the gully, and then plant a	
		ground cover and water until it is	
		established. Provide lime and a	
		one-time fertilizer application.	
	Sediment has accumulated to	Search for the source of the	
	a depth of greater than six	sediment and remedy the problem if	
	inches.	possible. Remove the sediment and	
		dispose of it in a location where it	
		will not cause impacts to streams or	
		the SCM.	
The flow diversion	The structure is clogged.	Unclog the conveyance and dispose	
structure (if applicable)		of any sediment off-site.	
	The structure is damaged.	Make any necessary repairs or	
		replace if damage is too large for	
		repair.	

SCM element:	Potential problem:	How to remediate the problem:	
The trench	Water is ponding on the surface for more than 24 hours after a storm. Grass or other plants are growing on the surface of the trench.	Remove the accumulated sediment from the infiltration system and dispose in a location that will not impact a stream or the SCM. Do not pull the weeds (may pull out media as well). Wipe them with a systemic herbicide such as glyphosate and then return within the week to remove them by hand. (Another option is to pour boiling	
The observation well(s)	Water present more than three days after a storm event.	water on them or steam them.) Clean out any clogged underdrain pipes. Consult an appropriate professional for clogged soil subgrade.	
The emergency overflow berm	Erosion or other signs of damage have occurred at the outlet.	Repair or replace the berm.	
The receiving water	Erosion or other signs of damage have occurred at the outlet.	Repair the damage and improve the flow dissipation structure.	

Permit Numb	er:	
(to be	provided by	City of Wilmington)

I acknowledge and agree by my signature below that I am responsible for the performance of the maintenance procedures listed above. I agree to notify City of Wilmington of any problems with the system or prior to any changes to the system or responsible party.

Project name: SEAHAWK COVE
SCM drainage basin number: 1 OF 1
Print name: BARRY COPPEDGE
Title: MANAGER, SEAHAWK COVE SH, LLC
Address: 305 PETTIGREW DRIVE, WILMINGTON, NC 28412
Phone: 910-367-9782
Signature:
Date: (17/2022
Note: The legally responsible party should not be a homeowners' association unless more than 50% of the lots have been sold and a resident of the subdivision has been named the president.
I, Tracy L. Lave, a Notary Public for the State of Marth Caroline, County of Hew Hanover, do hereby certify that
Marth Caroline, County of Hew Hanover, do hereby certify that
Barry Coppedge personally appeared before me this 17th
day of November, 2022, and acknowledge the due execution of the
forgoing infiltration trench maintenance requirements. Witness my hand and official
seal,
forgoing infiltration trench maintenance requirements. Witness my hand and official seal,

My commission expires_

SEAL