



Engineering 212 Operations Center Drive Wilmington, NC 28412 910 341-7807 910 341-5881 fax wilmingtonne.gov Dial 711 TTY/Voice

### COMPREHENSIVE STORMWATER MANAGEMENT PERMIT

### HIGH DENSITY DEVELOPMENT

### **SECTION 1 – APPROVAL**

Having reviewed the application and all supporting materials, the City of Wilmington has determined that the application is complete and the proposed development meets the requirements of the City of Wilmington's Comprehensive Stormwater Ordinance.

PERMIT HOLDER: Sea Pines Apartments, LLC

PROJECT:

Sea Pines Apartments

ADDRESS: PERMIT #: 1600 St. Andrews Drive.

DATE:

1997062R1 1/15/2016

Therefore, the above referenced site is hereby approved and subject to all conditions set forth in Section 2 of this approval and all applicable provisions of the City of Wilmington Comprehensive Stormwater Management Ordinance.

This permit shall be effective from the date of issuance until 1/15/2026 and shall be subject to the following specified conditions and limitations:

### Section 2 - CONDITIONS

1. This approval is valid only for the stormwater management system as proposed on the approved stormwater management plans dated 1/14/2016 and the plans previously approved by City Stormwater Discharge Permit 1997062. The design data for Pond 2 is noted in the attached supplement. The design data for Pond 1 is as follows:

| • | Drainage area, acres            | 7.55                          |
|---|---------------------------------|-------------------------------|
|   | <ul> <li>Onsite, sf</li> </ul>  | 396,396                       |
| • | Total Impervious Surfaces, sf   | 171,320                       |
| • | Average Design Depth, ft        | 6                             |
| • | TSS Removal Efficiency          | 90%                           |
| • | Permanent Pool Elevation, FMSL  | 35                            |
| • | Permanent Pool Surface Area, sf | 11,600                        |
| • | Permitted Storage Volume, cf    | 16,347 (at temp storage elev) |
| • | Temp Storage Elevation, FMSL    | 36.3                          |
| • | Controlling Örifice             | 2'Ø pipe                      |
| • | Permitted Forebay Volume, cf    | as shown on plans             |
| • | Fountain Horsepower, HP         | N/A '                         |
| • | Receiving Stream/River Bain     | Bernards Creek/Cape Fear      |
| • | Stream Index #                  | 18-80                         |
| • | Classification of Water Body    | "C, SW"                       |
|   |                                 |                               |

2. The project will be limited to the amount and type of built-upon area indicated in Section IV of the Stormwater Management Application Form submitted as part of the approved stormwater permit application package, and per the approved plans.





Engineering 212 Operations Center Drive Wilmington, NC 28412 910 341-7807 910 341-5881 fax wilmingtonnc.gov Dial 711 TTY/Voice

- This permit shall become void unless the facilities are constructed in accordance with the approved stormwater management plans, specifications and supporting documentation, including information provided in the application and supplements.
- 4. The runoff from all built-upon area within any permitted drainage area must be directed into the permitted stormwater control system for that drainage area.
- 5. The permittee shall submit a revised stormwater management application packet to the City of Wilmington and shall have received approval prior to construction, for any modification to the approved plans, including, but not limited to, those listed below:
  - a. Any revision to any item shown on the approved plans, including the stormwater management measures, built-upon area, details, etc.

b. Redesign or addition to the approved amount of built-upon area or to the drainage area.

c. Further subdivision, acquisition, lease or sale of any part of the project area.

d. Filling in, altering, or piping of any vegetative conveyance shown on the approved plan.

e. Construction of any permitted future areas shown on the approved plans.

- 6. A copy of the approved plans and specifications shall be maintained on file by the Permittee.
- 7. During construction, erosion shall be kept to a minimum and any eroded areas of the system will be repaired immediately.
- 8. If the stormwater system was used as an Erosion Control device, it must be restored to design condition prior to operation as a stormwater treatment device, and prior to issuance of any certificate of occupancy for the project.
- 9. All areas must be maintained in a permanently stabilized condition. If vegetated, permanent seeding requirements must follow the guidelines established in the North Carolina Erosion and Sediment Control Planning and Design Manual unless an alternative is specified and approved by the City of Wilmington.
- 10. All applicable operation & maintenance agreements and easements pertaining to each stormwater treatment system shall be referenced on the final plat and recorded with the Register of Deeds upon final plat approval. If no plat is recorded for the site the operation and maintenance agreements and easements shall be recorded with the Register of Deeds so as to appear in the chain of title of all subsequent purchasers under generally accepted searching standards.
- 11. The stormwater management system shall be constructed in its entirety, vegetated and operational for its intended use prior to the construction of any built-upon surface unless prior approval is obtained. City Staff must be notified of any deviation prior to construction of the built-upon surface. Any deviation request shall include justification and must propose an alternative timeline or construction sequence. Notification shall not constitute approval. Any alternative timeline approved by City staff shall become an enforceable component of this permit.





Engineering 212 Operations Center Drive Wilmington, NC 28412 910 341-7807 910 341-5881 fax wilmingtonnc.gov Dial 711 TTY/Voice

12. The permittee shall at all times provide the operation and maintenance necessary to assure the permitted stormwater system functions at optimum efficiency. The approved Operation and Maintenance Agreement must be followed in its entirety and maintenance must occur at the scheduled intervals including, but not limited to:

a. Scheduled inspections (interval noted on the agreement).

b. Sediment removal.

Moving and revegetation of slopes and the vegetated areas.

d. Maintenance of landscape plants, including those within the landscape buffer and on the vegetated shelf.

e. Immediate repair of eroded areas, especially slopes.

- f. Debris removal and unclogging of outlet structure, orifice device, flow spreader, catch basins and/or piping.
- g. Access to the outlet structure must be available at all times.
- 13. Records of inspection, maintenance and repair for the permitted stormwater system must be kept by the permittee for at least 5 years from the date of record and made available upon request to authorized personnel of the City of Wilmington. The records will indicate the date, activity, name of person performing the work and what actions were taken.
- 14. Upon completion of construction, before a Certificate of Occupancy shall be granted, and prior to operation or intended use of this permitted facility, the applicant shall submit to the City of Wilmington as-built plans for all stormwater management facilities. The plans shall show the final design specifications and the field location, type, depth, invert and planted vegetation of all measures, controls and devices, as-installed. A certification shall be submitted, along with all supporting documentation that specifies, under seal that the as-built stormwater measures, controls and devices are in compliance with the approved stormwater management plans. A final inspection by City of Wilmington personnel will be required prior to issuance of a certificate of occupancy or operation of the permitted facility.
- 15. This permit is not transferable except after application and approval by the City of Wilmington. In the event of a change of ownership, name change or change of address the permittee must submit a completed Name/Ownership Change form to the City of Wilmington at least 30 days prior to the change. It shall be signed by all applicable parties, and be accompanied by all required supporting documentation. Submittal of a complete application shall not be construed as an approved application. The application will be reviewed on its own merits by the City of Wilmington and may or may not be approved. The project must be in compliance with the terms of this permit in order for the transfer request to be considered. The permittee is responsible for compliance with all permit conditions until such time as the City of Wilmington approves the transfer request. Neither the sale of the project nor the conveyance of common area to a third party should be considered as an approved transfer of the permit.
- 16. Failure to abide by the conditions and limitations contained in this permit may subject the Permittee to enforcement action by the City of Wilmington, in accordance with Sections 18-52 and 18-53 and any other applicable section of the Land Development Code.





Engineering 212 Operations Center Drive Wilmington, NC 28412 910 341-7807 910 341-5881 fax wilmingtonnc.gov Dial 711 TTY/Voice

- 17. The City of Wilmington may notify the permittee when the permitted site does not meet one or more of the minimum requirements of the permit. Within the time frame specified in the notice, the permittee shall submit a written time schedule to the City of Wilmington for modifying the site to meet minimum requirements. The permittee shall provide copies of revised plans and certification in writing to the City of Wilmington that the changes have been made.
- 18. The issuance of this permit does not preclude the Permittee from complying with any and all statutes, rules, regulations, or ordinances, which may be imposed by other government agencies (local, state, and federal) having jurisdiction.
- 19. In the event that the facilities fail to perform satisfactorily, including the creation of nuisance conditions, the Permittee shall take immediate corrective action, including those as may be required by the City of Wilmington, such as the construction of additional or replacement stormwater management systems.
- 20. The permittee grants City of Wilmington Staff permission to enter the property during normal business hours for the purpose of inspecting all components of the permitted stormwater management facility.
- 21. The permit issued shall continue in force and effect until revoked or terminated by the City of Wilmington. The permit may be modified, revoked and reissued or terminated for cause. The filing of a request for a permit modification, revocation and re-issuance or termination does not stay any permit condition.
- 22. The approved stormwater management plans and all documentation submitted as part of the approved stormwater management permit application package for this project are incorporated by reference and are enforceable parts of the permit.
- The permittee shall submit a renewal request with all required forms and documentation at least 180 days prior to the expiration date of this permit.
- 24. If any one or more of the conditions of this permit is found to be unenforceable or otherwise invalidated, all remaining conditions shall remain in full effect.

Stormwater Management Permit issued this the 15th day of January, 2016

for Sterling Cheatham, City Manager

City of Wilmington





Public Services
Engineering
212 Operations Center Dr
Wilmington, NC 28412
910 341-7807
910 341-5881 fax
wilmingtonne.gov
Dial 711 TTY/Voice

## STORMWATER MANAGEMENT PERMIT APPLICATION FORM (Form SWP 2.2)

# I. GENERAL INFORMATION

| 1.  | Project Name (subdivision, facility, or establishment name - should be consistent with project name on plans, specifications, letters, operation and maintenance agreements, etc.):   |
|-----|---|
|     | Sea Pines Apartments  |
| 2.  | Location of Project (street address): 1600 Saint Andrews Drive  |
|     | City: Wilmington County: New Hanover Zip: 28403   |
| 3.  | Directions to project (from nearest major intersection):  South West Quadrant of 17th Street and Saint Andrews Drive intersection   |
| II. | PERMIT INFORMATION  |
| 1.  | Specify the type of project (check one): Low Density (High Density)  Drains to an Offsite Stormwater System Drainage Plan Other  If the project drains to an Offsite System, list the Stormwater Permit Number(s):  |
|     | City of Wilmington: State – NCDENR/DWQ:   |
| 2.  | Is the project currently covered (whole or in part) by an existing City or State (NCDENR/DWQ) Stormwater Permit? (Yes) No If yes, list all applicable Stormwater Permit Numbers:  |
|     | City of Wilmington: State – NCDENR/DWQ: SW8 970733  |
| 3.  | Additional Project Permit Requirements (check all applicable):  CAMA Major  Sedimentation/Erosion Control  NPDES Industrial Stormwater  404/401 Permit: Proposed Impacts:  If any of these permits have already been acquired please provide the Project Name, Project/Permit Number, issue date and the type of each permit: |



## **III. CONTACT INFORMATION**

| 1. | Print Applicant / Signing Official's name and title (specifically the developer, property owner, lessee, designated government official, individual, etc. who owns the project):   |  |  |
|----|--|--|--|
|    | Applicant / Organization: Sea Pines Apartments, LLC  |  |  |
|    | Signing Official & Title: Mark Maynard   |  |  |
|    | a. Contact information for Applicant / Signing Official:   |  |  |
|    | Street Address: 10 S Cardinal Dr.  |  |  |
|    | City: Wilmington State: NC Zip: 28403  |  |  |
|    | Phone: 910 251 5030 Fax: Email: markm@tributecompanies.com   |  |  |
|    | Mailing Address (if different than physical address):  |  |  |
|    | City:State:Zip:  |  |  |
|    | b. Please check the appropriate box. The applicant listed above is:  |  |  |
| 2. | The property owner (Skip to item 3)  Lessee* (Attach a copy of the lease agreement and complete items 2 and 2a below)  Purchaser* (Attach a copy of the pending sales agreement and complete items 2 and 2a below)  Developer* (Complete items 2 and 2a below.)  Print Property Owner's name and title below, if you are the lessee, purchaser, or developer. (This is |  |  |
|    | the person who owns the property that the project is on.)  |  |  |
|    | Property Owner / Organization: Sea Pines Apartments, LLC   |  |  |
|    | Signing Official & Title: Mark Maynard Manager   |  |  |
|    | a. Contact information for Property Owner:   |  |  |
|    | Street Address: 10 S Cardinal Drive  |  |  |
|    | City: Wilmington State: NC Zip: 28403  |  |  |
|    | Phone: 910 251-5030 Fax:Email: markm@tributecompanies.com  |  |  |
|    | Mailing Address (if different than physical address):  |  |  |
|    | City:        Zip:  |  |  |
| 3. | (Optional) Print the name and title of another contact such as the project's construction supervisor or another person who can answer questions about the project:   |  |  |
|    | Other Contact Person / Organization:   |  |  |
|    | Signing Official & Title:  |  |  |



|     | a. Contact information for perso  |                            |                           |                    |
|-----|---|----------------------------|---------------------------|--------------------|
|     | Street Address:   |                            |                           | ,                  |
|     | City:   |                            |                           |                    |
|     | Phone:Fax:  | Email                      | :                         |                    |
|     | Mailing Address (if different than  | physical address): _       |                           |                    |
|     | City:   | State                      | :Zip:                     |                    |
| IV. | . PROJECT INFORMATION   |                            |                           |                    |
| 1.  | In the space provided below, briefly s  | summarize how the s        | tormwater runoff will b   | e treated.         |
|     | Runoff from the new development   |                            |                           |                    |
|     | basin east edge of the developmen   |                            |                           |                    |
|     |   |                            | •                         |                    |
|     | comply with state and city stormy   | vater regulations resp     | pectively.                |                    |
| 2.  | Total Property Area: <u>537,501</u> squ   | uare feet                  |                           |                    |
| 3.  | Total Coastal Wetlands Area: 0  | square feet                |                           |                    |
| 4.  | Total Surface Water Area: 28,069  | square feet                |                           |                    |
| 5.  | Total Property Area (2) – Total Coast<br>Project Area: 509,432 square fe          |                            | – Total Surface Wate      | r Area (4) = Total |
| 6.  | Existing Impervious Surface within Pr   | operty Area: <u>164,26</u> | 0square feet              |                    |
| 7.  | Existing Impervious Surface to be Re  | moved/Demolished:          | 5,363 square fe           | et                 |
| 8.  | Existing Impervious Surface to Rema   | in: <u>158,897</u> so      | uare feet                 |                    |
| 9.  | Total Onsite (within property boundar   | y) Newly Constructe        | d Impervious Surface      | (in square feet):  |
|     | Buildings/Lots  | 17,696 + 4402 =            | 22,098                    | 7                  |
|     | Impervious Pavement   | 37,605 + 1786 =            | 39,391                    |                    |
| ,   | Pervious Pavement (adj. total, with   | % credit applied)          |                           |                    |
|     |   | 7,112 + 5,198 =            | 12,310                    |                    |
|     | Pervious Sidewalks (adj. total, with  | % credit applied)          |                           |                    |
|     | Other (describe)  |                            |                           | _                  |
|     | Future Development  |                            | 1,037                     |                    |
|     | Total Onsite Newly Constructed Imper  | vious Surface              | 62,413+1037=74,836        | _                  |
| 10. | . Total Onsite Impervious Surface<br>(Existing Impervious Surface to remain + Ons | ita Nawly Constructed Im   | nervious Surface) - 233.7 | /33 square feet    |

11. Project percent of impervious area: (Total Onsite Impervious Surface / Total Project Area) x100 = 45.9%



12. Total Offsite Newly Constructed Impervious Area (improvements made outside of property boundary, in square feet):

| Impervious Pavemer                                 |                   |                   |  |
|--|-------------------|-------------------|--|
| Pervious Pavement                                  |                   |                   |  |
| Impervious Sidewalk                                |                   |                   |  |
| Pervious Sidewalks                                 | (adj. total, with | % credit applied) |  |
| Other (describe)                                   |                   |                   |  |
| Total Offsite Newly Constructed Impervious Surface |                   |                   |  |

| 13. Total Newly Constructed Impervious Surface                  |        |             |
|---|--------|-------------|
| (Total Onsite + Offsite Newly Constructed Impervious Surface) = | 74,836 | square feet |

14. Complete the following information for each Stormwater BMP drainage area. If there are more than three drainage areas in the project, attach an additional sheet with the information for each area provided in the same format as below. Low Density projects may omit this section and skip to Section V.

| Basin Information                  | EX. WET POND<br>BMP # 1 | PROP. I. BASIN<br>BMP # 2 | BMP# |
|------------------------------------|-------------------------|---------------------------|------|
| Receiving Stream Name              | Barnard's Creek         | Barnard's Creek           |      |
| Receiving Stream Index Number      | 18-80                   | 18-80                     |      |
| Stream Classification              | C-SW                    | C-SW                      |      |
| Total Drainage Area (sf)           | 340,204                 | 100,188                   |      |
| On-Site Drainage Area (sf)         | 340,204                 | 100,188                   |      |
| Off-Site Drainage Area (sf)        |                         |                           |      |
| Total Impervious Area (sf)         | 171320                  | 62,413                    |      |
| Buildings/Lots (sf)                | 9,088                   | 17,696                    |      |
| Impervious Pavement (sf)           | 1,786                   | 37,605                    |      |
| Pervious Pavement (sf)             |                         |                           |      |
| Impervious Sidewalks (sf)          | 512                     | 7,112                     |      |
| Pervious Sidewalks (sf)            |                         |                           |      |
| Other (sf) EX. TO BE REMOVED       | -5,363-                 |                           |      |
| Future Development (sf)            | 1,037                   |                           |      |
| Existing Impervious to remain (sf) | 164,260 1588            | 97                        |      |
| Offsite (sf)                       |                         |                           |      |
| Percent Impervious Area (%)        | 48.3                    | 62.3                      |      |

| 15. | How wa | as the | off-site | impervious | s area | listed | above | determined? | ' Provide | document | ation: |
|-----|--------|--------|----------|------------|--------|--------|-------|-------------|-----------|----------|--------|
|     |        |        |          |            |        |        |       |             |           |          |        |



### V. SUBMITTAL REQUIREMENTS

- Supplemental and Operation & Maintenance Forms One applicable City of Wilmington Stormwater BMP supplement form and checklist must be submitted for each BMP specified for this project. One applicable proposed operation and maintenance (O&M) form must be submitted for each type of stormwater BMP. Once approved, the operation and maintenance forms must be referenced on the final plat and recorded with the register of deeds office.
- 2. Deed Restrictions and Restrictive Covenants For all subdivisions, outparcels, and future development, the appropriate property restrictions and protective covenants are required to be recorded prior to the sale of any lot. Due to variability in lot sizes or the proposed BUA allocations, a table listing each lot number, lot size, and the allowable built-upon area must be provided as an attachment to the completed and notarized deed restriction form. The appropriate deed restrictions and protective covenants forms can be downloaded at the link listed in section V (3). Download the latest versions for each submittal.

In instances where the applicant is different than the property owner, it is the responsibility of the property owner to sign the deed restrictions and protective covenants form while the applicant is responsible for ensuring that the deed restrictions are recorded.

By the notarized signature(s) below, the permit holder(s) certify that the recorded property restrictions and protective covenants for this project, if required, shall include all the items required in the permit and listed on the forms available on the website, that the covenants will be binding on all parties and persons claiming under them, that they will run with the land, that the required covenants cannot be changed or deleted without concurrence from the City of Wilmington, and that they will be recorded prior to the sale of any lot.

3. Only complete application packages will be accepted and reviewed by the City. A complete package includes all of the items listed on the City Engineering Plan Review Checklist, including the fee. Copies of the Engineering Plan Review Checklist, all Forms, Deed Restrictions as well as detailed instructions on how to complete this application form may be downloaded from:

http://www.wilmingtonnc.gov/PublicServices/Engineering/PlanReview/StormwaterPermits.aspx

The complete application package should be submitted to the following address:

City of Wilmington – Engineering Plan Review Section 212 Operations Center Dr Wilmington, NC 28412



## VI. CONSULTANT INFORMATION AND AUTHORIZATION

| 1                     | . Applicant: Complete this section if you wish to designate authority to another individual and/or firm<br>(such as a consulting engineer and /or firm) so that they may provide information on your behalf for<br>this project (such as addressing requests for additional information).   |
|-----------------------|---|
|                       | Consulting Engineer: James H. Fentress Jr.  |
|                       | Consulting Firm: Stroud Engineering, P.A.   |
|                       | a. Contact information for consultant listed above:   |
|                       | Mailing Address: 102 Suite D Cinema Dr.   |
|                       | City: Wilmington State: NC Zip: 28403   |
|                       | Phone: 910 815-0775 Fax: 910 815-0593 Email: jfentress@stroudengineer.com   |
| _                     |   |
| V                     | /II. PROPERTY OWNER AUTHORIZATION (If Section III(2) has been filled out, complete this section)  |
| p<br>li.<br>p         | (print or type name of person listed in Contact Information, item 2) Mark Maynard, certify that I will the property identified in this permit application, and thus give permission to (print or type name of erson listed in Contact Information, item 1) James Fentress with (print or type name of organization sted in Contact Information, item 1) Stroud Engineering to develop the project as currently proposed. A copy of the lease agreement or pending property sales contract has been provided with the submittal, which indicates the party responsible for the operation and maintenance of the tormwater system.  |
| d<br>V<br>r<br>C<br>V | esignated agent (entity listed in Contact Information, item 1) dissolves their company and/or cancels or lefaults on their lease agreement, or pending sale, responsibility for compliance with the City of Vilmington Stormwater Permit reverts back to me, the property owner. As the property owner, it is my esponsibility to notify the City of Wilmington immediately and submit a completed Name/Ownership Change Form within 30 days; otherwise I will be operating a stormwater treatment facility without a alid permit. I understand that the operation of a stormwater treatment facility without a valid permit is a iolation of the City of Wilmington Municipal Code of Ordinances and may result in appropriate enforcement including the assessment of civil penalties.  Signature:  |
|                       | KELLIE E. NORRIS  Notary Public  North Carolina  New Hanover County  New Hanover County |



| and acknowledge the due execution  **Ellin E: 11                      | of the application for a stormwater permit. Witness my hand and official seal,   |
|---|--|
| My commission expires: 3/5/2  |  |
| VIII. APPLICANT'S CERTIFIC  | CATION   |
| that the information included on that the project will be constructed | Contact Information, item 1) Mark Maynard certify this permit application form is, to the best of my knowledge, correct and in conformance with the approved plans, that the required deed ants will be recorded, and that the proposed project complies with the requirements of the applicable stormwater rules under. |
| SEAL  | Signature:   |
| KELLIE E. NORRIS  Notary Public  North Carolina                       | Date: Santha   |
| New Hanover County  | I, <u>Kellic E. Norris</u> , a Notary Public for the State of <u>NC</u> , County of <u>New Hano</u> , do   |
|   | hereby certify that Mark Maynard   |
| •   | personally appeared before me this day of <u>August 7</u> , <u>2015</u> ,  |
|   | and acknowledge the due execution of the application for a stormwater  |
| permit. Witness my hand and officia                                   | al seal,   |
| Bullie E: 7   | J  |
| My commission expires:35  | /2019  |
|   |  |

| Permit Number:                         |
|--|
| (to be provided by City of Wilmington) |
| BMP Drainage Basin #:                  |


## Wet Detention Basin Operation and Maintenance Agreement

I will keep a maintenance record on this BMP. This maintenance record will be kept in a log in a known set location. Any deficient BMP elements noted in the inspection will be corrected, repaired or replaced immediately. These deficiencies can affect the integrity of structures, safety of the public, and the removal efficiency of the BMP.

The wet detention basin system is defined as the wet detention basin, pretreatment including forebays and the vegetated filter if one is provided.

| This system (check one): $\square$ does $\square$ does not          | incorporate a vegetated filter at the outlet. |
|---|---|
| This system ( <i>check one</i> ): $\square$ does $\bowtie$ does not | incorporate pretreatment other than a forebay |

Important maintenance procedures:



Immediately after the wet detention basin is established, the plants on the vegetated shelf and perimeter of the basin should be watered twice weekly if needed, until the plants become established (commonly six weeks).

No portion of the wet detention pond should be fertilized after the first initial fertilization that is required to establish the plants on the vegetated shelf. Stable groundcover should be maintained in the drainage area to reduce the sediment load to the wet detention basin.

If the basin must be drained for an emergency or to perform maintenance, the flushing of sediment through the emergency drain should be minimized to the maximum extent practical.

Once a year, a dam safety expert should inspect the embankment.

After the wet detention pond is established, it should be inspected **once a month and within 24 hours after every storm event greater than 1.5 inches**. Records of operation and maintenance should be kept in a known set location and must be available upon request. Inspection activities shall be performed as follows. Any problems that are found shall be repaired immediately.

| BMP element:                               | Potential problem:                                     | How I will remediate the problem:   |
|--|--|---|
| The entire BMP                             | Trash/debris is present.                               | Remove the trash/debris.  |
| The side slopes of the wet detention basin | Areas of bare soil and/or erosive gullies have formed. | Regrade the soil if necessary to remove the gully, and then plant a ground cover and water until it is established. Provide lime and a one-time fertilizer application. |
|  | Vegetation is too short or too long.                   | Maintain vegetation at a height of approximately six inches.  |

| BMP element:                    | Potential problem:             | How I will remediate the problem:                                       |
|---------------------------------|--------------------------------|---|
| The inlet device: pipe or swale | The pipe is clogged.           | Unclog the pipe. Dispose of the sediment off-site.                      |
|                                 | The pipe is cracked or         | Replace the pipe.   |
|                                 | otherwise damaged.             |   |
|                                 | Erosion is occurring in the    | Regrade the swale if necessary to                                       |
|                                 | swale.                         | smooth it over and provide erosion                                      |
|                                 |                                | control devices such as reinforced                                      |
|                                 |                                | turf matting or riprap to avoid   |
|                                 |                                | future problems with erosion.   |
| The forebay                     | Sediment has accumulated to    | Search for the source of the  |
|                                 | a depth greater than the       | sediment and remedy the problem if                                      |
|                                 | original design depth for      | possible. Remove the sediment and                                       |
|                                 | sediment storage.              | dispose of it in a location where it                                    |
|                                 |                                | will not cause impacts to streams or                                    |
|                                 | 77                             | the BMP.  |
| r                               | Erosion has occurred.          | Provide additional erosion  |
| •                               |                                | protection such as reinforced turf                                      |
|                                 |                                | matting or riprap if needed to  |
|                                 | Mode are present               | prevent future erosion problems.  |
|                                 | Weeds are present.             | Remove the weeds, preferably by   |
| •                               |                                | hand. If pesticide is used, wipe it on the plants rather than spraying. |
| The vegetated shelf             | Best professional practices    |   |
| The vegetated shen              | show that pruning is needed    | Prune according to best professional practices                          |
|                                 | to maintain optimal plant      | practices   |
|                                 | health.                        |   |
| ,                               | The plant community and        | Restore plant vegetation to   |
|                                 | coverage is significantly      | approved condition. If landscape  |
|                                 | (>25%) different from          | plan needs to be adjusted to specify                                    |
|                                 | approved landscape plan.       | vegetation more appropriate for site                                    |
| •                               |                                | conditions, contact City Stormwater                                     |
|                                 |                                | or Engineering Staff.   |
|                                 | Cattails or other invasive     | Remove all invasives by physical  |
|                                 | plants cover >25% of the veg't | removal or by wiping them with  |
|                                 | shelf. A monculture of plants  | pesticide (do not spray) – consult a                                    |
|                                 | must be avoided)               | professional.   |
|                                 | Plants are dead, diseased or   | Determine the source of the   |
|                                 | dying.                         | problem: soils, hydrology, disease,                                     |
|                                 |                                | etc. Remedy the problem and   |
|                                 |                                | replace plants. Provide a one-time                                      |
|                                 |                                | fertilizer application to establish the                                 |
|                                 |                                | ground cover if a soil test indicates                                   |
|                                 |                                | it is necessary.  |
| The main treatment area         | Sediment has accumulated to    | Search for the source of the  |
|                                 | a depth greater than the       | sediment and remedy the problem if                                      |
|                                 | original design sediment       | possible. Remove the sediment and                                       |
|                                 | storage depth.                 | dispose of it in a location where it                                    |
|                                 |                                | will not cause impacts to streams or                                    |
|                                 |                                | the BMP.  |

| BMP element:            | Potential problem:             | How I will remediate the problem:    |
|-------------------------|--------------------------------|--------------------------------------|
| The main treatment area | Algal growth covers over       | Consult a professional to remove     |
| (continued)             | 25% of the area.               | and control the algal growth.        |
|                         | Cattails or other invasive     | Remove all invasives by physical     |
|                         | plants cover >25% of the veg't | removal or by wiping them with       |
|                         | shelf. A monculture of plants  | pesticide (do not spray) – consult a |
|                         | must be avoided)               | professional.                        |
| The embankment          | Shrubs have started to grow    | Remove shrubs immediately.           |
| !                       | on the embankment.             |                                      |
|                         | Evidence of muskrat or         | Use traps to remove muskrats and     |
|                         | beaver activity is present.    | consult a professional to remove     |
|                         |                                | beavers.                             |
|                         | A tree has started to grow on  | Consult a dam safety specialist to   |
|                         | the embankment.                | remove the tree.                     |
|                         | An annual inspection by an     | Make all needed repairs.             |
|                         | appropriate professional       |                                      |
|                         | shows that the embankment      |                                      |
|                         | needs repair. (if applicable)  |                                      |
| The outlet device       | Clogging has occurred.         | Clean out the outlet device. Dispose |
|                         |                                | of the sediment off-site.            |
|                         | The outlet device is damaged   | Repair or replace the outlet device. |
| The receiving water     | Erosion or other signs of      | Contact the local NC Division of     |
| , ,                     | damage have occurred at the    | Water Quality Regional Office, or    |
|                         | outlet.                        | the 401 Oversight Unit at 919-733-   |
|                         |                                | 1786.                                |


The measuring device used to determine the sediment elevation shall be such that it will give an accurate depth reading and not readily penetrate into accumulated sediments.

When the permanent pool depth reads <u>5.25</u> feet in the main pond, the sediment shall be removed.

When the permanent pool depth reads <u>3</u> feet in the forebay, the sediment shall be removed.

### **BASIN DIAGRAM**

(fill in the blanks)



| Permit Num | ber:        |            |           |
|------------|-------------|------------|-----------|
| (to be     | provided by | City of Wi | lmington) |

I acknowledge and agree by my signature below that I am responsible for the performance of the maintenance procedures listed above. I agree to notify the City of Wilmington of any problems with the system or prior to any changes to the system or responsible party.

| Project name: Sea Pines Apartments   |
|--|
| BMP drainage basin number: 1 EX. WET DETENTION POND  |
|  |
| Print name: Mark Maynard   |
| Title: Manager   |
| Address: 10 S Cardinial Dr.  |
| Phone: 910 251-5030  |
| Signature:   |
| Date:  |
| Note: The legally responsible party should not be a homeowners association unless more than 50% of the lots have been sold and a resident of the subdivision has been named the president. |
| I, Kellie E. Norris , a Notary Public for the State of   |
| NC County of New Hanover, do hereby certify that   |
| Mark Maynard personally appeared before me this 7  |
| day of August, 2015, and acknowledge the due execution of the  |
| forgoing infiltration basin maintenance requirements. Witness my hand and official seal,   |
| KELLIE E. NORRIS  Notary Public  North Carolina  New Handver County  |
| SEAL   |
| My commission expires 3/5/9/019  |

Page 4 of 4

| Permit No. |                        |
|------------|------------------------|
|            | tto be provided by DM# |

## STORMWATER MANAGEMENT PERMIT APPLICATION FORM 401 CERTIFICATION APPLICATION FORM

### **INFILTRATION BASIN SUPPLEMENT**

This form must be filled out, printed and submitted.


The Required Items Checklist (Part III) must be printed, filled out and submitted along with all of the required information.

| Project Name         | 38 Average (San Apartments | CONTRACTOR OF THE PROPERTY OF THE PARTY OF T |
|----------------------|----------------------------|--|
| Contact Person       | Mark Maynard Jr.           | ',   |
| Phone Number         | 910 612 3633               |  |
| Date                 | 10/20/2015                 |  |
| Drainage Area Number | 2                          |  |



| Phone Number   | 910 612 3633               |                        |               |
|--|----------------------------|------------------------|---------------|
| Date   | 10/20/2015                 |                        |               |
| Drainage Area Number   | 2                          |                        | :             |
| I was a second and |                            |                        |               |
| II. DESIGN INFORMATION   |                            |                        |               |
| Site Characteristics   |                            |                        |               |
| Drainage area  | 100,352.00 ft <sup>2</sup> |                        |               |
| Impervious area  | 62,413.00 ft <sup>2</sup>  |                        |               |
| Percent impervious   | 0.62 %                     |                        |               |
| Design rainfall depth  | 1.50in                     |                        | 115(1         |
| Peak Flow Calculations   |                            |                        | NOV - 2 2015  |
| 1-yr, 24-hr rainfall depth   | 3.83 in                    |                        |               |
| 1-yr, 24-hr intensity  | 0.16 in/hr                 |                        |               |
| Pre-development 1-yr, 24-hr discharge  | 1.76 ft <sup>3</sup> /sec  |                        | ENGINEEDING   |
| Post-development 1-yr, 24-hr discharge   | 5.55 ft <sup>3</sup> /sec  |                        | I ENGINEERING |
| Pre/Post 1-yr, 24-hr peak flow control   | 3.79 ft <sup>3</sup> /sec  |                        |               |
| Storage Volume: Non-SA Waters  |                            |                        |               |
| Minimum design volume required   | 7,649.00 ft <sup>3</sup>   |                        |               |
| Design volume provided   | 8,206.00 ft <sup>3</sup>   | OK for non-SA waters   |               |
| * '  | 0,220.00                   | Off for Horizon Waters |               |
| Storage Volume: SA Waters  | <u> </u>                   |                        |               |
| 1.5" runoff volume   | 7649.00 ft <sup>3</sup>    |                        |               |
| Pre-development 1-yr, 24-hr runoff volume  | 1,601.00 ft <sup>3</sup>   |                        |               |
| Post-development 1-yr, 24-hr runoff volume   | 19,530.00 ft <sup>3</sup>  |                        |               |
| Minimum required volume  | 17929.00 ft <sup>3</sup>   |                        |               |
| Volume provided  | 46,086.00 ft <sup>3</sup>  | OK                     | •             |
| Soils Report Summary   |                            |                        |               |
| Soil type  | LYNNHAVEN                  |                        |               |
| Infiltration rate  | 2.62 in/hr                 | _                      |               |
| SHWT elevation   | 37.00 fms                  |                        |               |
| Basin Design Parameters  |                            |                        |               |
| Drawdown time  | 0.20 days                  | ОК                     |               |
| Basin side slopes  | 3.00 :1                    | OK                     |               |
| Basin bottom elevation   | 39.00 fmsl                 | OK                     |               |
| Storage elevation  | 40,00 fms                  |                        |               |
| Storage Surface Area   | 9,331.00 ft <sup>2</sup>   |                        |               |
| Top elevation  | 43.00 fmsl                 |                        |               |
| Basin Bottom Dimensions  | <u></u>                    |                        |               |
| Basin length   | 194.00 ft                  |                        |               |
| Basin width  | 43.00 ft                   |                        |               |
| Datin Willi  | 43.00 π                    |                        |               |

| Bottom Surface Area                        | 7,080.00     | _ft²       |           |
|--|--------------|------------|-----------|
| Additional Information                     |              |            |           |
| Maximum runoff to each inlet to the basin? | 1.00         | ac-in      | OK        |
| Length of vegetative filter for overflow   | 30.00        | -<br>ft    | OK        |
| Distance to structure                      | 500.00       | -ft        | OK        |
| Distance from surface waters               | 50.00        | ft         | OK        |
| Distance from water supply well(s)         | 100.00       | ft         | OK        |
| Separation from impervious soil layer      | 2.00         | ft         | OK        |
| Naturally occuring soil above shwt         | 2.00         | ft         | OK        |
| Bottom covered with 4-in of clean sand?    | Y            | (Y or N)   | OK        |
| Proposed drainage easement provided?       | Y            | (Y or N)   | OK        |
| Capures all runoff at ultimate build-out?  | Υ            | (Y or N)   | OK        |
| Bypass provided for larger storms?         | . Y          | (Y or N)   | OK .      |
| Pretreatment device provided               | SEDIMENT BAS | IN IN PARK | NG ISLAND |
|  |              |            |           |



## filtration Basin Operation and Maintenance Agreement

I will keep a maintenance record on this BMP. This maintenance record will be kept in a log in a known set location. Any deficient BMP elements noted in the inspection will be corrected, repaired or replaced immediately. These deficiencies can affect the integrity of structures, safety of the public, and the removal efficiency of the BMP.

Important maintenance procedures:

- The drainage area will be carefully managed to reduce the sediment load to the infiltration basin.
- Immediately after the infiltration basin is established, the vegetation will be watered twice weekly if needed until the plants become established (commonly six weeks).
- No portion of the infiltration basin will be fertilized after the initial fertilization that is required to establish the vegetation.
- The vegetation in and around the basin will be maintained at a height of approximately six inches.

After the infiltration basin is established, it will be inspected **once a quarter and within 24 hours after every storm event greater than 1.5 inches**. Records of operation and maintenance will be kept in a known set location and will be available upon request.

Inspection activities shall be performed as follows. Any problems that are found shall be repaired immediately.

| BMP element:              | Potential problem:           | How I will remediate the problem:  |
|---------------------------|------------------------------|------------------------------------|
| The entire BMP            | Trash/debris is present.     | Remove the trash/debris.           |
| The perimeter of the      | Areas of bare soil and/or    | Regrade the soil if necessary to   |
| infiltration basin        | erosive gullies have formed. | remove the gully, and then plant a |
|                           | ·                            | ground cover and water until it is |
|                           |                              | established. Provide lime and a    |
|                           |                              | one-time fertilizer application.   |
| The inlet device: pipe or | The pipe is clogged (if      | Unclog the pipe. Dispose of the    |
| swale                     | applicable).                 | sediment off-site.                 |
|                           | The pipe is cracked or       | Replace the pipe.                  |
|                           | otherwise damaged (if        |                                    |
|                           | applicable).                 |                                    |
|                           | Erosion is occurring in the  | Regrade the swale if necessary to  |
|                           | swale (if applicable).       | smooth it over and provide erosion |
|                           |                              | control devices such as reinforced |
|                           |                              | turf matting or riprap to avoid    |
|                           |                              | future problems with erosion.      |

| BMP element:            | Potential problem:  | How I will remediate the problem:                              |
|-------------------------|---|--|
| The forebay             | Sediment has accumulated  | Search for the source of the                                   |
|                         | and reduced the depth to 75%  | sediment and remedy the problem if                             |
|                         | of the original design depth.   | possible. Remove the sediment and                              |
|                         |   | dispose of it in a location where it                           |
|                         |   | will not cause impacts to streams or                           |
|                         |   | the BMP.   |
|                         | Erosion has occurred or   | Provide additional erosion                                     |
|                         | riprap is displaced.  | protection such as reinforced turf                             |
|                         |   | matting or riprap if needed to                                 |
| İ                       |   | prevent future erosion problems.                               |
|                         | Weeds are present.  | Remove the weeds, preferably by                                |
|                         |   | hand. If pesticides are used, wipe                             |
|                         |   | them on the plants rather than                                 |
|                         |   | spraying.  |
| The main treatment area | A visible layer of sediment   | Search for the source of the                                   |
|                         | has accumulated.  | sediment and remedy the problem if                             |
|                         |   | possible. Remove the sediment and                              |
|                         |   | dispose of it in a location where it                           |
|                         |   | will not cause impacts to streams or                           |
|                         |   | the BMP. Replace any media that                                |
|                         |   | was removed in the process.                                    |
|                         |   | Revegetate disturbed areas                                     |
|                         | X1X   | immediately.   |
|                         | Water is standing more than   | Replace the top few inches of filter                           |
|                         | 5 days after a storm event.   | media and see if this corrects the                             |
|                         | ·   | standing water problem. If so,                                 |
|                         |   | revegetate immediately. If not,                                |
|                         |   | consult an appropriate professional                            |
|                         | YAY I - I - | for a more extensive repair.                                   |
|                         | Weeds and noxious plants are  | Remove the plants by hand or by                                |
|                         | growing in the main treatment area.   | wiping them with pesticide (do not                             |
| The embankment          | Shrubs or trees have started  | spray).  Remove shrubs or trees                                |
| THE EIRDANKIIIER        |   |  |
|                         | to grow on the embankment.  | immediately.   |
|                         | An annual inspection by an appropriate professional   | Make all needed repairs.                                       |
|                         | shows that the embankment   |  |
|                         | needs repair.   |  |
| The outlet device       | Clogging has occurred.  | Clean out the outlet device Dienose                            |
| THE OWNER WEATER        | Crogging has occurred.  | Clean out the outlet device. Dispose of the sediment off-site. |
|                         | The outlet device is damaged  | Repair or replace the outlet device.                           |
| The receiving water     | Erosion or other signs of   | Contact the NC Division of Water                               |
| THE ICCCIVILIE WATER    | damage have occurred at the   | Quality 401 Oversight Unit at 919-                             |
|                         | outlet.   | 733-1786.  |
|                         | Outil.  | 700-1700,  |

| Permit Number: |               |                |
|----------------|---------------|----------------|
| (to be pro     | vided by City | of Wilmington) |

I acknowledge and agree by my signature below that I am responsible for the performance of the maintenance procedures listed above. I agree to notify the City of Wilmington of any problems with the system or prior to any changes to the system or responsible party.

| Project name: Sea Pines Apartments   |
|--|
| BMP drainage basin number: 2   |
|  |
| Print name: Mark Maynard   |
| Title: Manager   |
| Address: 10 S Cardinial Dr.  |
| Phone: 910 251-5030  |
| Signature:   |
| Date:  |
| Note: The legally responsible party should not be a homeowners association unless more than 50% of the lots have been sold and a resident of the subdivision has been named the president. |
| I, Kellie E. Novris, a Notary Public for the State of  |
| NC , County of New Hanover, do hereby certify that   |
| Mark Maynard personally appeared before me this 7  |
| day of August, 2015, and acknowledge the due execution of the  |
| forgoing infiltration basin maintenance requirements. Witness my hand and official seal,   |
| KELLIE E. NORRIS  Notary Public  North Carolina  New Hanover County  |
| SEAL   |
| My commission expires 3/5/2019   |